PROJECT REFERENCE NO.	SHEET NO.
I-2513AA/AB	E-1D

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA PROFESSIONAL SEAL 055078 ENGINEER NATHAN P DOMINGUEZ

DocuSigned by: Nathan Dominguez

01/04/2024

TABLE "C" (CONTINUED) 6 JUNCTION BOX AND FORMED OPENINGS SUMMARY

CONTROL SYSTEM "X"														GPS LOCATION 7
			TYPE, PAY ITEM & SIZE											
			IN GROUND			LIGHT STANDARD			HIGH MAST			CONTROL SYSTEM	FORMED OPENING	FORMED OPENING	
SHEET	LABEL	LOCATION AND OFFSET	IG18 18"X12"	IG30 30"X17"	IG36 36"X24"	LS18 18"X12"	LS30 30"X17"	LS36 36"X24"	HM18 18"X12"	HM30 30"X17"	HM36 36"X24"	CS36 36"X24"	FO12 12"X10"	FO18 18"X12"	LAT/LONG
E-5	X-25-4JB	5' FROM LIGHT STANDARD SA X-25-4				X									
E-5	X-26-4JB	5' FROM LIGHT STANDARD SA X-26-4				X									
E-5	X-27-4JB	5' FROM LIGHT STANDARD SA X-27-4				X									
E-4	X-28-2JB	5' FROM LIGHT STANDARD SA X-28-2				X									
E-4	X-29-2JB	5' FROM LIGHT STANDARD SA X-29-2				X									
E-5	X-30-2JB	5' FROM LIGHT STANDARD SA X-30-2				X									
E-4	X-31-2JB	5' FROM LIGHT STANDARD SA X-31-2				X									
E-4	X-32-2JB	5' FROM LIGHT STANDARD SA X-32-2				X									
E-5	X-33-2JB	5' FROM LIGHT STANDARD SA X-33-2				X									
E-5	X-34-2JB	5' FROM LIGHT STANDARD SA X-34-2				X									
E-5	X-35-2JB	5' FROM LIGHT STANDARD SA X-35-2				X									
E-4	X-36-3JB	5' FROM LIGHT STANDARD SA X-36-3				X									
E-4	X-37-3JB	5' FROM LIGHT STANDARD SA X-37-3				X									
E-5	X-38-3JB	5' FROM LIGHT STANDARD SA X-38-3				X									
E-5	X-39-3JB	5' FROM LIGHT STANDARD SA X-39-3				X									
E-4	X-40-2JB	5' FROM LIGHT STANDARD SA X-40-2				X									
E-4	X-41-1	5' FROM LIGHT STANDARD SA X-41-1				X									
		CSX TOTALS	12			40			1			1			
		PROJECT TOTALS	14			48			1			2	2	1	

*NOTE: JBX2, JBX4-7, JBX11-14, AND JBX21 WERE REMOVED FROM THE DESIGN, AND ARE NOT ON THESE PLANS.

TABLE "B" ELECTRICAL DUCT SUMMARY (ESTIMATED LENGTH IN FEET)

CONTROL SYSTEM "X"			TYPE							
			TRENCHLESS (TL) FEET				BURIED (BD) FEET			
LOCATION	RACEWAY 1	SHEET	SIZE 2"	SIZE 3"	SIZE 4"	SIZE 6"	SIZE 2"	SIZE 3"	SIZE 4"	SIZE 6"
-RPC- STA. 32+52	JBX1 - CSX	E-4			70		85			
-RPC- STA. 15+59		E-4		100						
-L1_EB- STA. 71+17	JBX15 - JBX16	E-4			70		80			
-RPDB-STA.19+93	JBX17 - JBX18	E-4			60		70			
-L1_WB- STA. 62+75	JBX19 -X-33-2	E-5			50		80			
-RPD- STA. 24+18		E-5		60						
CSX TOTALS				160	250		315			
PROJECT TOTALS				230	345		430	30		

SEE SHEET "E-1" FOR LEGEND & △ NOTES

COMPUTED BY: MSQ DATE:

CHECKED BY: RGH DATE:

02/03/98

04-JAN-2024 12:52
R:\Lighting\Electrical\Lighting Design\I2513_le_dsn.dgn
msquadri AT RD-3294439L