PROJECT NO.	SHEET NO.	
I-5918	3B-3	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	0170000000-E REMOVAL OF EXST CONC PVMT SLABS	0241000000-E REMOVAL OF EXISTING ASPHALT / CONC. ISLAND	0255000000-E AGGREGATE SHOULDER BORROW	1099500000-E SHALLOW UNDERCUT	1099700000-E CLASS IV SUBGRADE STABILIZATION	1112000000-E GEOTEXTILE FOR SUBGRADE STABILIZATION	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 5/8" MILLING	1297000000-E 2" MILLING	1297000000-E 3" MILLING	1308000000-E 0" TO 2" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1523000000-E SURFACE COURSE, S9.5C	1524200000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5D	1575000000-E ASPHALT BINDER FOR PLANT MIX	1577000000-E POLYMER MODIFIED ASPHALT BINDER	1704000000-E PATCHING EXISTING PAVEMENT	1839140000-E ULTRA-THIN BONDED WEARING COURSE
										MI	FT			SY	SY	TON	CY	TON	SY	TON	SMI	SY	SY	SY	SY	SY	TON	TON	TON	TON	TON	TON	TON
45924.3.1	Iredell	1	I-77 N	FROM MM 36.5 TO MM 48.85	1,2,3	2, 3	MD	NO	NO	12.35	38	36.5	48.85	1,000.00		4,100	250.00	750	1,000.00	500	24.70	55,000	6,500		7,750				34,266		2,365	1,000	7,256.00
		TOTAL FOR MAP NO. 1								**12.35**				**1,000.00**		**4,100**	**250.00**	**750**	**1,000.00**	**500**	**24.70**	**55,000**	**6,500**		**7,750**				**34,266**		**2,365**	**1,000**	**7,256.00**
45924.3.1	Iredell	2	I-77 S	FROM MM 36.5 TO MM 48.85	1,2,3	2, 3	MD	NO	NO	12.35	38	36.5	48.85	1,000.00		4,100	250.00	750	1,000.00	500	24.70	55,000	7,500		13,750				34,282		2,366	1,000	7,260.67
		TOTAL FOR MAP NO. 2								**12.35**				**1,000.00**		**4,100**	**250.00**	**750**	**1,000.00**	**500**	**24.70**	**55,000**	**7,500**		**13,750**				**34,282**		**2,366**	**1,000**	**7,260.67**
45924.3.1	Iredell	3	EXIT 42 - I-77 NB OFF RAMP	FROM I-77 NB TO US 21	4	1		NO	NO	0.25	26	0	0.25			100					0.36		3,500						618		47	50	144.00
		TOTAL FOR MAP NO. 3								**0.25**						**100**					**0.36**		**3,500**						**618**		**47**	**50**	**144.00**
45924.3.1	Iredell	4	EXIT 42 - I-77 NB ON LOOP	FROM US 21 TO I-77 NB	5	1		NO	NO	0.15	20	0	0.15			15					0.09		3,500						367		30		104.00
		TOTAL FOR MAP NO. 4								**0.15**						**15**					**0.09**		**3,500**						**367**		**30**		**104.00**
45924.3.1	Iredell	5	EXIT 42 - I-77 SB ON RAMP	FROM US 21 TO I-77 SB	12	1		NO	NO	0.38	24	0	0.38			180					0.74			9,000			1,479		1,195		80	75	193.00
		TOTAL FOR MAP NO. 5								**0.38**						**180**					**0.74**			**9,000**			**1,479**		**1,195**		**80**	**75**	**193.00**
45924.3.1	Iredell	6	EXIT 42 - I-77 SB OFF LOOP	FROM I-77 SB TO US 21	5	1		NO	NO	0.22	20	0	0.22			100					0.26		4,000			250			518		45		161.00
		TOTAL FOR MAP NO. 6								**0.22**						**100**					**0.26**		**4,000**			**250**			**518**		**45**		**161.00**
45924.3.1	Iredell	7	EXIT 45 - I-77 NB OFF RAMP	FROM I-77 NB TO AMITY HILL RD (SR 2342)	6	1		NO	NO	0.16	24	0	0.16													250					4		74.00
		TOTAL FOR MAP NO. 7								**0.16**																**250**					**4**		**74.00**
45924.3.1	Iredell	8	EXIT 45 - I77 SB ON RAMP	FROM AMITY HILL RD (SR 2342) TO I-77 SB	7	1		NO	NO	0.25	24	0	0.25			150					0.50					250	400	135		26	6		111.00
		TOTAL FOR MAP NO. 8								**0.25**						**150**					**0.50**					**250**	**400**	**135**		**26**	**6**		**111.00**
45924.3.1	Iredell	9	EXIT 45 I-77 NB ON RAMP / DOVER RD.	FROM AMITY HILL RD (SR 2342) TO I-77NB	8	1		NO	NO	0.23	30	0	0.23									5,131				250					7		132.00
		TOTAL FOR MAP NO. 9								**0.23**												**5,131**				**250**					**7**		**132.00**
45924.3.1	Iredell	10	EXIT 45 - I-77 SB OFF RAMP	FROM I-77 SB TO AMITY HILL RD (SR 2342)	8	1		NO	NO	0.16	30	0	0.16									1,200				250					4		81.00
		TOTAL FOR MAP NO. 10								**0.16**												**1,200**				**250**					**4**		**81.00**
45924.3.1	Iredell	11	EXIT 49A - I-77 NB OFF RAMP	FROM I-77 NB TO US 70	8	1		NO	NO	0.22	24	0	0.22									3,668									6		110.00
		TOTAL FOR MAP NO. 11								**0.22**												**3,668**									**6**		**110.00**
45924.3.1	Iredell	12	EXIT 49A - I-77 SB ON RAMP	FROM US 70 TO I-77 SB	8	1		NO	NO	0.3	24	0	0.3									4,824									7		144.00
		TOTAL FOR MAP NO. 12								**0.3**												**4,824**									**7**		**144.00**
45924.3.1	Iredell	13	EXIT 49A - I-77 NB ON LOOP	FROM US 70 TO I-77 NB	9	1		NO	NO	0.14	24	0	0.14									2,305									4		69.00
		TOTAL FOR MAP NO. 13								**0.14**												**2,305**									**4**		**69.00**
45924.3.1	Iredell	14	EXIT 49A - I-77 SB OFF LOOP	FROM I-77 SB TO US 70	10	1		NO	NO	0.21	26	0	0.21																		5		104.00
		TOTAL FOR MAP NO. 14								**0.21**																					**5**		**104.00**
45924.3.1	Iredell	15	EXIT 49B - I-77 NB OFF LOOP	FROM I-77 NB TO SALISBURY RD (SR 2735)	9,11	1		NO	NO	0.17	22	0	0.17		225.00							2,294									4		80.00
		TOTAL FOR MAP NO. 15								**0.17**					**225.00**							**2,294**									**4**		**80.00**
45924.3.1	Iredell	16	EXIT 49B - I-77 NB ON RAMP	FROM SALISBURY RD (SR 2735) TO I-77 NB	8,11	1		NO	NO	0.26	24	0	0.26									3,861									7		135.00
		TOTAL FOR MAP NO. 16								**0.26**												**3,861**									**7**		**135.00**
45924.3.1	Iredell	17	EXIT 49B - I-77 SB ON LOOP	FROM SALISBURY RD (SR2375) TO I-77 SB	9	1		NO	NO	0.13	22	0	0.13									2,011									4		70.00
		TOTAL FOR MAP NO. 17								**0.13**												**2,011**									**4**		**70.00**
45924.3.1	Iredell	18	EXIT 49B - I-77 SB OFF RAMP	FROM I-3819 END CONSTRUCTION TO SALISBURY RD (SR 2375)	9	1		NO	NO	0.13	22	0	0.13									2,011									4		70.00
		TOTAL FOR MAP NO. 18								**0.13**												**2,011**									**4**		**70.00**
TOTAL FOR PROJ NO. 45924.3.1										**28.06**				**2,000.00**	**225.00**	**8,745**	**500.00**	**1,500**	**2,000.00**	**1,000**	**51.35**	**137,305**	**25,000**	**9,000**	**21,500**	**1,250**	**1,879**	**135**	**71,246**	**26**	**4,995**	**2,125**	**16,298.67**
GRAND TOTAL										**28.06**				**2,000.00**	**225.00**	**8,745**	**500.00**	**1,500**	**2,000.00**	**1,000**	**51.35**	**137,305**	**25,000**	**9,000**	**21,500**	**1,250**	**1,879**	**135**	**71,246**	**26**	**4,995**	**2,125**	**16,298.67**