PROJECT REFERENCE NO.	SHEET NO.
U-5813	Sig. 25.2

MAXTIME DETECTOR PROGRAMMING DETAIL
FOR ALTERNATE PHASING LOOP 5A

Front Panel
Main Menu >Controller >Detector >Veh Det Plans

Web Interface
Home >Controller >Detector Configuration >Vehicle Detectors

In the table view of web interface right click on "Detector" in
the top left corner of the table. Copy the entire contents of
Detector Plan 1. Paste Detector Plan 1 into Detector Plan 2.
Modify Detector Plan 2 as shown below and save changes.

Plan 2

5A

Detector	Call Phase	Delay
15	5	3
31	0	3

MAXTIME OVERLAP PROGRAMMING DETAIL
FOR ALTERNATE PHASING

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

In the table view of the web interface, right click on
"Overlap" in the top left corner of the table. Copy the
entire contents of Overlap Plan 1. Paste Overlap Plan 1
into Overlap Plan 2. Modify Overlap Plan 2 as shown
below and save changes.

Overlap Plan 2

Overlap	1	2	3	4
Type	-	-	FYA 4 - Section	-
Included Phases	-	-	-	-
Modifier Phases	-	-	5	-
Modifier Overlaps	-	-	-	-
Trail Green	0	0	0	0
Trail Yellow	0.0	0.0	0.0	0.0
Trail Red	0.0	0.0	0.0	0.0

← NOTICE REMOVED INCLUDED
PHASE FOR OL3

MAXTIME OVERLAP PROGRAMMING DETAIL
FOR DEFAULT PHASING

Front Panel
Main Menu >Controller >Overlap >Overlap Parameters/Overlap Timings

Web Interface
Home >Controller >Overlap Configuration >Overlaps

Overlap Plan 1

Overlap	1	2	3	4
Type	-	-	FYA 4 - Section	-
Included Phases	-	-	6	-
Modifier Phases	-	-	5	-
Modifier Overlaps	-	-	-	-
Trail Green	0	0	0	0
Trail Yellow	0.0	0.0	0.0	0.0
Trail Red	0.0	0.0	0.0	0.0

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 08-0501T3
DESIGNED: AUGUST 2021
SEALED: 05/21/2024
REVISED:

Signal Upgrade
Temporary Signal 3
Electrical Detail - Sheet 2 of 3

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMING
DETAILS FOR:

Prepared for the Offices of:

US 64 Bus./NC 49 (Dixie Drive)
at
I-73-US 220 NB/I-74 WB Ramps

Division 8	Randolph County	Asheboro
PLAN DATE: August 2021	REVIEWED BY: A.D. Klinksiek	
PREPARED BY: N.K. Vlanich	REVIEWED BY: N.R. Simmons	

SEAL

SEAL
031464
NATASHA R. SIMMONS
NORTH CAROLINA
PROFESSIONAL
ENGINEER

HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

750 N. Greenfield Pkwy, Garner, NC 27529

REVISIONS	INIT.	DATE

SIGNATURE
DocuSigned by:
Natasha R Simmons 5/21/2024
DATE

SIG. INVENTORY NO. 08-0501T3

SIG. INVENTORY NO. 08-0501T3