PROJECT REFERENCE NO.	SHEET NO.
B-5982	RW02C-2

Location and Surveys

Vaughn & Melton

SURVEY CONTROL SHEET

W/ EXISTING CENTERLINE ALIGNMENTS PRIOR TO CONSTRUCTION

BL

POINT	DESC.	NORTH	EAST	ELEVATION
1	BL-1	670616.4920	832794.1790	2675.14
2	BL-2	671493.0070	833298.1170	2613.24
G122	GPS-122	671956.2170	833548.6220	2583.10
G123	GPS-123	672411.1700	833804.7740	2568.79
3	BL-3	673025.4970	834155.7180	2569.42
4	BL-4	673931.8010	834668.3180	2619.57

BY1

POINT	DESC.	NORTH	EAST	ELEVATION
5	BY1-5	670542.6920	832578.7240	2678.96
Y1	BL-1	670616.4920	832794.1790	2675.14

BY2

POINT	DESC.	NORTH	EAST	ELEVATION
6	BY2-6	670624.0120	833048.1120	2649.56
YY1	BL-1	670616.4920	832794.1790	2675.14

BY3

POINT	DESC.	NORTH	EAST	ELEVATION
Y8	BY4-8	671976.4380	833338.1670	2563.11
7	BY3-7	671890.5430	833509.3540	2555.48

BY4

POINT	DESC.	NORTH	EAST	ELEVATION
8	BY4-8	671976.4380	833338.1670	2563.11
Y9	BY5-9	672585.7780	833677.8700	2523.71

BY5

POINT	DESC.	NORTH	EAST	ELEVATION
9	BY5-9	672585.7780	833677.8700	2523.71
Y123	GPS-123	672411.1700	833804.7740	2568.79
10	BY5-10	672485.9130	833886.2640	2523.02

BY6

POINT	DESC.	NORTH	EAST	ELEVATION
11	BY6-11	672776.0580	833810.4940	2521.95
12	BY6-12	672581.1520	834093.8290	2522.29

BM1 ELEVATION - 2679.38
N 670510 E 832571
SPIKE NAIL IN 24" MAPLE

BM2 ELEVATION - 2566.57
N 672352 E 833782
BOLT ON SIGN BASE

BM3 ELEVATION - 2622.99
N 673899 E 834672
SPIKE NAIL IN 8" X 12" DOUBLE MAPLE

BM4 ELEVATION - 2522.93
N 672372 E 834101
SPIKE NAIL IN 24" WALNUT

BM5 ELEVATION - 2520.27
N 672790 E 833753
SPIKE NAIL IN 18" WALNUT

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
2. THE SURVEY CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

REVISIONS

6/2/99