PROJ. REFERENCE NO.	SHEET NO.
BR-0097	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE : EMBANKMENT COLUMN DOES ONT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+50.00	0	0
20+00.00	6	0
20+50.00	5	0
21+00.00	6	0
21+50.00	11	6
22+00.00	26	28
22+50.00	53	61
23+00.00	78	91
23+50.00	79	96
24+00.00	65	86
24+50.00	54	94
25+00.00	43	89
25+50.00	26	88
26+00.00	18	108
26+50.00	17	129
27+00.00	19	162
27+50.00	25	176
28+00.00	19	216
28+50.00	11	290
29+00.00	6	780

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
31+50.00	0	0
32+00.00	0	1455
32+50.00	0	642
33+00.00	0	594
33+50.00	19	517
34+00.00	35	410
34+50.00	39	326
35+00.00	43	244
35+50.00	31	179
36+00.00	24	130
36+50.00	29	84
37+00.00	41	50
37+50.00	39	33
38+00.00	24	24
38+50.00	21	19
39+00.00	22	16
39+50.00	20	15
40+00.00	18	14
40+50.00	12	6
41+00.00	16	4
41+50.00	21	6
42+00.00	14	6
42+50.00	5	6
43+00.00	11	6
43+50.00	22	6
44+00.00	13	2
44+50.00	5	0
45+00.00	6	0