Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Removal of Existing Asphalt Pavement, Breaking of Existing Asphalt Pavement, and Clearing and Grubbing, will be paid for at the contract lump sum price for "Grading."

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+50.00	0	0	10+50.00	0	0
13+00.00	28	6	11+00.00	26	5
13+50.00	51	6	11+50.00	51	1
14+00.00	71	10			
14+50.00	106	37			
15+00.00	114	96			
15+50.00	80	167			
16+00.00	54	247			
16+50.00	42	345			
17+00.00	31	458			
17+50.00	27	549			
18+00.00	41	591			
18+50.00	30	596			
18+62.50	0	150			

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+50.50	0	0
23+00.00	0	349
23+50.00	7	310
24+00.00	22	263
24+50.00	34	237
25+00.00	68	229
25+50.00	86	216
26+00.00	61	198
26+50.00	41	165
27+00.00	31	127
27+50.00	37	81
28+00.00	35	54
28+50.00	11	48
29+00.00	0	42
29+50.00	0	49
30+00.00	0	64
30+50.00	9	75
31+00.00	9	74
31+50.00	0	89
32+00.00	0	130
32+50.00	4	209
33+00.00	4	273
33+50.00	0	307
34+00.00	0	338
34+50.00	0	306
35+00.00	0	251
35+50.00	0	204
36+00.00	0	165
36+50.00	0	151
37+00.00	0	140
37+50.00	3	121
38+00.00	15	102
38+50.00	21	79
39+00.00	25	41
39+50.00	24	16
40+00.00	17	11
40+20.00	6	4

5/14/99
19-JUL-2024 11:03
oadway\Corridor Modeling\BR0139_rdy_xsc_summary.dgn