

PROJECT NO.	SHEET NO.	TOTAL NO.
2025CPT.09.01.10291	15	
2025CPT.09.02.20291		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	1881000000-E		2830000000-N	2845000000-N		
														INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1 1/2"DEPTH	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS 10"	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS 18"	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOX		
														TONS	SMI	TONS	SY	SY	TONS	TONS	TONS	TONS	LF	LF	EA	EA		
2025CPT.09.01.10291	Davidson	1	NC-109 N	FROM UNITY ST SR2051 TO BRG#135 AT ABBOTTS CREEK	1,2,3	2,4	MD	NO	NO	4.47	31-78	28.22	32.69		8.94	1,725	88,100	16,806		10,177	601	10	38,000	850	8	4		
TOTAL FOR MAP NO. 1															8.94	1,725	88,100	16,806		10,177	601	10	38,000	850		8	4	
2025CPT.09.01.10291	Davidson	2	NC-109 S	FROM BRIDGE #135 AT ABBOTTS CREEK TO UNITY ST SR1800	1,2,3	2,4	MD	NO	NO	4.431	31-78	6.199	10.63		8.86	1,710	87,564	10,656		9,438	557	10	38,130					
TOTAL FOR MAP NO. 2															8.86	1,710	87,564	10,656		9,438	557	10	38,130					
TOTAL FOR PROJ NO. 2025CPT.09.01.10291															17.80	3,435	175,664	27,462		19,615	1,158	20	76,130	850		8	4	
2025CPT.09.02.20291	Davidson	3	SR-1493 / FRYE BRIDGE RD	FROM FORSYTH COUNTY LINE TO NC150	4	2	2WU	NO	NO	4.62	24.5-40	0	4.62	600	9.24	1,783	66,349	3,073		6,668		434	10			2	30	
TOTAL FOR MAP NO. 3															9.24	1,783	66,349	3,073		6,668		434	10		2	30		
2025CPT.09.02.20291	Davidson	4	SR-1741 / WALLBURG-HIGH POINT RD	FROM NC109 TO W LEXINGTON AVE SR1755	4	2,3	2WU	NO	NO	5.798	23.5-41	0	5.798	200	11.60	2,238	79,673	2,626		7,895		514	10			2	16	
TOTAL FOR MAP NO. 4															11.60	2,238	79,673	2,626		7,895		514	10		2	16		
2025CPT.09.02.20291	Davidson	5	SR-3056 / SCENIC WAY	FROM NC109 TO NC109	4	2,3	2WU	NO	NO	1.94	24.5-40	0	1.94	90	3.88	749	27,342	2,208		2,820		184	10			2	18	
TOTAL FOR MAP NO. 5															3.88	749	27,342	2,208		2,820		184	10		2	18		
2025CPT.09.02.20291	Davidson	6	SR-1770 / N ALBERTSON RD	FROM PLEASANT GROVE CH RD SR1769 TO W TRIAD BLVD SR1876/1877	6	2	2WU	NO	NO	0.16	19	0	0.16	20	0.32	62				254		17				2		
TOTAL FOR MAP NO. 6															0.32	62				254		17			2			
2025CPT.09.02.20291	Davidson	7	SR-1772 / HASTY SCHOOL RD	FROM SCENIC RD SR3056 TO US 29/70	4	2,3	2WU	NO	NO	2.99	24-37	0	2.99		5.98	1,154	43,216	3,687		4,476		291	10			8	32	
TOTAL FOR MAP NO. 7															5.98	1,154	43,216	3,687		4,476		291	10		8	32		
2025CPT.09.02.20291	Davidson	8	SR-1781 / WILL JOHNSON RD	FROM HASTY SCHOOL RD SR1772 TO BALL PARK RD	5	2	2WU	NO	NO	0.915	20	0	0.915	25	1.83	353				750		891	10					
TOTAL FOR MAP NO. 8															1.83	353				750		891	10					
2025CPT.09.02.20291	Davidson	9	SR-1800 / MIDWAY SCHOOL RD	FROM SCENIC RD SR3056 TO NC109	4	2,3	2WU	NO	NO	0.26	26-46	0	0.26	25	0.52	100	4,113			375		25	10					
TOTAL FOR MAP NO. 9															0.52	100	4,113		375		25	10						
TOTAL FOR PROJ NO. 2025CPT.09.02.20291															33.37	6,439	220,693	12,344		23,379		1,523	60		16	96		
GRAND TOTAL															25.584	960	51.17	9,874	396,357	39,806	23,379	19,615	2,681	80	76,130	850	24	100

Note: All quantities listed include turn lanes and are estimates; Payment will be based on measurements and quantities received