

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

<b>Kimley»Horn</b> <small>© 2024</small>
<small>200 S. TRYON ST. • CHARLOTTE, NC 28202</small>
<small>RIGHT-OF-WAY REV.</small>
<small>CONST. REV.</small>

<small>PROJECT REFERENCE NO.</small>	<small>SHEET NO.</small>
<i>U-4713A</i>	<i>EC-3A</i>

## ***SOIL STABILIZATION TIMEFRAMES***

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 TO 4:1	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH WITH SLOPES STEEPER THAN 4:1. 7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES

6/3/2024 K:\CHL\_PRR\01036426 - McKee Rd Ext\Environmental\Design\U-4713A.ec\_psh\_02&03.dgn