

PROJECT NO.	SHEET NO.
2025CPT.03.06.10671, ETC.	10

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1575000000-E	1693000000-E	1705000000-E	1705500000-E	2738000000-E		2830000000-N	2845000000-N	3287000000-N				
														ASPHALT BINDER FOR PLANT MIX	ASPHALT PLANT MIX, PAVEMENT REPAIR	PATCHING EIXSTING PAVEMENT (FULL DEPTH)	PATCHING EXISTING PAVEMENT (MILL)	REMOVE EXISTING ASPHALT ISLAND	5" MONOLITHIC CONC. ISLAND (GENERIC)	ADJUSTMENT OF MANHOLES	ADJUSTMENT OF METER OR VALVE BOX	GUARDRAIL END UNITS, TYPE TL-3				
														MI	FT											
														TON	TON	TON	TON	SY	SY	EA	EA	EA				
2025CPT.03.06.10671	Onslow	1	NC-24 E (LEJEUNE BLVD)	FROM NC HWY 53 (WESTERN BLVD) TO SR 1406 (PINEY GREEN RD) [MP 23.97 - MP 27.87]	1, 2, 3, 4	3	MD	NO	NO	3.90	38	23.97	27.87	596		120	5			6	2	10				
TOTAL FOR MAP NO. 1														3.90		596	120	5			6	2	10			
2025CPT.03.06.10671	Onslow	2	NC-24 W (FREEDOM WAY)	FROM SR 1406 (PINEY GREEN RD) TO NC HWY 53 (WESTERN BLVD) [MP 12.62 - MP 16.53]	1, 2, 3, 4	3	MD	NO	NO	3.91	36	12.62	16.53	537		120	5				2	8				
TOTAL FOR MAP NO. 2														3.91		537	120	5				2	8			
TOTAL FOR PROJ NO. 2025CPT.03.06.10671														7.81		1,133	240	10			6	4	18			
2025CPT.03.06.20671	Onslow	3	SR-1529 (TURKEY POINT RD/HARBOR POINT RD)	FROM SR 1518 (OLD FOLKSTONE RD) TO END OF MAINTENANCE [MP 0.00 - MP 1.83]	5	2	2WU	NO	NO	1.83	24	0.00	1.83	220			107									
TOTAL FOR MAP NO. 3														1.83		220		107								
2025CPT.03.06.20671	Onslow	4	SR-1530 (TURKEY POINT RD)	FROM SR 1529 (HARBOR PT) TO END OF MAINTENANCE [MP 0.00 - MP 0.82]	5	2	2WU	NO	NO	0.82	23	0.00	0.82	87							1					
TOTAL FOR MAP NO. 4														0.82		87						1				
2025CPT.03.06.20671	Onslow	5	SR-1531 (TAR LANDING RD)	FROM SR 1518 (OLD FOLKSTONE RD) TO END OF MAINTENANCE [MP 0.00 - MP 3.09]	6	2	2WU	NO	NO	3.09	21	0.00	3.09	255	10		607	250	250		3					
TOTAL FOR MAP NO. 5														3.09		255	10	607	250	250		3				
TOTAL FOR PROJ NO. 2025CPT.03.06.20671														5.74		562	10	714	250	250		4				
GRAND TOTAL														13.55		1,695	10	240	724	250	250	6	8	18		
																		500								