

PROJECT NO.	SHEET NO.	TOTAL NO.
2025CPT.07.08.10011, 2025CPT.07.08.20011	10	

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	0106000000-E	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1575000000-E	1704000000-E	1775000000-E	1838000000-E	2830000000-N	2845000000-N	5255000000-N	6000000000-E	6071010000-E	6084000000-E	7990000000-E		
									BORROW EXCAVATION	INCIDENTAL STONE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH	INCIDENTAL MILLING	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	ADJUSTMENT OF MANHOLES	ADJUSTMENT OF METER BOXES OR VALVE BOXES	PORTABLE LIGHTING	TEMPORARY SILT FENCE	WATTLE	SEEDING & MULCHING	INDUCTIVE LOOP SAW CUT (DEEP CUT)		
							MI	FT	CY	TONS	SMI	TON	SY	SY	TONS	TON	TONS	SY	GAL	EA	EA	LS	LF	LF	AC	LF		
2025CPT.07.08.10011	Alamance	1	NC-49/NC-54/NC-87/MAPLE AVE/HARDEN ST/E ELM ST/GRAHAM RD	FROM SR 1148 - ANTHONY RD TO SR 1801 - W MAIN ST	1,2	2-4	4.33	50	21	60	2.14	61	110,141	13,998	11,266	747	300			72	75	*	428	43	0.08	14,000		
<b>TOTAL FOR MAP NO. 1</b>							<b>4.33</b>		<b>21</b>	<b>60</b>	<b>2.14</b>	<b>61</b>	<b>110,141</b>	<b>13,998</b>	<b>11,266</b>	<b>747</b>	<b>300</b>			<b>72</b>	<b>75</b>		<b>428</b>	<b>43</b>	<b>0.08</b>	<b>14,000</b>		
<b>TOTAL FOR PROJ NO. 2025CPT.07.08.10011</b>							<b>4.33</b>		<b>21</b>	<b>60</b>	<b>2.14</b>	<b>61</b>	<b>110,141</b>	<b>13,998</b>	<b>11,266</b>	<b>747</b>	<b>300</b>					<b>72</b>	<b>75</b>	<b>1.00</b>	<b>428</b>	<b>43</b>	<b>0.08</b>	<b>14,000</b>
2025CPT.07.08.20011	Alamance	2	SR-1581 / STONEY CREEK CHURCH RD	FROM NC 87 TO SR 1001 - UNION RIDGE RD	3	2	7.91	21	157	360	15.68	445		742	9,190	765	3,500	97,289	32,105				3,148	315	0.57			
<b>TOTAL FOR MAP NO. 2</b>							<b>7.91</b>		<b>157</b>	<b>360</b>	<b>15.68</b>	<b>445</b>		<b>742</b>	<b>9,190</b>	<b>765</b>	<b>3,500</b>	<b>97,289</b>	<b>32,105</b>					<b>3,148</b>	<b>315</b>	<b>0.57</b>		
2025CPT.07.08.20011	Alamance	3	SR-1149 / HUFFMAN MILL RD	FROM 2 LANE SECTION TO SR 1213 - GRAND OAKS BLVD	1	2-4	0.20	25					6,677	173	622	41	10			1						3,200		
<b>TOTAL FOR MAP NO. 3</b>							<b>0.20</b>							<b>6,677</b>	<b>173</b>	<b>622</b>	<b>41</b>	<b>10</b>			<b>1</b>						<b>3,200</b>	
2025CPT.07.08.20011	Alamance	4	SR-1158 / HUFFMAN MILL RD	FROM SR 1213 - GRAND OAKS BLVD TO US 70/S CHURCH ST	1,2	2-4	2.00	60					75,687	12,014	7,959	531	290			26	25					13,000		
<b>TOTAL FOR MAP NO. 4</b>							<b>2.00</b>							<b>75,687</b>	<b>12,014</b>	<b>7,959</b>	<b>531</b>	<b>290</b>			<b>26</b>	<b>25</b>					<b>13,000</b>	
<b>TOTAL FOR PROJ NO. 2025CPT.07.08.20011</b>							<b>10.11</b>		<b>157</b>	<b>360</b>	<b>15.68</b>	<b>445</b>		<b>82,364</b>	<b>12,929</b>	<b>17,771</b>	<b>1,337</b>	<b>3,800</b>	<b>97,289</b>	<b>32,105</b>	<b>27</b>	<b>25</b>	<b>1.00</b>	<b>3,148</b>	<b>315</b>	<b>0.57</b>	<b>16,200</b>	
<b>GRAND TOTAL</b>							<b>14.44</b>		<b>178</b>	<b>420</b>	<b>17.82</b>	<b>506</b>		<b>192,505</b>	<b>26,927</b>	<b>29,037</b>	<b>2,084</b>	<b>4,100</b>	<b>97,289</b>	<b>32,105</b>	<b>99</b>	<b>100</b>	<b>1.00</b>	<b>3,576</b>	<b>358</b>	<b>0.65</b>	<b>30,200</b>	

**NOTE: All Quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received.**