CPRUETTCOMP,8/22/2024,X:\NCDOT\R-5921\Roadway\XSC\Earthwork\Final\xsc_ew_volumes.xls
Docusign Envelope ID: B0011873-4BA7-423C-9274-28B7E03A1CDD

PROJ. REFERENCE NO.	SHEET NO.
R-5921	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
274+00.00	63	28	12+75.00	20	44
274+50.00	58	91	13+00.00	21	50
275+00.00	45	113	13+50.00	34	120
275+50.00	40	88	14+00.00	29	136
276+00.00	53	66	14+50.00	20	170
276+50.00	62	40	15+00.00	5	338
278+00.00	210	38	15+50.00	0	452
278+50.00	71	3	16+00.00	27	285
279+00.00	57	8	16+50.00	27	176
279+50.00	49	16	17+00.00	4	223
280+00.00	46	26	17+50.00	7	236
280+50.00	44	33	18+00.00	59	150
281+10.00	58	36	18+50.00	128	43
281+50.00	39	46	19+00.00	143	44
281+75.00	39	28	19+50.00	106	65
282+00.00	49	10	20+00.00	44	83
282+50.00	73	19	20+50.00	10	89
282+80.00	38	13	21+00.00	15	68
283+50.00	116	43	21+50.00	37	52
284+00.00	109	27	22+00.00	47	54
284+50.00	108	47	22+40.00	33	42
285+00.00	81	91	22+50.00	11	5
285+50.00	67	63	23+00.00	53	18
286+00.00	64	74	23+60.00	23	38
286+50.00	70	90	23+85.00	6	14
286+75.00	30	14	24+20.00	29	15
287+20.00	39	7	24+30.00	9	3
287+50.00	25	7	24+50.00	14	4
288+00.00	44	11	25+00.00	43	5
288+50.00	47	11	25+10.00	10	0
289+00.00	41	12	25+50.00	42	1
289+50.00	43	13	26+00.00	19	1
290+00.00	41	17			
290+50.00	36	19			
291+00.00	33	9			
291+50.00	32	0			
292+00.00	31	0			
292+50.00	17	0			
293+00.00	3	1			
293+50.00	4	1			
294+00.00	5	0			
294+33.00	2	0			

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+30.00	11	0
10+50.00	9	3
11+00.00	3	18
11+50.00	6	30
12+00.00	19	36
12+50.00	31	54