

6/21/00

COMPUTED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

PROJECT REFERENCE NO. R-5726
 SHEET NO. 3B-4

**SUMMARY OF EXISTING
 ASPHALT PAVEMENT REMOVAL**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD ²
-L-	10+00	18+46	LT	342.30
-L-	10+00	13+38	LT-MED	34.05
-L-	10+00	12+91	RT-MED	37.87
-L-	10+00	16+85	RT	319.96
-L-	18+46	19+24	LT	19.96
-L-	17+30	30+00	RT	6,159.79
-L-	30+00	36+09	RT	1,590.57
-L-	36+09	47+10	LT	1,492.46
-L-	36+09	39+89	RT	703.44
-L-	39+89	43+95	RT	665.49
-L-	43+95	47+10	RT	549.95
-L-	47+10	56+13	LT	334.11
-L-	47+10	56+13	RT	164.07
-L-	56+13	86+34	LT	3,290.06
-L-	56+13	65+56	RT	1,020.33
-L-	86+34	98+96	LT	782.95
-L-	98+96	111+30	LT	1,003.74
-L-	111+30	117+60	LT	299.50
-L-	117+60	126+12	LT	1,375.90
-L-	126+12	131+51	LT	153.64
-L-	126+12	131+51	RT	262.14
-L-	131+51	136+63	LT	222.00
-L-	136+63	143+69	LT	1,180.67
-L-	143+69	151+10	LT	1,503.45
-L-	151+10	156+33	LT	256.04
-L-	156+33	169+52	LT	1,020.76
-L-	169+52	194+75	LT	2,374.61
-L-	194+75	212+85	LT	1,290.83
-L-	212+85	226+38	LT	1,291.70
-L-	226+38	234+00	LT	381.78
-L-	234+00	248+63	LT	664.54
-L-	248+63	262+75	LT	1,202.99
Y1	16+70	17+48	LT	14.26
Y1	16+70	17+48	RT	26.59
Y3	13+10	14+88	LT	30.81
Y3	13+10	14+88	RT	30.42
Y4	10+76	18+25	LT	1.84
Y4	10+76	18+25	RT	62.28
Y8A	11+21	11+58	CL	97.71
Y11	10+29	11+25	LT	27.29
Y11	10+29	11+25	RT	29.19
Y12	12+41	12+90	LT	6.73
Y12	12+41	12+90	RT	9.53
Y14	10+00	15+90	CL	126.54
Y16	10+00	10+25	CL	6.60
Y18	11+30	12+60	RT	643.37
Y19	10+00	10+22	LT	57.53
Y21	10+46	12+50	LT	25.51
Y21	10+46	12+50	RT	19.06
TEMPORARY PAVEMENT REMOVAL				
-L-	63+14.32	72+88.31	LT	852.43
-L-	104+12.75	111+30.00	RT	410.63
-L-	117+60.00	125+87.42	RT	454.70
-L-	136+62.58	151+10.00	RT	842.44
-L-	156+32.85	159+45.22	RT	164.46
-L-	191+24.83	194+75.00	RT	194.63
-L-	195+55.00	197+39.09	RT	135.10
-L-	249+82.36	256+27+75	RT	320.94
TOTAL:				36,582.24
SAY:				36,590

**SUMMARY OF
 CHAIN LINK FENCE, 72" FABRIC**

STATION TO STATION	LT or RT	A FABRIC (LF)	B END BRACE	C CORNER BRACE	D LINE BRACE	E 4" POSTS (EA)	F 5" POSTS (EA)	
-L- 118+40.00 TO 121+80.00	RT	957'	2	4	10	82	16	
-L- 213+85.00 TO 216+05.21	RT	735'	2	4	10	63	16	
-L- 42+23.00 TO 43+43.85	LT	121'	2			10	2	
TOTAL:		1813'				155	34	
SAY:		1850'				155	34	
DOUBLE GATES, 72" HIGH, 8' WIDE, 16' OPENING							SAY:	2
METAL GATE POST FOR 72" CHAIN LINK FENCE, DOUBLE GATE							SAY:	4

NOTE: LT or RT INDICATES LEFT OR RIGHT OF THE MAIN LINE.

SHOULDER BERM GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	LENGTH
-L-	183+25.00	194+00.00	RT	1,075.0'
-L-	186+00.00	192+25.00	LT	625.0'
TOTAL:				1,700.0'
SAY:				1,700'

EXPRESSWAY GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	LENGTH
-L-	196+00.00	200+50.00	LT	450.00'
-Y8A-	10+00.00	10+73.46	LT	100.00'
TOTAL:				550.00'
SAY:				550'