PROJECT REFERENCE NO. R-5726

PREEMPTION PROGRAMMING

Front Panel

Main Menu >Controller >Preemption >Preempt Phasing/Preempt Parameters

Web Interface

Home >Controller >Preempt Configuration >Preempts


Preempt Configuration

Preempt	1
Enabled	Enabled
Туре	Rail Road
Track Phases	4,39
Track Overlaps	-
Dwell Phases	2,5
Dwell Peds	-
Dwell Overlaps	3
Cycling Phases	2,5,6
Cycling Peds	-
Cycling Overlaps	3
Exit Phases	4
Exit Overlaps	-
Delay	0
Call Ext Time	1.0
Max Presence	0
Max Pres Act	Terminate
Enter Min Green	1
Enter Walk	0
Enter Ped Clear	0
Enter Yellow Change	4.7
Enter Red Clear	3.2
Track Green	22
Track Yellow Clr	3.2
Track Red Clear	2.9
Dwell Green	0
Exit Min Green	255
Exit Yellow Change	25.5
Exit Red Clear	25.5
Exit Type	Exit Phases
Non Locking Memory	-
Not Ovrd Flash	X
Not Ovrd Nxt Pre	-
Require All Red Entry	-
Track Clear Ovrd	Χ
Ped Clear During Yellow	-
Entry Omit OLTG	X
Track Reserve	X

RAILROAD PREEMPTION WIRING DETAIL

(wire as shown below)


PREEMPTION AND BLANKOUT SIGN CONTROL BOX



NOTES

- 1. Relay K1 is shown in the energized (Preempt <u>not</u> active) normal operation state.
- 2. Relay K1 is a DPDT with 120VAC coil with octal base.
- 3. Relay SSR1 is a SPST (normally open) Solid State Relay with AC input and AC (25 amp) output.
- 4. AC Isolator Card shall activate preemption upon removal of AC+ from the input (as shown above). To accomplish this set invert dip switch on AC Isolator Card.
- 5. IMPORTANT!! A jumper must be added between input file terminals J14-E and J14-K if not already present. Also, terminal TB9-12 (on input panel) shall be connected to AC neutral (jumper may have to be added).

FRONT VIEW



SEQUENCE DETAIL

Front Panel

Main Menu >Controller >Sequence & Phs Config>Sequences

Web Interface


Home >Controller >Sequence

Sequence 1

Ring	Sequence Data
1	1,2,a,3,4,b
2	5,6,a,7,8,b
3	39,c,40,d


PREEMPT 1 AC ISOLATOR (MODEL 252) **OUTPUT PROGRAMMING DETAIL**

(set DIP switches as shown below)



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 08-0410 DESIGNED: June 2024 SEALED: 7/11/2024 REVISED:

Electrical Detail - Sheet 3 of 3



NC 211 SR 1239 (Seven Lakes Drive)

and SR 1190 (Lakeway Drive) Division 8 Moore County Seven Lakes June 2024 REVIEWED BY: R. Mullinax PLAN DATE: PREPARED BY: LD Stouchko REVIEWED BY: REVISIONS INIT. DATE

034437 SIG. INVENTORY NO.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

M **MOTT MACDONALD** MOTT MACDONALD I & E, LLC 930 Main Campus Drive Suite 200 RALEIGH, NC 27606