



*Prepared for*  
**North Carolina Department of Transportation**  
Century Center Complex, Building B  
1020 Birch Ridge Drive  
Raleigh, North Carolina 27610

**PRELIMINARY SITE ASSESSMENT**  
**NC 211 IN WEST END**  
**PARCEL 43**  
**5114 NC HIGHWAY 211,**  
**MOORE COUNTY**  
**WEST END, NORTH CAROLINA**

**WBS #: 50218.1.1**  
**TIP#: R-5726**

*Prepared by*

Geosyntec Consultants of NC, PC  
2501 Blue Ridge Road, Suite 430  
Raleigh, North Carolina 27607

Project Number GN7039

October 2019

**Date:** October 21, 2019  
**WBS Number:** 50218.1.1  
**TIP Number:** R-5726  
**County:** Moore County  
**Description:** Preliminary Site Assessment  
**Address:** 5114 NC 211, West End, North Carolina 27376  
**Parcel ID:** Parcel 43 (Susan McCaskill Morgan and Others)  
**Author:** R. Matthew Jenny, P.E.

I, R. Matthew Jenny, a Professional Engineer for Geosyntec Consultants of NC, PC do certify that the information in this report is correct and accurate to the best of my knowledge.



Not considered final until all signatures are completed

Geosyntec Consultants of NC, PC is licensed to practice engineering in North Carolina. The certification number (Firm's License Number) is C-3500.

Geosyntec Consultants of NC, PC is licensed to practice geology in North Carolina. The certification number (Firm's License Number) is C-295.

## TABLE OF CONTENTS

1.	INTRODUCTION .....	1
1.1	Description.....	1
1.2	Site Background .....	1
1.3	Scope of Work .....	1
2.	HISTORY .....	3
2.1	Historical Aerial Photographs .....	3
2.2	Subject Site Findings .....	3
3.	METHODS .....	4
3.1	Geophysical Investigation .....	4
3.2	Sub-Surface Soil Investigation .....	4
4.	RESULTS .....	6
4.1	Site Observations .....	6
4.2	Geophysical Investigation Results.....	6
4.3	Sub-Surface Investigation Results.....	6
4.3.1	Field Sampling Observations and PID Results .....	6
4.3.2	Soil Sampling Analytical Results.....	7
5.	SUMMARY.....	8

## LIST OF TABLES

Table 1:	Soil Boring Coordinates
Table 2:	Soil Analytical Results – TPH by UVF
Table 3:	Soil Analytical Results – VOCs

## **LIST OF FIGURES**

- Figure 1: Site Location
- Figure 2: Site Layout
- Figure 3: Soil Boring Locations (Roadway Design Base Map)

## **LIST OF APPENDICES**

- Appendix A: Geophysical Investigation Report
- Appendix B: Photographic Log
- Appendix C: Soil Boring Logs
- Appendix D: Red Lab UVF Report
- Appendix E: Prism Laboratories Analytical Report

## **1. INTRODUCTION**

### **1.1 Description**

Geosyntec Consultants of NC, PC (Geosyntec) presents this technical report (Report) to the North Carolina Department of Transportation (NCDOT) for the Preliminary Site Assessment (PSA) of 5114 NC 211 in West End, North Carolina (the Site). The Site is associated with NCDOT TIP number R-5726, Parcel 43, and owned by Susan McCaskill Morgan and Others. A Site location map is presented in **Figure 1**.

Geosyntec understands NCDOT would like to acquire right-of-way (ROW) and Public Utility Easements (PUEs) for road improvements along NC 211 in West End, North Carolina. The principal purpose of this PSA is to assess the possible presence of underground storage tanks (USTs) and/or above-ground storage tanks (ASTs), determine the likelihood of environmental impacts (i.e., soil and/or groundwater contamination), and make recommendations for regulatory compliance within the project study area.

This report discusses the Site history, investigative methodology, observations, sampling results, conclusions, and recommendations.

### **1.2 Site Background**

NCDOT Parcel 43 (Moore County Parcel number 00022508 [Susan McCaskill Morgan and Others]) is located on 5114 NC HWY 211 in West End. **Figure 2** shows the general Site layout, including the locations of the soil borings advanced to investigate the subsurface of the Site. According to NCDOT, the Site is a former gas station and auto garage. Currently, the Site has a vacant building. No known UST incidents are associated with the Site.

The property is approximately 1.5 acres and is bounded to the immediate east by NC 211 and to the north, west and south by forest and grassland. Approximately two-thirds of the southern half of the property is covered by a dense tree line and was inaccessible. No investigative activities were performed in this inaccessible portion of the property.

### **1.3 Scope of Work**

The scope of work consisted of a historical Site desktop review, geophysical survey, and sub-surface soil investigation. The geophysical survey was performed to locate potential

*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



metallic USTs, UST-associated product lines, non-UST metallic anomalies, and private underground utility lines within the immediate vicinity of the proposed soil boring locations. Following the geophysical survey, soil borings were advanced and soil samples were collected from each location to determine if, and to what extent, contaminated soils are present within the study area.

## **2. HISTORY**

Geosyntec reviewed publicly accessible online environmental databases (i.e., the North Carolina Department of Environmental Quality [NCDEQ] Laserfiche database, the NCDEQ Division of Waste Management Site Locator Tool, and the NCDEQ UST Section database) to research the Site history.

### **2.1 Historical Aerial Photographs**

The following reviews the findings from the historical aerial photographs, as provided by Google Earth® imagery:

- The earliest aerial photographs date back to 1993, which shows one above-grade structure on the property. The structure identified in the 1993 aerial photograph appears consistent with the present-day building.
- No significant deviations to the site were identified between 1993 and 2018.
- The Site surroundings (residential and commercial land) appear generally consistent from 1993 to 2018.

### **2.2 Subject Site Findings**

There were no UST incidents associated with the property identified in the initial Site historical review. Further, other (i.e., non-UST) environmental incidents were not identified as part of a cursory desktop review.

Based upon the limited environmental history information, Geosyntec conducted a Site investigation inclusive of a geophysical survey and intrusive activities to screen soil and evaluate if there is contamination within the Site study area.

### **3. METHODS**

#### **3.1 Geophysical Investigation**

The geophysical investigation was performed at the Site by Pyramid Environmental and Engineering P.C. (Pyramid) from July 29 to July 31, 2019 to locate and mark buried USTs, buried metallic drums, and/or buried utility lines within the accessible portions of the ROW/PUE extent. Generally, the tasks consisted of an electromagnetic induction-metal (EM) detection followed by ground penetrating radar (GPR) surveys.

The EM data was digitally collected at approximately 1-foot intervals along survey lines spaced approximately five feet apart. The EM unit can detect a metal drum down to a depth of approximately eight (8) to ten (10) feet. GPR scanning was conducted across selected EM metal detection anomalies, around the proposed boring locations, and across the entire ROW/PUE area along with a DitchWitch utility locator for buried utility line clearance. Additional details of the geophysical investigation methodology are provided in **Appendix A** of the report.

#### **3.2 Sub-Surface Soil Investigation**

The sub-surface investigation was conducted on August 12-15, 2019 using a direct push technology (DPT) drill rig. SAEDACCO provided the drilling services. North Carolina 811 was notified to mark utility lines within the existing ROW prior to drilling. A hand auger was used for the top three (3) to five (5) feet of each boring as an additional safety precaution.

Four (4) soil borings were completed during this investigation, each extending 10 feet below ground surface (ft bgs). Soil sampling locations were selected in areas likely to be encountered during roadway construction. Specific priority was placed at locations proximal to the identified “No Confidence anomaly” (discussed in more detail in the Results section of the report). The soil lithology was recorded, and the soil was screened using a photo-ionization detector (PID) with a 10.6 electron-Volt lamp at approximately 6-inch intervals. Soil samples were collected from each boring at an elevation corresponding to the highest PID reading. In instances where PID readings were null, field personnel used professional judgement (e.g., odors, staining, historical Site-use information) to determine the appropriate sampling depth.



Upon DPT completion, the soil cuttings were dispersed over the Site's natural areas and/or backfilled within the boring. Boring surface completions matched pre-existing conditions to the extent practical. Boring locations were surveyed with a global position system (GPS) unit. DPT rods were decontaminated with a Liquinox<sup>®</sup> cleaning solution between borings. Free product was not encountered during soil sampling, nor was other investigative derived waste (IDW) accumulated. As such, IDW drums were unnecessary.

Samples were sent off-site to Red Lab, LLC (Red Lab) and Prism Laboratories, Inc. (Prism). The samples sent to Red Lab were analyzed for Total Petroleum Hydrocarbon (TPH), gasoline-range organics (GRO), and diesel-range organics (DRO) by Ultra-Violet Fluorescence (UVF). Soil samples submitted to Prism were analyzed for volatile organic compounds (VOCs) by USEPA Method 8260B, reporting only benzene, toluene, ethylbenzene, and xylenes (BTEX). The analytical approaches are consistent with the UST Section Guidance. Samples were sent on ice under chain of custody procedures to the applicable laboratory.

## **4. RESULTS**

### **4.1 Site Observations**

On July 29, 2019 Geosyntec performed an initial Site walk with Pyramid prior to conducting work. The Site is vacant and assumed to operate as a former fuel station and auto-maintenance shop. Most of the southern half of the property is covered by a dense tree line. **Appendix B** provides a photographic log of observations.

### **4.2 Geophysical Investigation Results**

The geophysical survey was performed to locate and mark buried USTs, buried metallic drums, and/or buried utility lines within the ROW/PUE extent using both EM and GPR approaches.

Pyramid identified four (4) EM anomalies. The majority of the EM anomalies were directly attributed to visible features at the ground surface. One metallic anomaly was associated with unknown buried metal and was investigated by GPR. GPR recorded evidence of a possible buried metallic structure or debris; however, the feature was not consistent with what would be expected for an UST. The anomaly was approximately 13 feet long and 6.5 feet wide and is classified by Pyramid as a “No Confidence anomaly”. The finding is buried approximately 4 ft bgs. Pyramid’s geophysical report is provided in **Appendix A**.

### **4.3 Sub-Surface Investigation Results**

#### **4.3.1 Field Sampling Observations and PID Results**

Following the geophysical survey, the sub-surface investigation was performed to determine if, and to what extent, contaminated soils are present within the study area. Four (4) soil borings were completed during this investigation, each extending 10 ft bgs. PID soil screening values were minimal (less than 1 part per million [ppm]) throughout the entirety of each soil boring. The soil lithology generally consisted of top soil in the first three (3) ft bgs followed by sandy clay with some gravel. Groundwater was not encountered. Soil sampling locations are shown on **Figure 2** and GPS coordinates are recorded on **Table 1**. The boring logs are provided in **Appendix C**.

### 4.3.2 Soil Sampling Analytical Results

Four (4) soil samples were collected as part of the intrusive investigation and analyzed for TPH by UVF and VOCs by EPA Method 8260B. The TPH analytical data was screened against the TPH DRO and TPH GRO values established in the UST Section Guidance. The benzo(a)pyrene and BTEX analytical data were compared to the NCDEQ UST Section Maximum Soil Contaminant Concentrations (MSCCs).

The UVF fingerprinting data do not indicate soil screening level exceedances for the constituents analyzed. DRO was detected in the SB43-01 soil sample. No results exceeded the screening values. **Table 2** shows the TPH analytical results.

VOC analytical data was screened against the NCDEQ UST Section MSCCs. No detections were reported. The VOC analytical results are shown in **Table 3**.

The UVF analytical report, including the fingerprint matching data, is provided in **Appendix D**; the Prism analytical report is provided in **Appendix E**<sup>1</sup>. **Figure 3** displays the soil boring locations using a preliminary roadway design drawing base map.

---

<sup>1</sup>The Prism Laboratory report includes analytical results for samples collected from other parcels associated with NCDOT project R-5726

## **5. SUMMARY**

From August 12-15, 2019 Geosyntec completed an environmental PSA to determine the likelihood of contamination within the proposed acquisition area on the property located at 5114 NC 211, West End, North Carolina (NCDOT Parcel 43). The property is owned by Susan McCaskill Morgan and Others. The following summarizes the findings of this PSA.

Following a cursory desktop Site review, no environmental incidents associated with the Site were identified. A geophysical survey and intrusive soil investigation were performed as part of this scope of work. Pyramid identified one metallic “No Confidence” anomaly believed to be associated with an unknown buried structure or debris. The anomaly is approximately 13 feet long and 6.5 feet wide and is located approximately 50 feet southeast of the former service station. The finding is located within the proposed PUE and is buried approximately 4 ft bgs. Four (4) soil borings were advanced within the PUE boundary to investigate the environmental impacts on the property, including two (2) soil borings within the immediate vicinity of the underground anomaly. Petroleum impacts to Site soils were not identified during field screening or as part of analytical testing. Groundwater was not encountered.

The work performed herein did not identify petroleum impacts in shallow soils within the Site study area. Geosyntec anticipates a low likelihood of encountering shallow soil impacts within the proposed PUE extent. Geosyntec recommends test pitting to clarify the No Confidence anomaly identified as part of this investigation.

*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# TABLES

**Table 1**  
**Soil Boring Coordinates**  
**5114 NC 211, West End, North Carolina 27376**  
**NCDOT Parcel 43**  
**TIP: R-5726**  
**WBS: 50218.1.1**

<b>Soil Boring ID</b>	<b>Longitude</b>	<b>Latitude</b>
SB43-01-4.5-5.0	-79.570211	35.245440
SB43-02-6.5-7.0	-79.570258	35.245467
SB43-03-7.0-7.5	-79.570310	35.245576
SB43-04-7.5-8.0	-79.570347	35.245677

Note:

- 1) Coordinate datum reference: WGS 1984.

**Table 2**  
**Soil Analytical Results - TPH by UVF**  
**5114 NC 211, West End, North Carolina 27376**  
**NCDOT Parcel 43**  
**TIP: R-5726**  
**WBS: 50218.1.1**

Analyte			BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	Benzo[a]pyrene
Units			mg/kg						
UST TPH Guidance			---	50	100	---	---	---	---
Soil-to-Water MSCCs			---	---	---	---	---	---	<b>0.096</b>
Residential Soil MSCCs			---	---	---	---	---	---	<b>0.088</b>
Commercial / Industrial MSCCs			---	---	---	---	---	---	<b>0.78</b>
Sample ID	Sample Depth (ft bgs)	Sample Date							
SB43-01-4.5-5.0	4.5-5.0	8/13/2019	<0.3	<0.3	<b>0.98</b>	<b>0.98</b>	<b>0.55</b>	<0.1	<0.012
SB43-02-6.5-7.0	6.5-7.0	8/13/2019	<0.32	<0.32	<0.32	<0.32	<0.06	<0.1	<0.013
SB43-03-7.0-7.5	7.0-7.5	8/13/2019	<0.25	<0.25	<0.25	<0.25	<0.05	<0.08	<0.01
SB43-04-7.5-8.0	7.5-8.0	8/13/2019	<0.28	<0.28	<0.28	<0.28	<0.06	<0.09	<0.011

Notes:

- (1) mg/kg indicates milligrams per kilogram.
- (2) NCDEQ UST Guidance references the 26 July 2016 Guidelines for North Carolina Action Limits for Total Petroleum Hydrocarbons (TPH).
- (3) MSCC indicates North Carolina Department of Environmental Quality (NCDEQ) Underground Storage Tank (UST) Section Maximum Contaminant Concentration Levels, updated November 2016.
- (4) < indicates analyte was not detected above the laboratory method detection limit (MDL).
- (5) Detections are identified in bold.
- (6) --- indicates screening criteria not established.
- (7) UVF indicates ultraviolet fluorescence.
- (8) TPH indicates total petroleum hydrocarbons.
- (9) GRO indicates gasoline range organics.
- (10) DRO indicates diesel range organics.
- (11) PAH indicates polycyclic aromatic hydrocarbon.
- (12) BTEX indicates benzene, toluene, ethylbenzene, and xylenes.
- (13) ft. bgs indicates feet below ground surface.

**Table 3**  
**Soil Sampling Analytical Summary - VOCs**  
**5114 NC 211, West End, North Carolina 27376**  
**NCDOT Parcel 43**  
**TIP: R-5726**  
**WBS: 50218.1.1**

Analyte	NCDEQ Residential Soil Cleanup Levels MSCC	NCDEQ Industrial/ Commercial Soil Cleanup Levels MSCC	NCDEQ Soil-to-Water Maximum Contaminant MSCC	Sample ID	SB43-01	SB43-02	SB43-03	SB43-04
				Sample Date	8/13/2019	8/13/2019	8/13/2019	8/13/2019
				Sample Depth (ft. bgs)	4.5-5.0	6.5-7.0	7.0-7.5	7.5-8.0
				Sample Type	Grab			
				Units	mg/kg			
<i>Volatile Organic Compounds (VOCs) by EPA Method 8260B</i>								
Benzene	18	164	0.0056	mg/kg	< 0.0053	< 0.0073	< 0.0061	< 0.0054
Ethylbenzene	1,560	40,000	4.9	mg/kg	< 0.0053	< 0.0073	< 0.0061	< 0.0054
m,p-Xylenes	3,129	81,760	4.6	mg/kg	< 0.011	< 0.015	< 0.012	< 0.011
o-Xylene	3,129	81,760	4.6	mg/kg	< 0.0053	< 0.0073	< 0.0061	< 0.0054
Toluene	1,200	32,000	4.3	mg/kg	< 0.0053	< 0.0073	< 0.0061	< 0.0054
Xylene (total)	3,129	81,760	4.6	mg/kg	< 0.016	< 0.022	< 0.018	< 0.016

Notes:


- (1) North Carolina Department of Environmental Quality (NCDEQ) Underground Storage Tank (UST) Section Maximum Soil Contaminant Concentrations (MSCCs) as indicated in the NCDEQ UST Section *Guidelines for Site Checks, Tank Closure, and Initial Response and Abatement for UST Releases*, amended April 2012.
  - (2) VOC indicates volatile organic compound.
  - (3) mg/kg indicates milligrams per kilogram
  - (4) Concentrations exceeding MSCCs are highlighted as shown:
- |                    |                   |                      |
|--------------------|-------------------|----------------------|
| <b>Residential</b> | <b>Industrial</b> | <b>Soil-to-Water</b> |
|--------------------|-------------------|----------------------|
- (5) ft bgs indicated feet below ground surface
  - (6) < indicates analyte was not detected above the laboratory reporting limit (RL).
  - (7) Only benzene, toluene, ethylbenzene, and xylenes (BTEX) were reported.




*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*







# FIGURES




Path: \\gish01\01\MapData\NCDOT\B-5726\West End\Moore County\2019\_07\G17032\_NC211\_West End\_VSR\MXD\LEVEL\_Site\_Location\_Parcel\_43.mxd, 27 August 2019, 8:02



**Legend**

-  Soil Boring Locations
-  Approximate PUE Extent
-  No Confidence Anomaly
-  NCDOT Moore County Parcel



**Site Layout (Susan McCaskill Morgan and Others)**  
 5114 NC-211 (NCDOT Parcel 43)  
 West End, Moore County, North Carolina  
 TIP: R-5726  
 WBS: 50218.1.1

**Notes:**


1. Property boundary provided by Moore County, North Carolina GIS.
2. Aerial imagery provided by ArcMap10.5, ESRI
3. PUE indicates Public Utility Easement.
4. Soil boring locations are approximated by GPS; locations were not surveyed by a licensed surveyor.

**Geosyntec**  
 Consultants of NC, PC  
 NC License No.: C-3500

Raleigh, NC      October 2019


**Figure**  
  
**2**

Path: \\Raleigh\01\Data\IN\NCDOT\B-5726 West End Moore County\2019\_07\G17039\NC211 West End\GSA\MDA\FB\_Parcel\_43.mxd 27 August 2019 RED



LEGEND	
	EXISTING RIGHT-OF-WAY
	EXISTING PROPERTY BOUNDARY
	PROPOSED RIGHT-OF-WAY LINE
	PROPOSED PERMANENT DRAINAGE
	PROPOSED SS CUT LINE
	PROPOSED SS FILL LINE
	TEMPORARY CONSTRUCTION EASEMENT
	GEOENVIRONMENTAL BORING
	NO CONFIDENCE ANOMALY

- NOTES:**
1. PSA PERFORMED IN THE PROPOSED ROW/PUE ONLY.
  2. CONSTITUENTS ANALYZED WERE NOT DETECTED ABOVE APPLICABLE NCDEQ UST SECTION SCREENING CRITERION.



NCDOT PARCEL 43 SOIL BORING LOCATIONS 5114 HIGHWAY NC-211 WEST END, MOORE COUNTY, NORTH CAROLINA WBS: 50218.1.1 TIP: R-5726	
 consultants of NC, PC NC License No: C-3500	<b>FIGURE</b> 3
PROJECT NO: GN7039	OCTOBER 2019

45

43

L- SC STD. 52+75.77

SUSAN McCASKILL-MORGAN ET. ALS  
 DB 804 PG 548  
 L- TS STD. 51+28.77

WEST END GEMETT  
 DB 139

SB43-04

SB43-03

SB43-02

SB43-01

NO CONFIDENCE ANOMALY

TDE

TDE

TDE

RW

RW

RW

RW

RW

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

PUE

*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# APPENDIX A

## Geophysical Investigation Report



PYRAMID GEOPHYSICAL SERVICES  
(PROJECT 2019-233)

# GEOPHYSICAL SURVEY

---

## METALLIC UST INVESTIGATION: PARCEL 43 NCDOT PROJECT R-5726 (50218.1.1)

5114 N.C. 211, WEST END, NC

August 23, 2019

Report prepared for: Mr. Matt Jenny, P.E.  
Geosyntec Consultants of NC, PC  
2501 Blue Ridge Road, Suite 430  
Raleigh, NC 27607

Prepared by: \_\_\_\_\_

Eric C. Cross, P.G.  
NC License #2181

Reviewed by: \_\_\_\_\_

Douglas A. Canavello, P.G.  
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY C1251: ENGINEERING

**GEOPHYSICAL INVESTIGATION REPORT**  
**Parcel 43 - 5114 N.C. 211**  
**West End, Moore County, North Carolina**

**Table of Contents**

Executive Summary .....	1
Introduction.....	2
Field Methodology.....	2
Discussion of Results.....	3
<i>Discussion of EM Results</i> .....	3
<i>Discussion of GPR Results</i> .....	4
Summary & Conclusions .....	5
Limitations .....	5

**Figures**

- Figure 1 – Parcel 43 - Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 43 - EM61 Results Contour Map
- Figure 3 – Parcel 43 - GPR Transect Locations and Images
- Figure 4 – Parcel 43 - Location and Size of One No Confidence Anomaly
- Figure 5 – Overlay of Metal Detection Results and One No Confidence Anomaly onto NCDOT Engineering Plans

## LIST OF ACRONYMS

CADD .....	Computer Assisted Drafting and Design
DF .....	Dual Frequency
EM.....	Electromagnetic
GPR.....	Ground Penetrating Radar
GPS .....	Global Positioning System
NCDOT.....	North Carolina Department of Transportation
ROW .....	Right-of-Way
UST .....	Underground Storage Tank



## EXECUTIVE SUMMARY

---

**Project Description:** Pyramid Environmental conducted a geophysical investigation for Geosyntec Consultants of NC, PC at Parcel 43, located at 5114 N.C. 211 in West End, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project R-5726). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from July 29-31, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

**Geophysical Results:** The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. A total of four EM anomalies were identified. The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface. One metallic anomaly was associated with unknown buried metal and was investigated by GPR. GPR recorded evidence of a possible buried metallic structure or debris; however, the feature was not consistent with what would be expected for a UST. This anomaly was approximately 13 feet long and 6.5 feet wide and was classified as a No Confidence anomaly. No evidence of any additional buried structures was observed. Collectively, the geophysical data recorded evidence of one No Confidence anomaly at Parcel 43.

## INTRODUCTION

---

Pyramid Environmental conducted a geophysical investigation for Geosyntec Consultants of NC, PC at Parcel 43, located at 5114 N.C. 211 in West End, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project R-5726). The survey was designed to extend from the existing edge of pavement into the proposed ROW and/or easements, whichever distance was greater. Conducted from July 29-31, 2019, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site included a commercial building surrounded by grass, dirt and asphalt surfaces. An aerial photograph showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

## FIELD METHODOLOGY

---

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection and ground penetrating radar (GPR) surveys. Pyramid collected the EM data using a Geonics EM61-MK2 (EM61) metal detector integrated with a Geode External GPS/GLONASS receiver. The integrated GPS system allows the location of the instrument to be recorded in real-time during data collection, resulting in an EM data set that is geo-referenced and can be overlain on aerial photographs and CADD drawings. A boundary grid was established around the perimeter of the site with marks every 10 feet to maintain orientation of the instrument throughout the survey and assure complete coverage of the area.

According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8-foot intervals along north-south trending or east-west trending, generally parallel survey lines, spaced five feet apart. The data were downloaded to a

computer and reviewed in the field and office using the Geonics NAV61 and Surfer for Windows Version 15.0 software programs.

GPR data were acquired across select EM anomalies on May 10, 2019, using a Geophysical Survey Systems, Inc. (GSSI) SIR 4000 controller coupled to a 350 MHz HS antenna. Data were collected both in reconnaissance fashion as well as along formal transect lines across EM features. The GPR data were viewed in real-time using a vertical scan of 512 samples, at a rate of 48 scans per second. GPR data were viewed down to a maximum depth of approximately 6 feet, based on dielectric constants calculated by the DF unit in the field during the reconnaissance scans. GPR transects across specific anomalies were saved to the hard drive of the DF unit for post-processing and figure generation.

Pyramid’s classifications of USTs for the purposes of this report are based directly on the geophysical UST ratings provided by the NCDOT. These ratings are as follows:

Geophysical Surveys for Underground Storage Tanks on NCDOT Projects			
High Confidence	Intermediate Confidence	Low Confidence	No Confidence
<b>Known UST</b> Active tank - spatial location, orientation, and approximate depth determined by geophysics.	<b>Probable UST</b> Sufficient geophysical data from both magnetic and radar surveys that is characteristic of a tank. Interpretation may be supported by physical evidence such as fill/vent pipe, metal cover plate, asphalt/concrete patch, etc.	<b>Possible UST</b> Sufficient geophysical data from either magnetic or radar surveys that is characteristic of a tank. Additional data is not sufficient enough to confirm or deny the presence of a UST.	Anomaly noted but not characteristic of a UST. Should be noted in the text and may be called out in the figures at the geophysicist’s discretion.

## DISCUSSION OF RESULTS

### *Discussion of EM Results*

A contour plot of the EM61 results obtained across the survey area at the property is presented in **Figure 2**. Each EM anomaly is numbered for reference in the figure. The following table presents the list of EM anomalies and the cause of the metallic response, if known:

**LIST OF METALLIC ANOMALIES IDENTIFIED BY EM SURVEY**

<b>Metallic Anomaly #</b>	<b>Cause of Anomaly</b>	<b>Investigated with GPR</b>
1	Building	✓
2	Metal Poles	
3	Sign/Light	
4	<b>No Confidence Anomaly</b>	✓

The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface, including the building, metal poles, a sign and a light. EM Anomaly 4 was associated with unknown buried metal and was investigated by GPR. GPR was also performed along the east side of the building to verify that the metallic interference observed in this area did not obscure any significant buried structures such as USTs.

*Discussion of GPR Results*

**Figure 3** presents the locations of the formal GPR transects performed at the property as well as the transect images. A total of three GPR transects were performed at the property. GPR Transects 1 and 2 were performed across the known buried metal associated with EM Anomaly 4. These transects recorded minor isolated hyperbolic reflectors in both directions that were suggestive of a buried metal structure or debris. The size and shape of the possible structure was inconsistent with what would be expected for a UST. For this reason, the feature has been classified as a No Confidence anomaly. The No Confidence anomaly was approximately 13 feet long and 6.5 feet wide. **Figure 4** provides the location and size of the No Confidence anomaly overlain on an aerial photograph as well as ground-level photographs. **Figure 5** provides an overlay of the metal detection results and the No Confidence anomaly onto the NCDOT Engineering plans.

GPR Transect 3 was performed along the east side of the building, and did not record any evidence of buried structures.

Collectively, the geophysical data recorded evidence of one No Confidence anomaly at Parcel 43.

## SUMMARY & CONCLUSIONS

---

Pyramid's evaluation of the EM61 and GPR data collected at Parcel 43 in West End, North Carolina, provides the following summary and conclusions:

- The EM61 and GPR surveys provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- The majority of the EM anomalies were directly attributed to visible cultural features at the ground surface.
- One metallic anomaly was associated with unknown buried metal and was investigated by GPR.
- GPR recorded evidence of a possible buried metallic structure or debris; however, the feature was not consistent with what would be expected for a UST. This anomaly was approximately 13 feet long and 6.5 feet wide and was classified as a No Confidence anomaly.
- No evidence of any additional buried structures was observed.
- Collectively, the geophysical data recorded evidence of one No Confidence anomaly at Parcel 43.

## LIMITATIONS

---

Geophysical surveys have been performed and this report was prepared for Geosyntec Consultants of NC, PC in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.

## APPROXIMATE BOUNDARIES OF GEOPHYSICAL SURVEY AREA



View of Survey Area  
(Facing Approximately North)



View of Survey Area  
(Facing Approximately South)



503 INDUSTRIAL AVENUE  
GREENSBORO, NC 27406  
(336) 335-3174 (p) (336) 691-0648 (f)  
License # C1251 Eng. / License # C257 Geology

PROJECT  
**PARCEL 43**  
WEST END, NORTH CAROLINA  
NCDOT PROJECT R-5726

TITLE  
**PARCEL 43 - GEOPHYSICAL**  
SURVEY BOUNDARIES AND SITE PHOTOGRAPHS

DATE  
8/8/2019

PYRAMID  
PROJECT #:  
2019-233

CLIENT  
GEOSYNTEC

**FIGURE 1**


# EM61 METAL DETECTION RESULTS



## EVIDENCE OF ONE NO CONFIDENCE ANOMALY OBSERVED.

The contour plot shows the differential results of the EM61 instrument in millivolts (mV). The differential results focus on larger metallic objects such as USTs and drums. The EM data were collected on July 29, 2019, using a Geonics EM61-MK2 instrument. Verification GPR data were collected using a GSSI SIR 4000 controller with a 350 MHz HS antenna on July 31, 2019.

EM61 Metal Detection Response (millivolts)



503 INDUSTRIAL AVENUE  
GREENSBORO, NC 27406  
(336) 335-3174 (p) (336) 691-0648 (f)  
License # C1251 Eng. / License # C257 Geology


PROJECT  
**PARCEL 43**  
WEST END, NORTH CAROLINA  
NCDOT PROJECT R-5726

TITLE  
**PARCEL 43 -**  
EM61 METAL DETECTION CONTOUR MAP


DATE  
8/8/2019  
PYRAMID PROJECT #:  
2019-233

CLIENT  
GEOSYNTEC  
**FIGURE 2**


# LOCATIONS OF GPR TRANSECTS



GPR TRANSECT 1 (T1)



GPR TRANSECT 2 (T2)



GPR TRANSECT 3 (T3)



503 INDUSTRIAL AVENUE  
GREENSBORO, NC 27406  
(336) 335-3174 (p) (336) 691-0648 (f)  
License # C1251 Eng. / License # C257 Geology

PROJECT  
**PARCEL 43**  
WEST END, NORTH CAROLINA  
NCDOT PROJECT R-5726


TITLE  
**PARCEL 43 -**  
GPR TRANSECT LOCATIONS AND IMAGES

DATE  
8/8/2019  
PYRAMID PROJECT #:  
2019-233

CLIENT  
GEOSYNTEC  
**FIGURE 3**



## LOCATIONS OF ONE NO CONFIDENCE ANOMALY



View of One No Confidence Anomaly  
Facing Approximately East



View of One No Confidence Anomaly  
Facing Approximately North



503 INDUSTRIAL AVENUE  
GREENSBORO, NC 27406  
(336) 335-3174 (p) (336) 691-0648 (f)  
License # C1251 Eng. / License # C257 Geology

PROJECT  
**PARCEL 43**  
WEST END, NORTH CAROLINA  
NCDOT PROJECT R-5726


TITLE  
**PARCEL 43 - LOCATION AND SIZE OF  
ONE NO CONFIDENCE ANOMALY**

DATE  
8/8/2019

PYRAMID  
PROJECT #:  
2019-233

CLIENT  
GEOSYNTEC

**FIGURE 4**



**LEGEND**


- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW LINE
- TEMPORARY CONSTRUCTION EASEMENT
- PROPOSED PERMANENT DRAINAGE
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE
- NO CONFIDENCE ANOMALY

**MILLIVOLTS (mV)**



**EM61 METAL DETECTION  
CONTOURS (SEE FIGURE 2  
FOR ANOMALY LABELS)**

**ONE NO CONFIDENCE ANOMALY**



TITLE OVERLAY OF METAL DETECTION RESULTS AND ONE NO CONFIDENCE ANOMALY ON NCDOT ENGINEERING PLANS	
PROJECT PARCEL 43 WEST END, NORTH CAROLINA NCDOT PROJECT R-5726	
503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 08-20-2019	REVISION NO. 0
PYRAMID PROJECT NO. 2019-233	FIGURE NO. 5

*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# APPENDIX B

## Photographic Log

**GEOSYNTEC CONSULTANTS**  
**Photographic Record**

**Client: NCDOT**

**Project Number: GN7039**

**Site Name: R-5726 - Parcel 43**

**Site Location: 5114 NC 211, West End, NC**

**Photograph 1**

**Date: 29 July 2019**

**Direction: SW**

**Comments: View of the northeastern side of the Site building.**



**Photograph 2**

**Date: 29 July 2019**

**Direction: W**

**Comments: View of the northeastern NCDOT boundary poles within the ROW and the inaccessible forest area to the south of the Site building.**



**GEOSYNTEC CONSULTANTS**  
**Photographic Record**

**Client: NCDOT**

**Project Number: GN7039**

**Site Name: R-5726 - Parcel 43**

**Site Location: 5114 NC 211, West End, NC**

**Photograph 3**

**Date: 29 July 2019**

**Direction: E**

**Comments: View of the back (western) side of the Site building. Located beyond the proposed ROW.**



**Photograph 4**

**Date: 29 July 2019**

**Direction: W**

**Comments: View of the southeastern side of the Site building with overhead powerlines.**



**GEOSYNTEC CONSULTANTS**  
**Photographic Record**

**Client: NCDOT**

**Project Number: GN7039**

**Site Name: R-5726 - Parcel 43**

**Site Location: 5114 NC 211, West End, NC**

**Photograph 5**

**Date: 29 July 2019**

**Direction: NW**

**Comments: View of the western side of the Site building.**



**Photograph 6**

**Date: 29 July 2019**

**Direction: E**

**Comments: Inside view of the Site building from the northern side window.**



*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# APPENDIX C

## Soil Boring Logs

DRILLING CO.: <u>Saedaco</u>		Status: <input type="checkbox"/> Well Installed <input type="checkbox"/> Plugged & Abnd. <input type="checkbox"/>	SITE: <u>Mass Pond</u>		Borehole Location Sketch Map				
METHOD & TOOLS: <u>DPT</u>			PROJECT NO.: <u>GN7039</u>						
RIG: <u>Geoprobe 7822DT</u>		N: _____ E: _____							
BIT DIAMETER: <u>2 1/4"</u>		DRILLER: <u>Brian T</u>		SUPERVISOR: <u>M Wang</u>					
GROUND ELEV.: <input type="checkbox"/> Surveyed <input type="checkbox"/> Estimated		DATE: <u>8/13/19</u>							
Top (Depth)	<input type="checkbox"/> Feet <input type="checkbox"/> Meters	Lithology Log	Graphic Log	Depth Scale	Well	SPT Blows/6*	Run (No.)	Rec. (%)	Drilling Log
0-5		0-0.5 ft, gray silt, dry, loose 0.5-2 ft, gray silt, dry-moist, loose 2-3 ft, brown sand, fine-medium, dry, loose, poor sorted 3-5 ft, brown sand, fine-medium, dry-moist, loose-compact, poor sorted with fine sand						100	Hand Auger PZD = 0.9 ppm @ 0.5 ft PZD = 0.3 ppm @ 1.5 ft
5-10		6.5-8 ft, sand & silt, some plastic, moist, brown color 8-10 ft, saprolite, reddish color, low-medium plastic, moist. samples are collected from 4.5-5 ft @ 1340 SB43-01-4.5-5						70	PZD = 0

MW



DRILLING CO.: <u>Saedaco</u>	Status: <input type="checkbox"/> Well Installed <input type="checkbox"/> Plugged & Abnd. <input type="checkbox"/>	SITE: <u>West End</u>	Borehole Location Sketch Map
METHOD & TOOLS: <u>DPT</u>		PROJECT NO.: <u>GN7039</u>	
RIG: <u>Geoprobe 782201</u>		N: _____ E: _____	
BIT DIAMETER: <u>2 1/4"</u> DRILLER: <u>Brian J</u>		SUPERVISOR: <u>M Wang</u>	
GROUND ELEV.: <input type="checkbox"/> Surveyed <input type="checkbox"/> Estimated		DATE: <u>8/13/19</u>	

Top (Depth)	<input type="checkbox"/> Feet <input type="checkbox"/> Meters	Lithology Log	Graphic Log	Depth Scale	Well	SPT Blows/6*	Run (No.)	Rec. (%)	Drilling Log
<u>0-5 ft</u>		<u>0-1.5ft, light grey / brown sand, fine, dry, loose</u>							<u>100 PWD=0 Hand Auger</u>
		<u>1.5-5ft, brown sand, fine-medium, loose, poorly sorted</u>							
<u>5-10 ft</u>		<u>5-6.5ft, not recovered</u>							<u>70 PWD=0</u>
		<u>6.5-7ft, brown sand, fine to medium, loose, dry</u>							
		<u>7-10ft, saprolite, reddish sand, mixed with some clay &amp; gravel, hard, low plastic, dry-moist</u>							
		<u>Samples are collected from</u>							
		<u>6.5-7ft @ 1400</u>							
		<u>SB43-02-6.5-7</u>							

*MW*

DRILLING CO.: <u>Saedawo</u>	Status: <input type="checkbox"/> Well Installed <input type="checkbox"/> Plugged & Abnd.	SITE: <u>West End</u>	Borehole Location Sketch Map
METHOD & TOOLS: <u>DPT</u>		PROJECT NO.: <u>GN7039</u>	
RIG: <u>Geoprobe 7822DT</u>	N: _____ E: _____		
BIT DIAMETER: <u>2 1/4"</u> DRILLER: <u>Brian T</u>	SUPERVISOR: <u>M Wang</u>		
GROUND ELEV.: <input type="checkbox"/> Surveyed <input type="checkbox"/> Estimated	DATE: <u>8/13/19</u>		

Top (Depth)	<input type="checkbox"/> Feet <input type="checkbox"/> Meters	Lithology Log	Graphic Log	Depth Scale	Well	SPT Blows/6"	Run (No.)	Rec. (%)	Drilling Log
0- <del>3</del> ft		0-1 ft, light grey sand, fine, dry, loose						100	Hand Auger PTD = 0
		1- <del>3</del> ft, brown sand, fine to medium, dry-moist, loose, poor sorted							
<del>0</del> 3-5 ft		Saprolite, brown sand, with reddish clay & gravels, Dry-moist, hard						100	PTD = 0
5-10 ft		5-5.5 ft no recovery 5.5-10 ft, same as interval 3-5 ft.							
		Samples are collected from 7-7.5 ft @ 1430 SB43-03-7-7.5 @							

*MW*

DRILLING CO.: <u>Sandaco</u>		Status: <input type="checkbox"/> Well Installed <input type="checkbox"/> Plugged & Abnd. <input type="checkbox"/>	SITE: <u>West End</u>		Borehole Location Sketch Map
METHOD & TOOLS: <u>DPT</u>			PROJECT NO.: <u>GN7039</u>		
RIG: <u>Geoprobe 7822DT</u>		N: _____ E: _____			
BIT DIAMETER: <u>2 1/4"</u>		SUPERVISOR: <u>M Wang</u>			
GROUND ELEV.: <input type="checkbox"/> Surveyed <input type="checkbox"/> Estimated		DATE: <u>8/13/19</u>			

Top (Depth)	<input type="checkbox"/> Feet <input type="checkbox"/> Meters	Lithology Log	Graphic Log	Depth Scale	Well	SPT Blows/6'	Run (No.)	Rec. (%)	Drilling Log
<u>0-5 ft</u>		<p>0-1 ft. light gray sand, fines, dry, loose</p> <p><del>1-3</del> 1-4.5 ft. brown sand, fine to medium, dry-moist, loose poorly sorted.</p> <p>4.5-5 ft. brown sand, mixed with some gray clay. Fine-medium, dry-moist, loose.</p>							<p>100% Hard Auger P20=0</p>
<u>5-10 ft</u>		<p>saprolite, brown sand, mixed with reddish clay &amp; gravels.</p> <p>Dry-moist, hard, low plastic.</p> <p>Samples are collected from 7.5-8 ft @ 1445 SB43-04-7.5-8</p>						100	P20=0

*MW*

*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# APPENDIX D

## Red Lab UVF Report



### Hydrocarbon Analysis Results

**Client:** GEOSYNTEC  
**Address:** 2501 BLUE RIDGE RD  
 SUITE 430 RALEIGH, NC

**Samples taken** Monday, August 12, 2019  
**Samples extracted** Monday, August 12, 2019  
**Samples analysed** Friday, August 16, 2019

**Contact:** MICHAEL WANG

**Operator** CAROLINE STEVENS





**Project:** R5726

													H09382
Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	% Ratios			HC Fingerprint Match
										C5 - C10	C10 - C18	C18	
s	SB43-01-4.5-5.0	12.2	<0.3	<0.3	0.98	0.98	0.55	<0.1	<0.012	0	63.9	36.1	V.Deg.PHC 91.8%,(FCM),(BO),(P)
s	SB43-02-6.5-7.0	12.7	<0.32	<0.32	<0.32	<0.32	<0.06	<0.1	<0.013	0	100	0	(FCM)
s	SB43-03-7-7.5	10.1	<0.25	<0.25	<0.25	<0.25	<0.05	<0.08	<0.01	0	100	0	Residual HC,(BO)
s	SB43-04-7.5-8.0	11.0	<0.28	<0.28	<0.28	<0.28	<0.06	<0.09	<0.011	0	100	0	(FCM),(P)
Initial Calibrator QC check			OK		Final FCM QC Check			OK		95.7 %			

Concentration values in mg/kg for soil samples and mg/L for water samples. Soil values uncorrected for moisture or stone content. Fingerprints provide a tentative hydrocarbon identification.  
 Abbreviations :- FCM = Results calculated using Fundamental Calibration Mode : % = confidence of hydrocarbon identification : (PFM) = Poor Fingerprint Match : (T) = Turbid : (P) = Particulate detected  
 B = Blank Drift : (SBS)/(LBS) = Site Specific or Library Background Subtraction applied to result : (BO) = Background Organics detected : (OCR) = Outside cal range : (M) = Modified Result.  
 % Ratios estimated aromatic carbon number proportions : HC = Hydrocarbon : PHC = Petroleum HC : FP = Fingerprint only. **Data generated by HC-1 Analyser**

QED Hydrocarbon Fingerprints

Project: R5726



*Preliminary Site Assessment (Parcel 43 – Susan McCaskill Morgan and Others)  
TIP Number R-5726  
5114 NC 211, West End, North Carolina  
October 2019*



# APPENDIX E

## Prism Laboratories Analytical Report



Full-Service Analytical & Environmental Solutions

NC Certification No. 402  
NC Drinking Water Cert No. 37735  
SC Certification No. 99012

# Case Narrative

8/28/19 11:20

Geosyntec Consultants of NC, PC - Raleigh  
Michael Wang  
2501 Blue Ridge Road, Ste 430  
Raleigh, NC 27607

Project: NCDOT R-5726 West End  
Project No.: GN7039  
Lab Submittal Date: 08/16/2019  
Prism Work Order: 9080260

This data package contains the analytical results for the project identified above and includes a Case Narrative, Sample Results and Chain of Custody. Unless otherwise noted, all samples were received in acceptable condition and processed according to the referenced methods.

Data qualifiers are flagged individually on each sample. A key reference for the data qualifiers appears at the end of this case narrative.

Please call if you have any questions relating to this analytical report.

Respectfully,

**PRISM LABORATORIES, INC.**

Robbi A. Jones  
President/Project Manager

Reviewed By Robbi A. Jones  
President/Project Manager

**Data Qualifiers Key Reference:**

- SR Surrogate recovery outside the QC limits.
- BRL Below Reporting Limit
- MDL Method Detection Limit
- RPD Relative Percent Difference
- \* Results reported to the reporting limit. All other results are reported to the MDL with values between MDL and reporting limit indicated with a J.

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

449 Springbrook Road - P.O. Box 240543 - Charlotte, NC 28224-0543  
Phone: 704/529-6364 - Toll Free Number: 1-800/529-6364 - Fax: 704/525-0409





Client Sample ID	Lab Sample ID	Matrix	Date/Time Sampled	Date/Time Received
SB13-01-7.5-8.0	9080260-01	Solid	08/12/19 10:30	08/16/19 9:15
SB13-02-7-7.5	9080260-02	Solid	08/12/19 11:00	08/16/19 9:15
SB13-03-6.5-7.0	9080260-03	Solid	08/12/19 11:30	08/16/19 9:15
SB43-01-4.5-5.0	9080260-04	Solid	08/13/19 13:40	08/16/19 9:15
SB43-02-6.5-7.0	9080260-05	Solid	08/13/19 14:00	08/16/19 9:15
SB43-03-7.0-7.5	9080260-06	Solid	08/13/19 14:30	08/16/19 9:15
SB43-04-7.5-8.0	9080260-07	Solid	08/13/19 14:45	08/16/19 9:15
SB66867-01-5-5.5	9080260-08	Solid	08/13/19 8:40	08/16/19 9:15
SB66867-02-4.0-4.5	9080260-09	Solid	08/13/19 9:10	08/16/19 9:15
SB66867-03-6.5-7	9080260-10	Solid	08/13/19 10:20	08/16/19 9:15
SB66867-04-5.5-6.0	9080260-11	Solid	08/13/19 9:45	08/16/19 9:15
SB66867-05-7-7.5	9080260-12	Solid	08/13/19 11:10	08/16/19 9:15
SB66867-06-7.5-8	9080260-13	Solid	08/13/19 12:20	08/16/19 9:15
SB69-01-6.0-6.5	9080260-14	Solid	08/12/19 13:00	08/16/19 9:15
SB69-02-4.0-4.5	9080260-15	Solid	08/12/19 13:30	08/16/19 9:15
SB69-03-5.0-5.5	9080260-16	Solid	08/12/19 14:00	08/16/19 9:15
SB69-04-5.0-5.5	9080260-17	Solid	08/12/19 14:45	08/16/19 9:15
SB69-05-9.5-10	9080260-18	Solid	08/12/19 15:25	08/16/19 9:15
SB69-06-9-9.5	9080260-19	Solid	08/12/19 16:15	08/16/19 9:15
SB69-07-5.0-5.5	9080260-20	Solid	08/12/19 16:45	08/16/19 9:15
SB69-08-6.0-6.5	9080260-21	Solid	08/13/19 13:00	08/16/19 9:15
SB78-01-7-7.5	9080260-22	Solid	08/13/19 15:50	08/16/19 9:15
SB78-02-5.5-6	9080260-23	Solid	08/14/19 8:25	08/16/19 9:15
SB78-03-6-6.5	9080260-24	Solid	08/14/19 9:00	08/16/19 9:15
SB78-04-6.5-7	9080260-25	Solid	08/14/19 9:30	08/16/19 9:15
SB89-01-5-5.5	9080260-26	Solid	08/15/19 9:00	08/16/19 9:15
SB89-02-5.5-6	9080260-27	Solid	08/15/19 9:40	08/16/19 9:15
SB89-03-6.5-7	9080260-28	Solid	08/15/19 10:30	08/16/19 9:15
SB89-04-7-7.5	9080260-29	Solid	08/15/19 11:30	08/16/19 9:15
SB102-01-2.5-3	9080260-30	Solid	08/14/19 10:50	08/16/19 9:15
SB102-02-5.5-6	9080260-31	Solid	08/14/19 11:35	08/16/19 9:15
SB102-03-7-7.5	9080260-32	Solid	08/14/19 13:00	08/16/19 9:15
SB102-04-7.5-8	9080260-33	Solid	08/14/19 13:30	08/16/19 9:15

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

SB102-05-4.5-5	9080260-34	Solid	08/14/19 14:00	08/16/19 9:15
SB102-06-0.5-1	9080260-35	Solid	08/14/19 14:50	08/16/19 9:15
SB102-07-7.5-8	9080260-36	Solid	08/14/19 15:35	08/16/19 9:15
SB102-08-8-8.5	9080260-37	Solid	08/14/19 16:05	08/16/19 9:15
SB102-09-8.5-9	9080260-38	Solid	08/14/19 16:45	08/16/19 9:15
SB102-10-9-9.5	9080260-39	Solid	08/14/19 17:20	08/16/19 9:15

---

Samples were received in good condition at 3.3 degrees C unless otherwise noted.

---

Prism ID	Client ID	Parameter	Method	Result	Units
----------	-----------	-----------	--------	--------	-------

---

**There were no detections reported.**

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB13-01-7.5-8.0  
 Prism Sample ID: 9080260-01  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 10:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	91.0	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0071	0.0011	1	8260D	8/20/19 17:51	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0071	0.0011	1	8260D	8/20/19 17:51	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.014	0.0018	1	8260D	8/20/19 17:51	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0071	0.00075	1	8260D	8/20/19 17:51	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0071	0.0011	1	8260D	8/20/19 17:51	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.021	0.0025	1	8260D	8/20/19 17:51	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	112 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB13-02-7-7.5  
 Prism Sample ID: 9080260-02  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 11:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	86.2	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0069	0.0011	1	8260D	8/20/19 18:21	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0069	0.0010	1	8260D	8/20/19 18:21	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.014	0.0018	1	8260D	8/20/19 18:21	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0069	0.00074	1	8260D	8/20/19 18:21	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0069	0.0011	1	8260D	8/20/19 18:21	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.021	0.0025	1	8260D	8/20/19 18:21	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	98 %	70-130
Dibromofluoromethane	114 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB13-03-6.5-7.0  
 Prism Sample ID: 9080260-03  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 11:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	95.0	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0051	0.00079	1	8260D	8/20/19 18:51	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0051	0.00077	1	8260D	8/20/19 18:51	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.010	0.0013	1	8260D	8/20/19 18:51	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0051	0.00054	1	8260D	8/20/19 18:51	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0051	0.00081	1	8260D	8/20/19 18:51	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.015	0.0018	1	8260D	8/20/19 18:51	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	116 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB43-01-4.5-5.0  
 Prism Sample ID: 9080260-04  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 13:40  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	97.8	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0053	0.00083	1	8260D	8/20/19 19:21	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0053	0.00080	1	8260D	8/20/19 19:21	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/20/19 19:21	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0053	0.00056	1	8260D	8/20/19 19:21	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0053	0.00084	1	8260D	8/20/19 19:21	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.016	0.0019	1	8260D	8/20/19 19:21	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	113 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB43-02-6.5-7.0  
 Prism Sample ID: 9080260-05  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 14:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	91.4	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0073	0.0011	1	8260D	8/22/19 15:18	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0073	0.0011	1	8260D	8/22/19 15:18	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.015	0.0019	1	8260D	8/22/19 15:18	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0073	0.00077	1	8260D	8/22/19 15:18	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0073	0.0012	1	8260D	8/22/19 15:18	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.022	0.0026	1	8260D	8/22/19 15:18	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	127 %	84-123
Toluene-d8	93 %	76-129



Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB43-03-7.0-7.5  
 Prism Sample ID: 9080260-06  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 14:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	75.6	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0061	0.00095	1	8260D	8/20/19 20:21	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0061	0.00091	1	8260D	8/20/19 20:21	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0016	1	8260D	8/20/19 20:21	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0061	0.00065	1	8260D	8/20/19 20:21	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0061	0.00097	1	8260D	8/20/19 20:21	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.018	0.0022	1	8260D	8/20/19 20:21	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	120 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB43-04-7.5-8.0  
 Prism Sample ID: 9080260-07  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 14:45  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	84.1	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0054	0.00085	1	8260D	8/20/19 20:51	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0054	0.00082	1	8260D	8/20/19 20:51	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/20/19 20:51	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0054	0.00058	1	8260D	8/20/19 20:51	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0054	0.00086	1	8260D	8/20/19 20:51	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.016	0.0020	1	8260D	8/20/19 20:51	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	101 %	70-130
Dibromofluoromethane	119 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB66867-01-5-5.5  
 Prism Sample ID: 9080260-08  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 08:40  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	90.8	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0050	0.00078	1	8260D	8/20/19 21:21	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0050	0.00075	1	8260D	8/20/19 21:21	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.010	0.0013	1	8260D	8/20/19 21:21	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0050	0.00053	1	8260D	8/20/19 21:21	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0050	0.00080	1	8260D	8/20/19 21:21	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.015	0.0018	1	8260D	8/20/19 21:21	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	122 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB66867-02-4.0-4.5  
 Prism Sample ID: 9080260-09  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 09:10  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	86.8	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0061	0.00096	1	8260D	8/20/19 21:51	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0061	0.00092	1	8260D	8/20/19 21:51	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0016	1	8260D	8/20/19 21:51	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0061	0.00065	1	8260D	8/20/19 21:51	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0061	0.00098	1	8260D	8/20/19 21:51	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.018	0.0022	1	8260D	8/20/19 21:51	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	118 %	84-123
Toluene-d8	97 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
Attn: Michael Wang  
2501 Blue Ridge Road, Ste 430  
Raleigh, NC 27607

Project: NCDOT R-5726 West End  
Project No.: GN7039  
Sample Matrix: Solid

Client Sample ID: SB66867-03-6.5-7  
Prism Sample ID: 9080260-10  
Prism Work Order: 9080260  
Time Collected: 08/13/19 10:20  
Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	90.8	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0059	0.00092	1	8260D	8/20/19 22:20	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0059	0.00088	1	8260D	8/20/19 22:20	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/20/19 22:20	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0059	0.00063	1	8260D	8/20/19 22:20	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0059	0.00094	1	8260D	8/20/19 22:20	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.018	0.0021	1	8260D	8/20/19 22:20	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	120 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB66867-04-5.5-6.0  
 Prism Sample ID: 9080260-11  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 09:45  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	94.1	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0056	0.00088	1	8260D	8/20/19 22:50	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0056	0.00085	1	8260D	8/20/19 22:50	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/20/19 22:50	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0056	0.00060	1	8260D	8/20/19 22:50	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0056	0.00090	1	8260D	8/20/19 22:50	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.017	0.0020	1	8260D	8/20/19 22:50	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	97 %	70-130
Dibromofluoromethane	118 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB66867-05-7-7.5  
 Prism Sample ID: 9080260-12  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 11:10  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	89.3	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0060	0.00094	1	8260D	8/20/19 23:20	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0060	0.00091	1	8260D	8/20/19 23:20	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/20/19 23:20	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0060	0.00064	1	8260D	8/20/19 23:20	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0060	0.00096	1	8260D	8/20/19 23:20	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.018	0.0022	1	8260D	8/20/19 23:20	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	119 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB66867-06-7.5-8  
 Prism Sample ID: 9080260-13  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 12:20  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	89.0	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0049	0.00076	1	8260D	8/19/19 16:12	JLB	P9H0310
Ethylbenzene	BRL	mg/kg dry	0.0049	0.00074	1	8260D	8/19/19 16:12	JLB	P9H0310
m,p-Xylenes	BRL	mg/kg dry	0.0098	0.0013	1	8260D	8/19/19 16:12	JLB	P9H0310
o-Xylene	BRL	mg/kg dry	0.0049	0.00052	1	8260D	8/19/19 16:12	JLB	P9H0310
Toluene	BRL	mg/kg dry	0.0049	0.00078	1	8260D	8/19/19 16:12	JLB	P9H0310
Xylenes, total	BRL	mg/kg dry	0.015	0.0018	1	8260D	8/19/19 16:12	JLB	P9H0310

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	110 %	84-123
Toluene-d8	97 %	76-129



Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-01-6.0-6.5  
 Prism Sample ID: 9080260-14  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 13:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	90.5	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0052	0.00081	1	8260D	8/21/19 19:41	JLB	P9H0366
Ethylbenzene	BRL	mg/kg dry	0.0052	0.00078	1	8260D	8/21/19 19:41	JLB	P9H0366
m,p-Xylenes	BRL	mg/kg dry	0.010	0.0013	1	8260D	8/21/19 19:41	JLB	P9H0366
o-Xylene	BRL	mg/kg dry	0.0052	0.00055	1	8260D	8/21/19 19:41	JLB	P9H0366
Toluene	BRL	mg/kg dry	0.0052	0.00082	1	8260D	8/21/19 19:41	JLB	P9H0366
Xylenes, total	BRL	mg/kg dry	0.016	0.0019	1	8260D	8/21/19 19:41	JLB	P9H0366

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	123 %	84-123
Toluene-d8	92 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-02-4.0-4.5  
 Prism Sample ID: 9080260-15  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 13:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	95.0	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0080	0.0012	1	8260D	8/21/19 0:20	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0080	0.0012	1	8260D	8/21/19 0:20	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.016	0.0020	1	8260D	8/21/19 0:20	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0080	0.00085	1	8260D	8/21/19 0:20	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0080	0.0013	1	8260D	8/21/19 0:20	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.024	0.0029	1	8260D	8/21/19 0:20	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	122 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-03-5.0-5.5  
 Prism Sample ID: 9080260-16  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 14:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	93.2	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0043	0.00067	1	8260D	8/21/19 0:49	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0043	0.00064	1	8260D	8/21/19 0:49	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.0086	0.0011	1	8260D	8/21/19 0:49	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0043	0.00046	1	8260D	8/21/19 0:49	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0043	0.00068	1	8260D	8/21/19 0:49	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.013	0.0015	1	8260D	8/21/19 0:49	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	121 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-04-5.0-5.5  
 Prism Sample ID: 9080260-17  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 14:45  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	92.2	% by Weight	0.100	0.100	1	*SM2540 G	8/22/19 10:22	EDV	P9H0353
----------	------	-------------	-------	-------	---	-----------	---------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0049	0.00076	1	8260D	8/21/19 1:19	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0049	0.00074	1	8260D	8/21/19 1:19	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.0098	0.0013	1	8260D	8/21/19 1:19	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0049	0.00052	1	8260D	8/21/19 1:19	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0049	0.00078	1	8260D	8/21/19 1:19	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.015	0.0018	1	8260D	8/21/19 1:19	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	123 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-05-9.5-10  
 Prism Sample ID: 9080260-18  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 15:25  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	91.0	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0056	0.00088	1	8260D	8/21/19 1:50	JLB	P9H0347
Ethylbenzene	BRL	mg/kg dry	0.0056	0.00084	1	8260D	8/21/19 1:50	JLB	P9H0347
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/21/19 1:50	JLB	P9H0347
o-Xylene	BRL	mg/kg dry	0.0056	0.00060	1	8260D	8/21/19 1:50	JLB	P9H0347
Toluene	BRL	mg/kg dry	0.0056	0.00089	1	8260D	8/21/19 1:50	JLB	P9H0347
Xylenes, total	BRL	mg/kg dry	0.017	0.0020	1	8260D	8/21/19 1:50	JLB	P9H0347

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	119 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-06-9-9.5  
 Prism Sample ID: 9080260-19  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 16:15  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	87.3	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0046	0.00072	1	8260D	8/22/19 15:47	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0046	0.00069	1	8260D	8/22/19 15:47	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.0092	0.0012	1	8260D	8/22/19 15:47	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0046	0.00049	1	8260D	8/22/19 15:47	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0046	0.00073	1	8260D	8/22/19 15:47	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.014	0.0017	1	8260D	8/22/19 15:47	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	125 %	84-123
Toluene-d8	92 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-07-5.0-5.5  
 Prism Sample ID: 9080260-20  
 Prism Work Order: 9080260  
 Time Collected: 08/12/19 16:45  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	93.3	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0051	0.00080	1	8260D	8/22/19 16:17	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0051	0.00077	1	8260D	8/22/19 16:17	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.010	0.0013	1	8260D	8/22/19 16:17	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0051	0.00055	1	8260D	8/22/19 16:17	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0051	0.00082	1	8260D	8/22/19 16:17	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.015	0.0019	1	8260D	8/22/19 16:17	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	127 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB69-08-6.0-6.5  
 Prism Sample ID: 9080260-21  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 13:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	85.7	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0060	0.00094	1	8260D	8/26/19 19:27	JLB	P9H0434
Ethylbenzene	BRL	mg/kg dry	0.0060	0.00091	1	8260D	8/26/19 19:27	JLB	P9H0434
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/26/19 19:27	JLB	P9H0434
o-Xylene	BRL	mg/kg dry	0.0060	0.00064	1	8260D	8/26/19 19:27	JLB	P9H0434
Toluene	BRL	mg/kg dry	0.0060	0.00096	1	8260D	8/26/19 19:27	JLB	P9H0434
Xylenes, total	BRL	mg/kg dry	0.018	0.0022	1	8260D	8/26/19 19:27	JLB	P9H0434

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	112 %	70-130
Dibromofluoromethane	96 %	84-123
Toluene-d8	101 %	76-129



Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB78-01-7-7.5  
 Prism Sample ID: 9080260-22  
 Prism Work Order: 9080260  
 Time Collected: 08/13/19 15:50  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	83.4	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0053	0.00082	1	8260D	8/22/19 17:34	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0053	0.00079	1	8260D	8/22/19 17:34	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0013	1	8260D	8/22/19 17:34	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0053	0.00056	1	8260D	8/22/19 17:34	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0053	0.00084	1	8260D	8/22/19 17:34	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.016	0.0019	1	8260D	8/22/19 17:34	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	132 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB78-02-5.5-6  
 Prism Sample ID: 9080260-23  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 08:25  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	97.8	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0043	0.00067	1	8260D	8/19/19 16:42	JLB	P9H0310
Ethylbenzene	BRL	mg/kg dry	0.0043	0.00065	1	8260D	8/19/19 16:42	JLB	P9H0310
Isopropylbenzene (Cumene)	BRL	mg/kg dry	0.0043	0.00050	1	8260D	8/19/19 16:42	JLB	P9H0310
m,p-Xylenes	BRL	mg/kg dry	0.0086	0.0011	1	8260D	8/19/19 16:42	JLB	P9H0310
o-Xylene	BRL	mg/kg dry	0.0043	0.00046	1	8260D	8/19/19 16:42	JLB	P9H0310
Toluene	BRL	mg/kg dry	0.0043	0.00068	1	8260D	8/19/19 16:42	JLB	P9H0310
Xylenes, total	BRL	mg/kg dry	0.013	0.0015	1	8260D	8/19/19 16:42	JLB	P9H0310

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	109 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB78-03-6-6.5  
 Prism Sample ID: 9080260-24  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 09:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	85.2	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0068	0.0011	1	8260D	8/19/19 17:12	JLB	P9H0310
Ethylbenzene	BRL	mg/kg dry	0.0068	0.0010	1	8260D	8/19/19 17:12	JLB	P9H0310
m,p-Xylenes	BRL	mg/kg dry	0.014	0.0017	1	8260D	8/19/19 17:12	JLB	P9H0310
o-Xylene	BRL	mg/kg dry	0.0068	0.00072	1	8260D	8/19/19 17:12	JLB	P9H0310
Toluene	BRL	mg/kg dry	0.0068	0.0011	1	8260D	8/19/19 17:12	JLB	P9H0310
Xylenes, total	BRL	mg/kg dry	0.020	0.0024	1	8260D	8/19/19 17:12	JLB	P9H0310

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	110 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB78-04-6.5-7  
 Prism Sample ID: 9080260-25  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 09:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	85.1	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0062	0.00097	1	8260D	8/22/19 18:04	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0062	0.00093	1	8260D	8/22/19 18:04	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0016	1	8260D	8/22/19 18:04	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0062	0.00066	1	8260D	8/22/19 18:04	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0062	0.00099	1	8260D	8/22/19 18:04	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.019	0.0022	1	8260D	8/22/19 18:04	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	98 %	70-130
Dibromofluoromethane	130 %	84-123
Toluene-d8	93 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB89-01-5-5.5  
 Prism Sample ID: 9080260-26  
 Prism Work Order: 9080260  
 Time Collected: 08/15/19 09:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	96.3	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0056	0.00088	1	8260D	8/22/19 18:34	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0056	0.00085	1	8260D	8/22/19 18:34	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/22/19 18:34	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0056	0.00060	1	8260D	8/22/19 18:34	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0056	0.00090	1	8260D	8/22/19 18:34	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.017	0.0020	1	8260D	8/22/19 18:34	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	98 %	70-130
Dibromofluoromethane	127 %	84-123
Toluene-d8	94 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB89-02-5.5-6  
 Prism Sample ID: 9080260-27  
 Prism Work Order: 9080260  
 Time Collected: 08/15/19 09:40  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	96.6	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0066	0.0010	1	8260D	8/22/19 19:04	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0066	0.0010	1	8260D	8/22/19 19:04	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.013	0.0017	1	8260D	8/22/19 19:04	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0066	0.00070	1	8260D	8/22/19 19:04	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0066	0.0011	1	8260D	8/22/19 19:04	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.020	0.0024	1	8260D	8/22/19 19:04	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	135 %	84-123
Toluene-d8	93 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB89-03-6.5-7  
 Prism Sample ID: 9080260-28  
 Prism Work Order: 9080260  
 Time Collected: 08/15/19 10:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	92.2	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0065	0.0010	1	8260D	8/22/19 19:34	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0065	0.00098	1	8260D	8/22/19 19:34	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.013	0.0017	1	8260D	8/22/19 19:34	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0065	0.00069	1	8260D	8/22/19 19:34	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0065	0.0010	1	8260D	8/22/19 19:34	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.019	0.0023	1	8260D	8/22/19 19:34	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	128 %	84-123
Toluene-d8	90 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB89-04-7-7.5  
 Prism Sample ID: 9080260-29  
 Prism Work Order: 9080260  
 Time Collected: 08/15/19 11:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	93.9	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0062	0.00097	1	8260D	8/22/19 20:03	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0062	0.00094	1	8260D	8/22/19 20:03	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0016	1	8260D	8/22/19 20:03	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0062	0.00066	1	8260D	8/22/19 20:03	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0062	0.00099	1	8260D	8/22/19 20:03	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.019	0.0022	1	8260D	8/22/19 20:03	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	98 %	70-130
Dibromofluoromethane	136 %	84-123
Toluene-d8	91 %	76-129



Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-01-2.5-3  
 Prism Sample ID: 9080260-30  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 10:50  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	89.8	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0069	0.0011	1	8260D	8/22/19 20:33	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0069	0.0010	1	8260D	8/22/19 20:33	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.014	0.0018	1	8260D	8/22/19 20:33	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0069	0.00073	1	8260D	8/22/19 20:33	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0069	0.0011	1	8260D	8/22/19 20:33	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.021	0.0025	1	8260D	8/22/19 20:33	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	101 %	70-130
Dibromofluoromethane	134 %	84-123
Toluene-d8	92 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-02-5.5-6  
 Prism Sample ID: 9080260-31  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 11:35  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	96.4	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0059	0.00093	1	8260D	8/22/19 21:03	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0059	0.00089	1	8260D	8/22/19 21:03	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/22/19 21:03	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0059	0.00063	1	8260D	8/22/19 21:03	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0059	0.00095	1	8260D	8/22/19 21:03	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.018	0.0021	1	8260D	8/22/19 21:03	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	100 %	70-130
Dibromofluoromethane	133 %	84-123
Toluene-d8	91 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-03-7-7.5  
 Prism Sample ID: 9080260-32  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 13:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	94.4	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0053	0.00082	1	8260D	8/22/19 21:33	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0053	0.00079	1	8260D	8/22/19 21:33	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/22/19 21:33	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0053	0.00056	1	8260D	8/22/19 21:33	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0053	0.00084	1	8260D	8/22/19 21:33	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.016	0.0019	1	8260D	8/22/19 21:33	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	99 %	70-130
Dibromofluoromethane	132 %	84-123
Toluene-d8	91 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-04-7.5-8  
 Prism Sample ID: 9080260-33  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 13:30  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	80.6	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0060	0.00094	1	8260D	8/22/19 22:03	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0060	0.00091	1	8260D	8/22/19 22:03	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/22/19 22:03	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0060	0.00064	1	8260D	8/22/19 22:03	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0060	0.00096	1	8260D	8/22/19 22:03	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.018	0.0022	1	8260D	8/22/19 22:03	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	97 %	70-130
Dibromofluoromethane	131 %	84-123
Toluene-d8	92 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-05-4.5-5  
 Prism Sample ID: 9080260-34  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 14:00  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	97.4	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0070	0.0011	1	8260D	8/22/19 22:33	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0070	0.0011	1	8260D	8/22/19 22:33	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.014	0.0018	1	8260D	8/22/19 22:33	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0070	0.00075	1	8260D	8/22/19 22:33	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0070	0.0011	1	8260D	8/22/19 22:33	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.021	0.0025	1	8260D	8/22/19 22:33	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	138 %	84-123
Toluene-d8	96 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-06-0.5-1  
 Prism Sample ID: 9080260-35  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 14:50  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	88.1	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0075	0.0012	1	8260D	8/22/19 23:02	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0075	0.0011	1	8260D	8/22/19 23:02	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.015	0.0019	1	8260D	8/22/19 23:02	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0075	0.00080	1	8260D	8/22/19 23:02	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0075	0.0012	1	8260D	8/22/19 23:02	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.022	0.0027	1	8260D	8/22/19 23:02	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	143 %	84-123
Toluene-d8	89 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-07-7.5-8  
 Prism Sample ID: 9080260-36  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 15:35  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	83.5	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0043	0.00067	1	8260D	8/22/19 23:33	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0043	0.00065	1	8260D	8/22/19 23:33	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.0086	0.0011	1	8260D	8/22/19 23:33	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0043	0.00046	1	8260D	8/22/19 23:33	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0043	0.00069	1	8260D	8/22/19 23:33	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.013	0.0016	1	8260D	8/22/19 23:33	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	102 %	70-130
Dibromofluoromethane	135 %	84-123
Toluene-d8	91 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-08-8-8.5  
 Prism Sample ID: 9080260-37  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 16:05  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	87.9	% by Weight	0.100	0.100	1	*SM2540 G	8/23/19 8:10	EDV	P9H0369
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0058	0.00090	1	8260D	8/26/19 18:57	JLB	P9H0434
Ethylbenzene	BRL	mg/kg dry	0.0058	0.00087	1	8260D	8/26/19 18:57	JLB	P9H0434
m,p-Xylenes	BRL	mg/kg dry	0.012	0.0015	1	8260D	8/26/19 18:57	JLB	P9H0434
o-Xylene	BRL	mg/kg dry	0.0058	0.00061	1	8260D	8/26/19 18:57	JLB	P9H0434
Toluene	BRL	mg/kg dry	0.0058	0.00092	1	8260D	8/26/19 18:57	JLB	P9H0434
Xylenes, total	BRL	mg/kg dry	0.017	0.0021	1	8260D	8/26/19 18:57	JLB	P9H0434

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	103 %	70-130
Dibromofluoromethane	93 %	84-123
Toluene-d8	99 %	76-129



Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-09-8.5-9  
 Prism Sample ID: 9080260-38  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 16:45  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	87.0	% by Weight	0.100	0.100	1	*SM2540 G	8/26/19 8:25	EDV	P9H0406
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0053	0.00082	1	8260D	8/23/19 0:32	JLB	P9H0389
Ethylbenzene	BRL	mg/kg dry	0.0053	0.00079	1	8260D	8/23/19 0:32	JLB	P9H0389
m,p-Xylenes	BRL	mg/kg dry	0.011	0.0014	1	8260D	8/23/19 0:32	JLB	P9H0389
o-Xylene	BRL	mg/kg dry	0.0053	0.00056	1	8260D	8/23/19 0:32	JLB	P9H0389
Toluene	BRL	mg/kg dry	0.0053	0.00084	1	8260D	8/23/19 0:32	JLB	P9H0389
Xylenes, total	BRL	mg/kg dry	0.016	0.0019	1	8260D	8/23/19 0:32	JLB	P9H0389

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	98 %	70-130
Dibromofluoromethane	140 %	84-123
Toluene-d8	95 %	76-129

Geosyntec Consultants of NC, PC - Raleigh  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430  
 Raleigh, NC 27607

Project: NCDOT R-5726 West End  
 Project No.: GN7039  
 Sample Matrix: Solid

Client Sample ID: SB102-10-9-9.5  
 Prism Sample ID: 9080260-39  
 Prism Work Order: 9080260  
 Time Collected: 08/14/19 17:20  
 Time Submitted: 08/16/19 09:15

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
-----------	--------	-------	--------------	-----	-----------------	--------	--------------------	---------	----------

### General Chemistry Parameters

% Solids	89.4	% by Weight	0.100	0.100	1	*SM2540 G	8/26/19 8:25	EDV	P9H0406
----------	------	-------------	-------	-------	---	-----------	--------------	-----	---------

### Volatile Organic Compounds by GC/MS

Benzene	BRL	mg/kg dry	0.0048	0.00075	1	8260D	8/26/19 18:27	JLB	P9H0434
Ethylbenzene	BRL	mg/kg dry	0.0048	0.00072	1	8260D	8/26/19 18:27	JLB	P9H0434
m,p-Xylenes	BRL	mg/kg dry	0.0096	0.0012	1	8260D	8/26/19 18:27	JLB	P9H0434
o-Xylene	BRL	mg/kg dry	0.0048	0.00051	1	8260D	8/26/19 18:27	JLB	P9H0434
Toluene	BRL	mg/kg dry	0.0048	0.00077	1	8260D	8/26/19 18:27	JLB	P9H0434
Xylenes, total	BRL	mg/kg dry	0.014	0.0017	1	8260D	8/26/19 18:27	JLB	P9H0434

Surrogate	Recovery	Control Limits
4-Bromofluorobenzene	104 %	70-130
Dibromofluoromethane	95 %	84-123
Toluene-d8	98 %	76-129



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
Attn: Michael Wang  
2501 Blue Ridge Road, Ste 430 Project No: GN7039  
Raleigh, NC 27607

Prism Work Order: 9080260  
Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0310 - 5035</b>										
<b>Blank (P9H0310-BLK1)</b>										
Prepared & Analyzed: 08/19/19										
1,1,1,2-Tetrachloroethane	BRL	0.0050	mg/kg wet							
1,1,1-Trichloroethane	BRL	0.0050	mg/kg wet							
1,1,2,2-Tetrachloroethane	BRL	0.0050	mg/kg wet							
1,1,2-Trichloroethane	BRL	0.0050	mg/kg wet							
1,1-Dichloroethane	BRL	0.0050	mg/kg wet							
1,1-Dichloroethylene	BRL	0.0050	mg/kg wet							
1,1-Dichloropropylene	BRL	0.0050	mg/kg wet							
1,2,3-Trichlorobenzene	BRL	0.010	mg/kg wet							
1,2,3-Trichloropropane	BRL	0.0050	mg/kg wet							
1,2,4-Trichlorobenzene	BRL	0.010	mg/kg wet							
1,2,4-Trimethylbenzene	BRL	0.0050	mg/kg wet							
1,2-Dibromoethane	BRL	0.0050	mg/kg wet							
1,2-Dichlorobenzene	BRL	0.0050	mg/kg wet							
1,2-Dichloroethane	BRL	0.0050	mg/kg wet							
1,2-Dichloropropane	BRL	0.0050	mg/kg wet							
1,3,5-Trimethylbenzene	BRL	0.0050	mg/kg wet							
1,3-Dichlorobenzene	BRL	0.0050	mg/kg wet							
1,3-Dichloropropane	BRL	0.0050	mg/kg wet							
1,4-Dichlorobenzene	BRL	0.0050	mg/kg wet							
2,2-Dichloropropane	BRL	0.0050	mg/kg wet							
2-Chlorotoluene	BRL	0.0050	mg/kg wet							
4-Chlorotoluene	BRL	0.0050	mg/kg wet							
4-Isopropyltoluene	BRL	0.0050	mg/kg wet							
Acetone	BRL	0.020	mg/kg wet							
Benzene	BRL	0.0050	mg/kg wet							
Bromobenzene	BRL	0.0050	mg/kg wet							
Bromochloromethane	BRL	0.0050	mg/kg wet							
Bromodichloromethane	BRL	0.0050	mg/kg wet							
Bromoform	BRL	0.0050	mg/kg wet							
Bromomethane	BRL	0.010	mg/kg wet							
Carbon Tetrachloride	BRL	0.0050	mg/kg wet							
Chlorobenzene	BRL	0.0050	mg/kg wet							
Chloroethane	BRL	0.010	mg/kg wet							
Chloroform	BRL	0.0050	mg/kg wet							
Chloromethane	BRL	0.010	mg/kg wet							
cis-1,2-Dichloroethylene	BRL	0.0050	mg/kg wet							
cis-1,3-Dichloropropylene	BRL	0.0050	mg/kg wet							
Dibromochloromethane	BRL	0.0050	mg/kg wet							
Dichlorodifluoromethane	BRL	0.010	mg/kg wet							
Ethylbenzene	BRL	0.0050	mg/kg wet							
Isopropyl Ether	BRL	0.0050	mg/kg wet							
Isopropylbenzene (Cumene)	BRL	0.0050	mg/kg wet							
m,p-Xylenes	BRL	0.010	mg/kg wet							
Methyl Butyl Ketone (2-Hexanone)	BRL	0.020	mg/kg wet							
Methyl Ethyl Ketone (2-Butanone)	BRL	0.020	mg/kg wet							
Methyl Isobutyl Ketone	BRL	0.020	mg/kg wet							

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0310 - 5035</b>										
<b>Blank (P9H0310-BLK1)</b>										
Prepared & Analyzed: 08/19/19										
Methylene Chloride	BRL	0.0050	mg/kg wet							
Methyl-tert-Butyl Ether	BRL	0.0050	mg/kg wet							
Naphthalene	BRL	0.010	mg/kg wet							
n-Butylbenzene	BRL	0.0050	mg/kg wet							
n-Propylbenzene	BRL	0.0050	mg/kg wet							
o-Xylene	BRL	0.0050	mg/kg wet							
sec-Butylbenzene	BRL	0.0050	mg/kg wet							
Styrene	BRL	0.0050	mg/kg wet							
tert-Butylbenzene	BRL	0.0050	mg/kg wet							
Tetrachloroethylene	BRL	0.0050	mg/kg wet							
Toluene	BRL	0.0050	mg/kg wet							
trans-1,2-Dichloroethylene	BRL	0.0050	mg/kg wet							
trans-1,3-Dichloropropylene	BRL	0.0050	mg/kg wet							
Trichloroethylene	BRL	0.0050	mg/kg wet							
Trichlorofluoromethane	BRL	0.010	mg/kg wet							
Vinyl acetate	BRL	0.010	mg/kg wet							
Vinyl chloride	BRL	0.010	mg/kg wet							
Xylenes, total	BRL	0.015	mg/kg wet							
Surrogate: 4-Bromofluorobenzene	50.9		ug/L	50.00		102	70-130			
Surrogate: Dibromofluoromethane	53.9		ug/L	50.00		108	84-123			
Surrogate: Toluene-d8	49.2		ug/L	50.00		98	76-129			
<b>LCS (P9H0310-BS1)</b>										
Prepared & Analyzed: 08/19/19										
1,1,1,2-Tetrachloroethane	0.0442	0.0050	mg/kg wet	0.05000		88	72-115			
1,1,1-Trichloroethane	0.0460	0.0050	mg/kg wet	0.05000		92	67-131			
1,1,2,2-Tetrachloroethane	0.0421	0.0050	mg/kg wet	0.05000		84	56-126			
1,1,2-Trichloroethane	0.0421	0.0050	mg/kg wet	0.05000		84	70-133			
1,1-Dichloroethane	0.0432	0.0050	mg/kg wet	0.05000		86	74-127			
1,1-Dichloroethylene	0.0394	0.0050	mg/kg wet	0.05000		79	67-149			
1,1-Dichloropropylene	0.0453	0.0050	mg/kg wet	0.05000		91	71-130			
1,2,3-Trichlorobenzene	0.0432	0.010	mg/kg wet	0.05000		86	68-130			
1,2,3-Trichloropropane	0.0419	0.0050	mg/kg wet	0.05000		84	60-137			
1,2,4-Trichlorobenzene	0.0450	0.010	mg/kg wet	0.05000		90	66-125			
1,2,4-Trimethylbenzene	0.0442	0.0050	mg/kg wet	0.05000		88	69-129			
1,2-Dibromoethane	0.0426	0.0050	mg/kg wet	0.05000		85	70-132			
1,2-Dichlorobenzene	0.0425	0.0050	mg/kg wet	0.05000		85	72-123			
1,2-Dichloroethane	0.0446	0.0050	mg/kg wet	0.05000		89	68-128			
1,2-Dichloropropane	0.0437	0.0050	mg/kg wet	0.05000		87	73-130			
1,3,5-Trimethylbenzene	0.0440	0.0050	mg/kg wet	0.05000		88	69-128			
1,3-Dichlorobenzene	0.0429	0.0050	mg/kg wet	0.05000		86	71-120			
1,3-Dichloropropane	0.0428	0.0050	mg/kg wet	0.05000		86	75-124			
1,4-Dichlorobenzene	0.0428	0.0050	mg/kg wet	0.05000		86	71-123			
2,2-Dichloropropane	0.0463	0.0050	mg/kg wet	0.05000		93	50-142			
2-Chlorotoluene	0.0437	0.0050	mg/kg wet	0.05000		87	67-124			
4-Chlorotoluene	0.0438	0.0050	mg/kg wet	0.05000		88	71-126			
4-Isopropyltoluene	0.0451	0.0050	mg/kg wet	0.05000		90	68-129			
Acetone	0.120	0.020	mg/kg wet	0.1000		120	29-198			

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0310 - 5035</b>										
<b>LCS (P9H0310-BS1)</b>										
Prepared & Analyzed: 08/19/19										
Benzene	0.0433	0.0050	mg/kg wet	0.05000		87	74-127			
Bromobenzene	0.0429	0.0050	mg/kg wet	0.05000		86	73-125			
Bromochloromethane	0.0422	0.0050	mg/kg wet	0.05000		84	72-134			
Bromodichloromethane	0.0456	0.0050	mg/kg wet	0.05000		91	75-122			
Bromoform	0.0467	0.0050	mg/kg wet	0.05000		93	66-135			
Bromomethane	0.0437	0.010	mg/kg wet	0.05000		87	20-180			
Carbon Tetrachloride	0.0464	0.0050	mg/kg wet	0.05000		93	64-143			
Chlorobenzene	0.0429	0.0050	mg/kg wet	0.05000		86	74-118			
Chloroethane	0.0420	0.010	mg/kg wet	0.05000		84	33-149			
Chloroform	0.0442	0.0050	mg/kg wet	0.05000		88	73-127			
Chloromethane	0.0382	0.010	mg/kg wet	0.05000		76	45-143			
cis-1,2-Dichloroethylene	0.0432	0.0050	mg/kg wet	0.05000		86	76-134			
cis-1,3-Dichloropropylene	0.0444	0.0050	mg/kg wet	0.05000		89	71-125			
Dibromochloromethane	0.0446	0.0050	mg/kg wet	0.05000		89	73-122			
Dichlorodifluoromethane	0.0405	0.010	mg/kg wet	0.05000		81	26-146			
Ethylbenzene	0.0435	0.0050	mg/kg wet	0.05000		87	74-128			
Isopropyl Ether	0.0443	0.0050	mg/kg wet	0.05000		89	59-159			
Isopropylbenzene (Cumene)	0.0440	0.0050	mg/kg wet	0.05000		88	68-126			
m,p-Xylenes	0.0886	0.010	mg/kg wet	0.1000		89	75-124			
Methyl Butyl Ketone (2-Hexanone)	0.0480	0.020	mg/kg wet	0.05000		96	61-157			
Methyl Ethyl Ketone (2-Butanone)	0.0510	0.020	mg/kg wet	0.05000		102	63-149			
Methyl Isobutyl Ketone	0.0451	0.020	mg/kg wet	0.05000		90	57-162			
Methylene Chloride	0.0414	0.0050	mg/kg wet	0.05000		83	74-129			
Methyl-tert-Butyl Ether	0.0432	0.0050	mg/kg wet	0.05000		86	70-130			
Naphthalene	0.0428	0.010	mg/kg wet	0.05000		86	57-157			
n-Butylbenzene	0.0460	0.0050	mg/kg wet	0.05000		92	65-135			
n-Propylbenzene	0.0443	0.0050	mg/kg wet	0.05000		89	67-130			
o-Xylene	0.0442	0.0050	mg/kg wet	0.05000		88	74-126			
sec-Butylbenzene	0.0446	0.0050	mg/kg wet	0.05000		89	66-131			
Styrene	0.0438	0.0050	mg/kg wet	0.05000		88	77-121			
tert-Butylbenzene	0.0445	0.0050	mg/kg wet	0.05000		89	67-132			
Tetrachloroethylene	0.0449	0.0050	mg/kg wet	0.05000		90	68-130			
Toluene	0.0435	0.0050	mg/kg wet	0.05000		87	71-129			
trans-1,2-Dichloroethylene	0.0444	0.0050	mg/kg wet	0.05000		89	73-132			
trans-1,3-Dichloropropylene	0.0448	0.0050	mg/kg wet	0.05000		90	68-123			
Trichloroethylene	0.0453	0.0050	mg/kg wet	0.05000		91	75-133			
Trichlorofluoromethane	0.0452	0.010	mg/kg wet	0.05000		90	44-146			
Vinyl acetate	0.0456	0.010	mg/kg wet	0.05000		91	85-161			
Vinyl chloride	0.0430	0.010	mg/kg wet	0.05000		86	48-147			
Xylenes, total	0.133	0.015	mg/kg wet	0.1500		89	74-126			
Surrogate: 4-Bromofluorobenzene	49.3		ug/L	50.00		99	70-130			
Surrogate: Dibromofluoromethane	50.5		ug/L	50.00		101	84-123			
Surrogate: Toluene-d8	49.4		ug/L	50.00		99	76-129			

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0310 - 5035</b>										
<b>LCS Dup (P9H0310-BSD1)</b>										
Prepared & Analyzed: 08/19/19										
1,1,1,2-Tetrachloroethane	0.0447	0.0050	mg/kg wet	0.05000		89	72-115	1	20	
1,1,1-Trichloroethane	0.0444	0.0050	mg/kg wet	0.05000		89	67-131	4	20	
1,1,2,2-Tetrachloroethane	0.0413	0.0050	mg/kg wet	0.05000		83	56-126	2	20	
1,1,2-Trichloroethane	0.0422	0.0050	mg/kg wet	0.05000		84	70-133	0.4	20	
1,1-Dichloroethane	0.0423	0.0050	mg/kg wet	0.05000		85	74-127	2	20	
1,1-Dichloroethylene	0.0402	0.0050	mg/kg wet	0.05000		80	67-149	2	20	
1,1-Dichloropropylene	0.0441	0.0050	mg/kg wet	0.05000		88	71-130	3	20	
1,2,3-Trichlorobenzene	0.0433	0.010	mg/kg wet	0.05000		87	68-130	0.1	20	
1,2,3-Trichloropropane	0.0413	0.0050	mg/kg wet	0.05000		83	60-137	2	20	
1,2,4-Trichlorobenzene	0.0438	0.010	mg/kg wet	0.05000		88	66-125	3	20	
1,2,4-Trimethylbenzene	0.0436	0.0050	mg/kg wet	0.05000		87	69-129	1	20	
1,2-Dibromoethane	0.0434	0.0050	mg/kg wet	0.05000		87	70-132	2	20	
1,2-Dichlorobenzene	0.0426	0.0050	mg/kg wet	0.05000		85	72-123	0.1	20	
1,2-Dichloroethane	0.0446	0.0050	mg/kg wet	0.05000		89	68-128	0.1	20	
1,2-Dichloropropane	0.0435	0.0050	mg/kg wet	0.05000		87	73-130	0.4	20	
1,3,5-Trimethylbenzene	0.0430	0.0050	mg/kg wet	0.05000		86	69-128	2	20	
1,3-Dichlorobenzene	0.0428	0.0050	mg/kg wet	0.05000		86	71-120	0.1	20	
1,3-Dichloropropane	0.0437	0.0050	mg/kg wet	0.05000		87	75-124	2	20	
1,4-Dichlorobenzene	0.0424	0.0050	mg/kg wet	0.05000		85	71-123	0.8	20	
2,2-Dichloropropane	0.0445	0.0050	mg/kg wet	0.05000		89	50-142	4	20	
2-Chlorotoluene	0.0426	0.0050	mg/kg wet	0.05000		85	67-124	3	20	
4-Chlorotoluene	0.0434	0.0050	mg/kg wet	0.05000		87	71-126	1	20	
4-Isopropyltoluene	0.0442	0.0050	mg/kg wet	0.05000		88	68-129	2	20	
Acetone	0.126	0.020	mg/kg wet	0.1000		126	29-198	5	20	
Benzene	0.0421	0.0050	mg/kg wet	0.05000		84	74-127	3	20	
Bromobenzene	0.0431	0.0050	mg/kg wet	0.05000		86	73-125	0.4	20	
Bromochloromethane	0.0425	0.0050	mg/kg wet	0.05000		85	72-134	0.8	20	
Bromodichloromethane	0.0450	0.0050	mg/kg wet	0.05000		90	75-122	1	20	
Bromoform	0.0463	0.0050	mg/kg wet	0.05000		93	66-135	1	20	
Bromomethane	0.0415	0.010	mg/kg wet	0.05000		83	20-180	5	20	
Carbon Tetrachloride	0.0452	0.0050	mg/kg wet	0.05000		90	64-143	3	20	
Chlorobenzene	0.0424	0.0050	mg/kg wet	0.05000		85	74-118	1	20	
Chloroethane	0.0404	0.010	mg/kg wet	0.05000		81	33-149	4	20	
Chloroform	0.0438	0.0050	mg/kg wet	0.05000		88	73-127	1	20	
Chloromethane	0.0366	0.010	mg/kg wet	0.05000		73	45-143	4	20	
cis-1,2-Dichloroethylene	0.0429	0.0050	mg/kg wet	0.05000		86	76-134	0.7	20	
cis-1,3-Dichloropropylene	0.0441	0.0050	mg/kg wet	0.05000		88	71-125	0.6	20	
Dibromochloromethane	0.0444	0.0050	mg/kg wet	0.05000		89	73-122	0.5	20	
Dichlorodifluoromethane	0.0389	0.010	mg/kg wet	0.05000		78	26-146	4	20	
Ethylbenzene	0.0430	0.0050	mg/kg wet	0.05000		86	74-128	1	20	
Isopropyl Ether	0.0437	0.0050	mg/kg wet	0.05000		87	59-159	1	20	
Isopropylbenzene (Cumene)	0.0430	0.0050	mg/kg wet	0.05000		86	68-126	2	20	
m,p-Xylenes	0.0871	0.010	mg/kg wet	0.1000		87	75-124	2	20	
Methyl Butyl Ketone (2-Hexanone)	0.0482	0.020	mg/kg wet	0.05000		96	61-157	0.4	20	
Methyl Ethyl Ketone (2-Butanone)	0.0512	0.020	mg/kg wet	0.05000		102	63-149	0.3	20	
Methyl Isobutyl Ketone	0.0442	0.020	mg/kg wet	0.05000		88	57-162	2	20	

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0310 - 5035</b>										
<b>LCS Dup (P9H0310-BSD1)</b>										
Prepared & Analyzed: 08/19/19										
Methylene Chloride	0.0412	0.0050	mg/kg wet	0.05000		82	74-129	0.2	20	
Methyl-tert-Butyl Ether	0.0434	0.0050	mg/kg wet	0.05000		87	70-130	0.6	20	
Naphthalene	0.0426	0.010	mg/kg wet	0.05000		85	57-157	0.4	20	
n-Butylbenzene	0.0448	0.0050	mg/kg wet	0.05000		90	65-135	3	20	
n-Propylbenzene	0.0432	0.0050	mg/kg wet	0.05000		86	67-130	2	20	
o-Xylene	0.0441	0.0050	mg/kg wet	0.05000		88	74-126	0.3	20	
sec-Butylbenzene	0.0439	0.0050	mg/kg wet	0.05000		88	66-131	2	20	
Styrene	0.0445	0.0050	mg/kg wet	0.05000		89	77-121	2	20	
tert-Butylbenzene	0.0432	0.0050	mg/kg wet	0.05000		86	67-132	3	20	
Tetrachloroethylene	0.0425	0.0050	mg/kg wet	0.05000		85	68-130	6	20	
Toluene	0.0426	0.0050	mg/kg wet	0.05000		85	71-129	2	20	
trans-1,2-Dichloroethylene	0.0430	0.0050	mg/kg wet	0.05000		86	73-132	3	20	
trans-1,3-Dichloropropylene	0.0444	0.0050	mg/kg wet	0.05000		89	68-123	0.9	20	
Trichloroethylene	0.0435	0.0050	mg/kg wet	0.05000		87	75-133	4	20	
Trichlorofluoromethane	0.0419	0.010	mg/kg wet	0.05000		84	44-146	8	20	
Vinyl acetate	0.0467	0.010	mg/kg wet	0.05000		93	85-161	2	20	
Vinyl chloride	0.0404	0.010	mg/kg wet	0.05000		81	48-147	6	20	
Xylenes, total	0.131	0.015	mg/kg wet	0.1500		87	74-126	1	20	
Surrogate: 4-Bromofluorobenzene	50.0		ug/L	50.00		100	70-130			
Surrogate: Dibromofluoromethane	50.3		ug/L	50.00		101	84-123			
Surrogate: Toluene-d8	49.6		ug/L	50.00		99	76-129			

**Batch P9H0347 - 5035**

<b>Blank (P9H0347-BLK1)</b>										
Prepared & Analyzed: 08/20/19										
Benzene	BRL	0.0050	mg/kg wet							
Ethylbenzene	BRL	0.0050	mg/kg wet							
m,p-Xylenes	BRL	0.010	mg/kg wet							
o-Xylene	BRL	0.0050	mg/kg wet							
Toluene	BRL	0.0050	mg/kg wet							
Xylenes, total	BRL	0.015	mg/kg wet							
Surrogate: 4-Bromofluorobenzene	50.2		ug/L	50.00		100	70-130			
Surrogate: Dibromofluoromethane	53.2		ug/L	50.00		106	84-123			
Surrogate: Toluene-d8	48.9		ug/L	50.00		98	76-129			



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0347 - 5035</b>										
<b>LCS (P9H0347-BS1)</b>										
Prepared & Analyzed: 08/20/19										
Benzene	0.0533	0.0050	mg/kg wet	0.05000		107	74-127			
Ethylbenzene	0.0547	0.0050	mg/kg wet	0.05000		109	74-128			
m,p-Xylenes	0.111	0.010	mg/kg wet	0.1000		111	75-124			
o-Xylene	0.0558	0.0050	mg/kg wet	0.05000		112	74-126			
Toluene	0.0546	0.0050	mg/kg wet	0.05000		109	71-129			
Xylenes, total	0.167	0.015	mg/kg wet	0.1500		111	74-126			
Surrogate: 4-Bromofluorobenzene	48.7		ug/L	50.00		97	70-130			
Surrogate: Dibromofluoromethane	51.6		ug/L	50.00		103	84-123			
Surrogate: Toluene-d8	48.6		ug/L	50.00		97	76-129			
<b>LCS Dup (P9H0347-BSD1)</b>										
Prepared & Analyzed: 08/20/19										
Benzene	0.0520	0.0050	mg/kg wet	0.05000		104	74-127	2	20	
Ethylbenzene	0.0536	0.0050	mg/kg wet	0.05000		107	74-128	2	20	
m,p-Xylenes	0.109	0.010	mg/kg wet	0.1000		109	75-124	2	20	
o-Xylene	0.0549	0.0050	mg/kg wet	0.05000		110	74-126	2	20	
Toluene	0.0532	0.0050	mg/kg wet	0.05000		106	71-129	2	20	
Xylenes, total	0.164	0.015	mg/kg wet	0.1500		109	74-126	2	20	
Surrogate: 4-Bromofluorobenzene	48.3		ug/L	50.00		97	70-130			
Surrogate: Dibromofluoromethane	51.5		ug/L	50.00		103	84-123			
Surrogate: Toluene-d8	49.0		ug/L	50.00		98	76-129			
<b>Matrix Spike (P9H0347-MS1)</b>										
Source: 9080260-01 Prepared: 08/20/19 Analyzed: 08/21/19										
Benzene	0.0524	0.0055	mg/kg dry	0.05504	BRL	95	60-135			
Ethylbenzene	0.0536	0.0055	mg/kg dry	0.05504	BRL	97	44-144			
m,p-Xylenes	0.110	0.011	mg/kg dry	0.1101	BRL	100	36-148			
o-Xylene	0.0546	0.0055	mg/kg dry	0.05504	BRL	99	43-143			
Toluene	0.0528	0.0055	mg/kg dry	0.05504	BRL	96	57-135			
Xylenes, total	0.165	0.017	mg/kg dry	0.1651	BRL	100	36-148			
Surrogate: 4-Bromofluorobenzene	45.8		ug/L	50.00		92	70-130			
Surrogate: Dibromofluoromethane	51.8		ug/L	50.00		104	84-123			
Surrogate: Toluene-d8	47.2		ug/L	50.00		94	76-129			



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch P9H0347 - 5035**

Matrix Spike Dup (P9H0347-MSD1)	Source: 9080260-01		Prepared: 08/20/19		Analyzed: 08/21/19					
Benzene	0.0486	0.0054	mg/kg dry	0.05417	BRL	90	60-135	8	20	
Ethylbenzene	0.0499	0.0054	mg/kg dry	0.05417	BRL	92	44-144	7	19	
m,p-Xylenes	0.103	0.011	mg/kg dry	0.1083	BRL	95	36-148	7	20	
o-Xylene	0.0519	0.0054	mg/kg dry	0.05417	BRL	96	43-143	5	17	
Toluene	0.0495	0.0054	mg/kg dry	0.05417	BRL	91	57-135	7	22	
Xylenes, total	0.154	0.016	mg/kg dry	0.1625	BRL	95	36-148	6	20	
Surrogate: 4-Bromofluorobenzene	48.3		ug/L	50.00		97	70-130			
Surrogate: Dibromofluoromethane	55.3		ug/L	50.00		111	84-123			
Surrogate: Toluene-d8	47.2		ug/L	50.00		94	76-129			

**Batch P9H0366 - 5035**

Blank (P9H0366-BLK1)	Prepared & Analyzed: 08/21/19					
Benzene	BRL	0.0050	mg/kg wet			
Ethylbenzene	BRL	0.0050	mg/kg wet			
m,p-Xylenes	BRL	0.010	mg/kg wet			
o-Xylene	BRL	0.0050	mg/kg wet			
Toluene	BRL	0.0050	mg/kg wet			
Xylenes, total	BRL	0.015	mg/kg wet			
Surrogate: 4-Bromofluorobenzene	51.2		ug/L	50.00	102	70-130
Surrogate: Dibromofluoromethane	60.3		ug/L	50.00	121	84-123
Surrogate: Toluene-d8	47.1		ug/L	50.00	94	76-129

**LCS (P9H0366-BS1)**

LCS (P9H0366-BS1)	Prepared & Analyzed: 08/21/19						
Benzene	0.0531	0.0050	mg/kg wet	0.05000		106	74-127
Ethylbenzene	0.0562	0.0050	mg/kg wet	0.05000		112	74-128
m,p-Xylenes	0.115	0.010	mg/kg wet	0.1000		115	75-124
o-Xylene	0.0575	0.0050	mg/kg wet	0.05000		115	74-126
Toluene	0.0550	0.0050	mg/kg wet	0.05000		110	71-129
Xylenes, total	0.173	0.015	mg/kg wet	0.1500		115	74-126
Surrogate: 4-Bromofluorobenzene	48.7		ug/L	50.00		97	70-130
Surrogate: Dibromofluoromethane	54.0		ug/L	50.00		108	84-123
Surrogate: Toluene-d8	48.9		ug/L	50.00		98	76-129

Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch P9H0366 - 5035**

<b>LCS Dup (P9H0366-BSD1)</b>		Prepared & Analyzed: 08/21/19								
Benzene	0.0494	0.0050	mg/kg wet	0.05000		99	74-127	7	20	
Ethylbenzene	0.0523	0.0050	mg/kg wet	0.05000		105	74-128	7	20	
m,p-Xylenes	0.107	0.010	mg/kg wet	0.1000		107	75-124	7	20	
o-Xylene	0.0540	0.0050	mg/kg wet	0.05000		108	74-126	6	20	
Toluene	0.0511	0.0050	mg/kg wet	0.05000		102	71-129	7	20	
Xylenes, total	0.161	0.015	mg/kg wet	0.1500		107	74-126	7	20	
Surrogate: 4-Bromofluorobenzene	48.8		ug/L	50.00		98	70-130			
Surrogate: Dibromofluoromethane	53.0		ug/L	50.00		106	84-123			
Surrogate: Toluene-d8	48.5		ug/L	50.00		97	76-129			

**Batch P9H0389 - 5035**

<b>Blank (P9H0389-BLK1)</b>		Prepared & Analyzed: 08/22/19								
Benzene	BRL	0.0050	mg/kg wet							
Ethylbenzene	BRL	0.0050	mg/kg wet							
m,p-Xylenes	BRL	0.010	mg/kg wet							
o-Xylene	BRL	0.0050	mg/kg wet							
Toluene	BRL	0.0050	mg/kg wet							
Xylenes, total	BRL	0.015	mg/kg wet							
Surrogate: 4-Bromofluorobenzene	50.8		ug/L	50.00		102	70-130			
Surrogate: Dibromofluoromethane	61.1		ug/L	50.00		122	84-123			
Surrogate: Toluene-d8	47.1		ug/L	50.00		94	76-129			

<b>LCS (P9H0389-BS1)</b>		Prepared & Analyzed: 08/22/19								
Benzene	0.0502	0.0050	mg/kg wet	0.05000		100	74-127			
Ethylbenzene	0.0535	0.0050	mg/kg wet	0.05000		107	74-128			
m,p-Xylenes	0.111	0.010	mg/kg wet	0.1000		111	75-124			
o-Xylene	0.0542	0.0050	mg/kg wet	0.05000		108	74-126			
Toluene	0.0520	0.0050	mg/kg wet	0.05000		104	71-129			
Xylenes, total	0.165	0.015	mg/kg wet	0.1500		110	74-126			
Surrogate: 4-Bromofluorobenzene	47.1		ug/L	50.00		94	70-130			
Surrogate: Dibromofluoromethane	55.3		ug/L	50.00		111	84-123			
Surrogate: Toluene-d8	44.9		ug/L	50.00		90	76-129			

Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatiles Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0389 - 5035</b>										
<b>LCS Dup (P9H0389-BSD1)</b>										
Prepared & Analyzed: 08/22/19										
Benzene	0.0473	0.0050	mg/kg wet	0.05000		95	74-127	6	20	
Ethylbenzene	0.0501	0.0050	mg/kg wet	0.05000		100	74-128	7	20	
m,p-Xylenes	0.104	0.010	mg/kg wet	0.1000		104	75-124	6	20	
o-Xylene	0.0514	0.0050	mg/kg wet	0.05000		103	74-126	5	20	
Toluene	0.0489	0.0050	mg/kg wet	0.05000		98	71-129	6	20	
Xylenes, total	0.155	0.015	mg/kg wet	0.1500		104	74-126	6	20	
Surrogate: 4-Bromofluorobenzene	47.0		ug/L	50.00		94	70-130			
Surrogate: Dibromofluoromethane	53.8		ug/L	50.00		108	84-123			
Surrogate: Toluene-d8	48.6		ug/L	50.00		97	76-129			
<b>Matrix Spike (P9H0389-MS1)</b>										
<b>Source: 9080260-19</b>										
Prepared: 08/22/19 Analyzed: 08/23/19										
Benzene	0.0476	0.0057	mg/kg dry	0.05685	BRL	84	60-135			
Ethylbenzene	0.0509	0.0057	mg/kg dry	0.05685	BRL	90	44-144			
m,p-Xylenes	0.107	0.011	mg/kg dry	0.1137	BRL	94	36-148			
o-Xylene	0.0492	0.0057	mg/kg dry	0.05685	BRL	87	43-143			
Toluene	0.0487	0.0057	mg/kg dry	0.05685	BRL	86	57-135			
Xylenes, total	0.156	0.017	mg/kg dry	0.1705	BRL	91	36-148			
Surrogate: 4-Bromofluorobenzene	46.8		ug/L	50.00		94	70-130			
Surrogate: Dibromofluoromethane	60.8		ug/L	50.00		122	84-123			
Surrogate: Toluene-d8	46.1		ug/L	50.00		92	76-129			
<b>Matrix Spike Dup (P9H0389-MSD1)</b>										
<b>Source: 9080260-19</b>										
Prepared: 08/22/19 Analyzed: 08/23/19										
Benzene	0.0501	0.0057	mg/kg dry	0.05696	BRL	88	60-135	5	20	
Ethylbenzene	0.0491	0.0057	mg/kg dry	0.05696	BRL	86	44-144	4	19	
m,p-Xylenes	0.104	0.011	mg/kg dry	0.1139	BRL	91	36-148	3	20	
o-Xylene	0.0490	0.0057	mg/kg dry	0.05696	BRL	86	43-143	0.5	17	
Toluene	0.0511	0.0057	mg/kg dry	0.05696	BRL	90	57-135	5	22	
Xylenes, total	0.153	0.017	mg/kg dry	0.1709	BRL	89	36-148	2	20	
Surrogate: 4-Bromofluorobenzene	45.0		ug/L	50.00		90	70-130			
Surrogate: Dibromofluoromethane	61.7		ug/L	50.00		123	84-123			
Surrogate: Toluene-d8	46.6		ug/L	50.00		93	76-129			



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
 Attn: Michael Wang  
 2501 Blue Ridge Road, Ste 430 Project No: GN7039  
 Raleigh, NC 27607

Prism Work Order: 9080260  
 Time Submitted: 8/16/2019 9:15:00AM

**Volatile Organic Compounds by GC/MS - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0434 - 5035</b>										
<b>Blank (P9H0434-BLK1)</b>										
Prepared & Analyzed: 08/26/19										
Benzene	BRL	0.0050	mg/kg wet							
Ethylbenzene	BRL	0.0050	mg/kg wet							
m,p-Xylenes	BRL	0.010	mg/kg wet							
o-Xylene	BRL	0.0050	mg/kg wet							
Toluene	BRL	0.0050	mg/kg wet							
Xylenes, total	BRL	0.015	mg/kg wet							
Surrogate: 4-Bromofluorobenzene	51.0		ug/L	50.00		102	70-130			
Surrogate: Dibromofluoromethane	46.7		ug/L	50.00		93	84-123			
Surrogate: Toluene-d8	49.6		ug/L	50.00		99	76-129			
<b>LCS (P9H0434-BS1)</b>										
Prepared & Analyzed: 08/26/19										
Benzene	0.0513	0.0050	mg/kg wet	0.05000		103	74-127			
Ethylbenzene	0.0516	0.0050	mg/kg wet	0.05000		103	74-128			
m,p-Xylenes	0.100	0.010	mg/kg wet	0.1000		100	75-124			
o-Xylene	0.0501	0.0050	mg/kg wet	0.05000		100	74-126			
Toluene	0.0516	0.0050	mg/kg wet	0.05000		103	71-129			
Xylenes, total	0.150	0.015	mg/kg wet	0.1500		100	74-126			
Surrogate: 4-Bromofluorobenzene	52.0		ug/L	50.00		104	70-130			
Surrogate: Dibromofluoromethane	44.7		ug/L	50.00		89	84-123			
Surrogate: Toluene-d8	51.0		ug/L	50.00		102	76-129			
<b>LCS Dup (P9H0434-BSD1)</b>										
Prepared & Analyzed: 08/26/19										
Benzene	0.0480	0.0050	mg/kg wet	0.05000		96	74-127	7	20	
Ethylbenzene	0.0479	0.0050	mg/kg wet	0.05000		96	74-128	7	20	
m,p-Xylenes	0.0930	0.010	mg/kg wet	0.1000		93	75-124	7	20	
o-Xylene	0.0468	0.0050	mg/kg wet	0.05000		94	74-126	7	20	
Toluene	0.0481	0.0050	mg/kg wet	0.05000		96	71-129	7	20	
Xylenes, total	0.140	0.015	mg/kg wet	0.1500		93	74-126	7	20	
Surrogate: 4-Bromofluorobenzene	52.6		ug/L	50.00		105	70-130			
Surrogate: Dibromofluoromethane	43.7		ug/L	50.00		87	84-123			
Surrogate: Toluene-d8	50.0		ug/L	50.00		100	76-129			



Geosyntec Consultants of NC, PC - Raleigh Project: NCDOT R-5726 West End  
Attn: Michael Wang  
2501 Blue Ridge Road, Ste 430 Project No: GN7039  
Raleigh, NC 27607

Prism Work Order: 9080260  
Time Submitted: 8/16/2019 9:15:00AM

General Chemistry Parameters - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
<b>Batch P9H0353 - Solids, Dry Weight</b>										
<b>Duplicate (P9H0353-DUP1)</b>		<b>Source: 9080260-04</b>		Prepared: 08/21/19		Analyzed: 08/22/19				
% Solids	91.4	0.100	% by Weight		97.8			7	20	
<b>Duplicate (P9H0353-DUP2)</b>		<b>Source: 9080260-14</b>		Prepared: 08/21/19		Analyzed: 08/22/19				
% Solids	96.6	0.100	% by Weight		90.5			7	20	
<b>Batch P9H0369 - Solids, Dry Weight</b>										
<b>Duplicate (P9H0369-DUP1)</b>		<b>Source: 9080260-20</b>		Prepared: 08/22/19		Analyzed: 08/23/19				
% Solids	93.3	0.100	% by Weight		93.3			0.02	20	
<b>Duplicate (P9H0369-DUP2)</b>		<b>Source: 9080260-23</b>		Prepared: 08/22/19		Analyzed: 08/23/19				
% Solids	97.6	0.100	% by Weight		97.8			0.1	20	
<b>Batch P9H0406 - Solids, Dry Weight</b>										
<b>Duplicate (P9H0406-DUP1)</b>		<b>Source: 9080260-39</b>		Prepared: 08/23/19		Analyzed: 08/26/19				
% Solids	88.6	0.100	% by Weight		89.4			0.9	20	

## Sample Extraction Data

**Prep Method: Solids, Dry Weight**

Lab Number	Batch	Initial	Final	Date/Time
9080260-01	P9H0353	30 g	30 g	08/21/19 10:40
9080260-02	P9H0353	30 g	30 g	08/21/19 10:40
9080260-03	P9H0353	30 g	30 g	08/21/19 10:40
9080260-04	P9H0353	30 g	30 g	08/21/19 10:40
9080260-05	P9H0353	30 g	30 g	08/21/19 10:40
9080260-06	P9H0353	30 g	30 g	08/21/19 10:40
9080260-07	P9H0353	30 g	30 g	08/21/19 10:40
9080260-08	P9H0353	30 g	30 g	08/21/19 10:40
9080260-09	P9H0353	30 g	30 g	08/21/19 10:40
9080260-10	P9H0353	30 g	30 g	08/21/19 10:40
9080260-11	P9H0353	30 g	30 g	08/21/19 10:40
9080260-12	P9H0353	30 g	30 g	08/21/19 10:40
9080260-13	P9H0353	30 g	30 g	08/21/19 10:40
9080260-14	P9H0353	30 g	30 g	08/21/19 10:40
9080260-15	P9H0353	30 g	30 g	08/21/19 10:40
9080260-16	P9H0353	30 g	30 g	08/21/19 10:40
9080260-17	P9H0353	30 g	30 g	08/21/19 10:40
9080260-18	P9H0369	30 g	30 g	08/22/19 11:13
9080260-19	P9H0369	30 g	30 g	08/22/19 11:13
9080260-20	P9H0369	30 g	30 g	08/22/19 11:13
9080260-21	P9H0369	30 g	30 g	08/22/19 11:13
9080260-22	P9H0369	30 g	30 g	08/22/19 11:13
9080260-23	P9H0369	30 g	30 g	08/22/19 11:13
9080260-24	P9H0369	30 g	30 g	08/22/19 11:13
9080260-25	P9H0369	30 g	30 g	08/22/19 11:13
9080260-26	P9H0369	30 g	30 g	08/22/19 11:13
9080260-27	P9H0369	30 g	30 g	08/22/19 11:13
9080260-28	P9H0369	30 g	30 g	08/22/19 11:13
9080260-29	P9H0369	30 g	30 g	08/22/19 11:13
9080260-30	P9H0369	30 g	30 g	08/22/19 11:13
9080260-31	P9H0369	30 g	30 g	08/22/19 11:13
9080260-32	P9H0369	30 g	30 g	08/22/19 11:13
9080260-33	P9H0369	30 g	30 g	08/22/19 11:13
9080260-34	P9H0369	30 g	30 g	08/22/19 11:13
9080260-35	P9H0369	30 g	30 g	08/22/19 11:13
9080260-36	P9H0369	30 g	30 g	08/22/19 11:13
9080260-37	P9H0369	30 g	30 g	08/22/19 11:13
9080260-38	P9H0406	30 g	30 g	08/23/19 12:00
9080260-39	P9H0406	30 g	30 g	08/23/19 12:00

**Prep Method: 5035**

Lab Number	Batch	Initial	Final	Date/Time
9080260-01	P9H0347	3.89 g	5 mL	08/20/19 10:00
9080260-02	P9H0347	4.18 g	5 mL	08/20/19 10:00
9080260-03	P9H0347	5.17 g	5 mL	08/20/19 10:00
9080260-04	P9H0347	4.83 g	5 mL	08/20/19 10:00
9080260-05	P9H0389	3.77 g	5 mL	08/22/19 10:00
9080260-06	P9H0347	5.45 g	5 mL	08/20/19 10:00
9080260-07	P9H0347	5.48 g	5 mL	08/20/19 10:00
9080260-08	P9H0347	5.5 g	5 mL	08/20/19 10:00
9080260-09	P9H0347	4.69 g	5 mL	08/20/19 10:00
9080260-10	P9H0347	4.68 g	5 mL	08/20/19 10:00
9080260-11	P9H0347	4.72 g	5 mL	08/20/19 10:00
9080260-12	P9H0347	4.64 g	5 mL	08/20/19 10:00
9080260-13	P9H0310	5.74 g	5 mL	08/19/19 10:00
9080260-14	P9H0366	5.34 g	5 mL	08/21/19 10:00

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

## Sample Extraction Data

Prep Method: 5035

Lab Number	Batch	Initial	Final	Date/Time
9080260-15	P9H0347	3.3 g	5 mL	08/20/19 10:00
9080260-16	P9H0347	6.27 g	5 mL	08/20/19 10:00
9080260-17	P9H0347	5.54 g	5 mL	08/20/19 10:00
9080260-18	P9H0347	4.89 g	5 mL	08/20/19 10:00
9080260-19	P9H0389	6.23 g	5 mL	08/22/19 10:00
9080260-20	P9H0389	5.21 g	5 mL	08/22/19 10:00
9080260-21	P9H0434	4.84 g	5 mL	08/26/19 11:00
9080260-22	P9H0389	5.69 g	5 mL	08/22/19 10:00
9080260-23	P9H0310	5.96 g	5 mL	08/19/19 10:00
9080260-24	P9H0310	4.34 g	5 mL	08/19/19 10:00
9080260-25	P9H0389	4.74 g	5 mL	08/22/19 10:00
9080260-26	P9H0389	4.6 g	5 mL	08/22/19 10:00
9080260-27	P9H0389	3.91 g	5 mL	08/22/19 10:00
9080260-28	P9H0389	4.18 g	5 mL	08/22/19 10:00
9080260-29	P9H0389	4.28 g	5 mL	08/22/19 10:00
9080260-30	P9H0389	4.06 g	5 mL	08/22/19 10:00
9080260-31	P9H0389	4.36 g	5 mL	08/22/19 10:00
9080260-32	P9H0389	5.01 g	5 mL	08/22/19 10:00
9080260-33	P9H0389	5.13 g	5 mL	08/22/19 10:00
9080260-34	P9H0389	3.66 g	5 mL	08/22/19 10:00
9080260-35	P9H0389	3.79 g	5 mL	08/22/19 10:00
9080260-36	P9H0389	6.93 g	5 mL	08/22/19 10:00
9080260-37	P9H0434	4.94 g	5 mL	08/26/19 11:00
9080260-38	P9H0389	5.45 g	5 mL	08/22/19 10:00
9080260-39	P9H0434	5.81 g	5 mL	08/26/19 11:00

This report should not be reproduced, except in its entirety, without the written consent of Prism Laboratories, Inc.

449 Springbrook Road - P.O. Box 240543 - Charlotte, NC 28224-0543  
Phone: 704/529-6364 - Toll Free Number: 1-800/529-6364 - Fax: 704/525-0409

Page 56 of 60

449 Springbrook Road • Charlotte, NC 28217  
 Phone 704/529-6364 • Fax: 704/525-0409

Client Company Name: Geosyntec

Report To/Contact Name: Michael Wang

Reporting Address: 2501 Blue Ridge Rd. Ste 420 Raleigh, NC 27607

Phone: 919-551-5334 Fax (Yes) (No): No

Email Address: mwang@geosyntec.com

EDD Type: PDF  Excel  Other

Site Location Name: NCDDOT W&S End

Site Location Physical Address: W&S End, NC

## CHAIN OF CUSTODY RECORD

PAGE 1 OF 4 QUOTE # TO ENSURE PROPER BILLING: 61V7039

Project Name: NCDDOT W&S End

Short Hold Analysis: (Yes) (No) (No) UST Project: (Yes) (No) (No)

\*Please ATTACH any project specific reporting (QC LEVEL I II III IV) provisions and/or QC Requirements

Invoice To: Geosyntec

Address: W&S End, NC

Purchase Order No./Billing Reference: 61V7039

Requested Due Date  1 Day  2 Days  3 Days  4 Days  5 Days

"Working Days"  6-9 Days  Standard 10 days  Rush Work Must Be Pre-Approved

Samples received after 14:00 will be processed next business day. Turnaround time is based on business days, excluding weekends and holidays. (SEE REVERSE FOR TERMS & CONDITIONS REGARDING SERVICES RENDERED BY PRISM LABORATORIES, INC. TO CLIENT)

## LAB USE ONLY

Samples INTACT upon arrival? YES  NO  N/A

Received ON WET ICE? YES  NO  N/A

PROPER PRESERVATIVES indicated? YES  NO  N/A

Received WITHIN HOLDING TIMES? YES  NO  N/A

CUSTODY SEALS INTACT? YES  NO  N/A

VOLATILES rec'd W/OUT HEADSPACE? YES  NO  N/A

PROPER CONTAINERS used? YES  NO  N/A

TEMP: Therm ID: 3.2 Observed: 3.2 °C / Corr: 3.3 °C

### TO BE FILLED IN BY CLIENT/SAMPLING PERSONNEL

Certification: NELAC  DOD  FL  NC

Water Chlorinated: YES  NO  OTHER  N/A

Sample Iced Upon Collection: YES  NO

CLIENT SAMPLE DESCRIPTION	DATE COLLECTED	TIME COLLECTED MILITARY HOURS	MATRIX (SOIL, WATER OR SLUDGE)	SAMPLE CONTAINER			PRESERVATIVES	ANALYSIS REQUESTED	REMARKS	PRISM LAB NO. ID NO.
				*TYPE SEE BELOW	NO.	SIZE				
SB13-01-75-800	8/13/19	1030	Soil	VOA	4		Multiple		BTEX ONLY	01
SB13-02-7-7.5	8/12/19	1100	Soil							02
SB13-03-6.5-9.0	8/12/19	1130	Soil							03
SB43-01-4-5.5	8/13/19	1340								04
SB43-02-6-5-7	8/13/19	1400								05
SB43-03-7-7.5	8/13/19	1430								06
SB43-04-7-5.8	8/13/19	1445								07
SB66867-01-5-5.5	8/13/19	0840								08
SB66867-02-4-0-8.5	8/13/19	0910	V							09
SB66867-03-6-5-7	8/13/19	1020	Soil	VOA	4		Multiple		BTEX ONLY	10

Sampler's Signature: Michael Wang Sampled By (Print Name): Michael Wang Affiliation: Geosyntec

Upon relinquishing, this Chain of Custody is your authorization for Prism to proceed with the analyses as requested above. Any changes must be submitted in writing to the Prism Project Manager. There will be charges for any changes after analyses have been initialized.

Relinquished By: (Signature) [Signature] Received By: (Signature) [Signature] Date: 8/15/19 Military/Hours: 1605

Relinquished By: (Signature) [Signature] Received By: (Signature) [Signature] Date: 8-16-19 Military/Hours: 0915

Relinquished By: (Signature) [Signature] Received For Prism Laboratories By: [Signature] Date: 8-16-19 Military/Hours: 0915

Method of Shipment:  Fed Ex  UPS  Hand-delivered  Prism Field Service  Other

NOTE: ALL SAMPLE COOLERS SHOULD BE TAPED SHUT WITH CUSTODY SEALS FOR TRANSPORTATION TO THE LABORATORY. SAMPLES ARE NOT ACCEPTED AND VERIFIED AGAINST COC UNTIL RECEIVED AT THE LABORATORY.

NPDES:  NC  SC  UT  NC  SC  NC  SC  NC  SC  NC  SC  NC  SC

GROUNDWATER:  NC  SC  NC  SC  NC  SC  NC  SC

DRINKING WATER:  NC  SC  NC  SC  NC  SC  NC  SC

SOLID WASTE:  NC  SC  NC  SC  NC  SC  NC  SC

RCRA:  NC  SC  NC  SC  NC  SC  NC  SC

CERCLA:  NC  SC  NC  SC  NC  SC  NC  SC

LANDFILL:  NC  SC  NC  SC  NC  SC  NC  SC

OTHER:  NC  SC  NC  SC  NC  SC  NC  SC

COC Group No. 9080260

Additional Comments:

PRESS DOWN FIRMLY - 3 COPIES

### PRISM USE ONLY

Site Arrival Time: \_\_\_\_\_

Site Departure Time: \_\_\_\_\_

Field Tech Fee: \_\_\_\_\_

Mileage: \_\_\_\_\_

SEE REVERSE FOR TERMS & CONDITIONS



**CHAIN OF CUSTODY RECORD**

PAGE 2 OF 4 QUOTE # TO ENSURE PROPER BILLING: 61V 7039

Project Name: Norbert West End UST Project: (Yes) (No) (NO)  
 Short Hold Analysis: (Yes) (No) (NO)  
 \*Please ATTACH any project specific reporting (QC LEVEL I, II, III, IV) provisions and/or QC Requirements  
 Invoice To: Greystone  
 Address: \_\_\_\_\_

**LAB USE ONLY**

Samples INTACT upon arrival? YES  NO  N/A

Received ON WET ICE? YES  NO  N/A

PROPER PRESERVATIVES indicated? YES  NO  N/A

RECEIVED WITHIN HOLDING TIMES? YES  NO  N/A

CUSTODY SEALS INTACT? YES  NO  N/A

VOLATILES rec'd W/OUT HEADSPACE? YES  NO  N/A

PROPER CONTAINERS used? YES  NO  N/A

TEMP. Therm ID: 2019 Observed: 32 °C / Contr: 33 °C

Client Company Name: Greystone  
 Report To/Contact Name: Michael Wang  
 Reporting Address: 2501 Blue Ridge Rd.  
Ste 430, Raleigh, NC, 27607  
 Phone: 979-551-5334 Fax (Yes) (No): NO  
 Email Address: mwang@greystone.com  
 EDD Type: PDF  Excel  Other   
 Site Location Name: Norbert West End  
 Site Location Physical Address: West End, NC

Purchase Order No./Billing Reference: 61V 7039  
 Requested Due Date  1 Day  2 Days  3 Days  4 Days  5 Days  
 "Working Days"  6-9 Days  Standard 10 days  Rush Work Must Be Pre-Approved  
 Samples received after 14:00 will be processed next business day.  
 Turnaround time is based on business days, excluding weekends and holidays.  
 (SEE REVERSE FOR TERMS & CONDITIONS REGARDING SERVICES RENDERED BY PRISM LABORATORIES, INC. TO CLIENT)

**TO BE FILLED IN BY CLIENT/SAMPLING PERSONNEL**  
 Certification: NELAC  DOD  FL  NC   
 SC  OTHER  N/A   
 Water Chlorinated: YES  NO   
 Sample Iced Upon Collection: YES  NO

CLIENT SAMPLE DESCRIPTION	DATE COLLECTED	TIME COLLECTED MILITARY HOURS	MATRIX (SOIL, WATER OR SLUDGE)	SAMPLE CONTAINER			PRESERVATIVES	ANALYSIS REQUESTED	REMARKS	PRISM LAB ID NO.
				*TYPE SEE BELOW	NO.	SIZE				
SB66667-04-5560	8/13/19	0945	Soil	VOA	4		Multiple		RTX ONLY	11
SB66667-05-75	8/13/19	1110	Soil							12
SB66667-06-758	8/13/19	1220	Soil							13
SB69-01-60-65	8/12/19	1300								14
SB69-02-40-45	8/12/19	1330								15
SB69-03-5-55	8/12/19	1400								16
SB69-04-5-55	8/12/19	1445								17
SB69-05-9510	8/12/19	1525								18
SB69-06-99.5	8/12/19	1615								19
SB69-07-5055	8/12/19	1645	Soil	VOA	4		Multiple		RTX ONLY	20

Sampler's Signature: [Signature] Sampled By (Print Name): Michael Wang Affiliation: \_\_\_\_\_

Upon relinquishing this Chain of Custody is your authorization for Prism to proceed with the analyses as requested above. Any changes must be submitted in writing to the Prism Project Manager. There will be charges for any changes after analyses have been initialized.

Relinquished By (Signature): [Signature] Received By (Signature): \_\_\_\_\_ Date: 8/14/19 Military/Hours: 1600

Relinquished By (Signature): [Signature] Received By (Signature): \_\_\_\_\_ Date: \_\_\_\_\_ Military/Hours: \_\_\_\_\_

Relinquished By (Signature): \_\_\_\_\_ Received For Prism Laboratories By: \_\_\_\_\_ Date: 8-16-19 Military/Hours: 0915

Method of Shipment: NOTE: ALL SAMPLE COOLERS SHOULD BE TAPED SHUT WITH CUSTODY SEALS FOR TRANSPORTATION TO THE LABORATORY. SAMPLES ARE NOT ACCEPTED AND VERIFIED AGAINST COC UNTIL RECEIVED AT THE LABORATORY.

Fed Ex  UPS  Hand-delivered  Prism Field Service  Other \_\_\_\_\_

NPDES:  UST:  GROUNDWATER:  DRINKING WATER:  SOLID WASTE:  RCRA:  CERCLA  LANDFILL  OTHER:

NC  SC  NC  SC  NC  SC  NC  SC  NC  SC  NC  SC  NC  SC  NC  SC

\*CONTAINER TYPE CODES: A = Amber C = Clear G = Glass P = Plastic; TL = Teflon-Lined Cap VOA = Volatile Organics Analysis (Zero Head Space)

**PRISM USE ONLY**

Site Arrival Time: \_\_\_\_\_

Site Departure Time: \_\_\_\_\_

Field Tech Fee: \_\_\_\_\_

Mileage: \_\_\_\_\_

SEE REVERSE FOR TERMS & CONDITIONS

**CHAIN OF CUSTODY RECORD**

PAGE 3 OF 4 QUOTE # TO ENSURE PROPER BILLING: 6W7039

Project Name: West End UST Project: (Yes)  (NO)   
 Short Hold Analysis: (Yes)  (NO)   
 \*Please ATTACH any project specific reporting (QC LEVEL I III III IV) provisions and/or QC Requirements  
 Invoice To: Greystone  
 Address: \_\_\_\_\_

**LAB USE ONLY**

Samples INTACT upon arrival?	YES	NO	N/A
Received ON WET ICE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PROPER PRESERVATIVES indicated?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Received WITHIN HOLDING TIMES?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CUSTODY SEALS INTACT?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
VOLATILES rec'd W/OUT HEADSPACE?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PROPER CONTAINERS used?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TEMP: Therm ID: <u>1019</u> Observed: <u>31.2</u> °C / Corr: <u>3.3</u> °C			

Client Company Name: Greystone  
 Report To/Contact Name: Michael Wang  
 Reporting Address: 7501 Blue Ridge Rd Ste 420 Raleigh, NC 27607  
 Phone: 919-551-5334 Fax (Yes) (No): NO  
 Email Address: mwang@greystone.com  
 EDD Type: PDF  Excel  Other   
 Site Location Name: WDDT West End  
 Site Location Physical Address: West End, NC

Purchase Order No./Billing Reference: 6W7039  
 Requested Due Date  1 Day  2 Days  3 Days  4 Days  5 Days  
 "Working Days"  6-9 Days  Standard 10 days  Rush Work Must Be Samples received after 14:00 will be processed next business day.  
 Turnaround time is based on business days, excluding weekends and holidays.  
 (SEE REVERSE FOR TERMS & CONDITIONS REGARDING SERVICES RENDERED BY PRISM LABORATORIES, INC. TO CLIENT)

**TO BE FILLED IN BY CLIENT/SAMPLING PERSONNEL**  
 Certification: NELAC  DOD  FL  NC   
 Water Chlorinated: YES  NO   
 Sample Iced Upon Collection: YES  NO

CLIENT SAMPLE DESCRIPTION	DATE COLLECTED	TIME COLLECTED MILITARY HOURS	MATRIX (SOIL, WATER OR SLUDGE)	SAMPLE CONTAINER			PRESERVATIVES	ANALYSIS REQUESTED	REMARKS	PRISM LAB ID NO.
				*TYPE SEE BELOW	NO.	SIZE				
SB69-08-6-6.5	8/13/19	1300	Soil	VOA	4		Multiple			21
SB78-01-7-7.5	8/13/19	1550								22
SB78-02-5-5.6	8/14/19	0825								23
SB78-03-6-6.5	8/14/19	0900								24
SB78-04-6-5.7	8/14/19	0930								25
SB89-01-5-5.5	8/15/19	0900								26
SB89-02-5-5.6	8/15/19	0940								27
SB89-03-6-5.7	8/15/19	1030								28
SB89-04-7-7.5	8/15/19	1130								29
SB02-01-2-5.3	8/14/19	1050	Soil	VOA	4		Multiple			30

Sampler's Signature: [Signature]  
 Upon relinquishing this Chain of Custody is your authorization for Prism to proceed with the analyses as requested above. Any changes must be submitted in writing to the Prism Project Manager. There will be charges for any changes after analyses have been initialized.

Received By (Print Name): Michael Wang Affiliation: \_\_\_\_\_  
 Received By (Signature): [Signature] Date: 8/15/19  
 Received By (Signature): \_\_\_\_\_ Date: \_\_\_\_\_  
 Received For Prism Laboratories By: [Signature] Date: 8/15/19  
 COC Group No.: 9080260

Additional Comments: BTEx ONLY  
**PRESS DOWN FIRMLY - 3 COPIES**  
**PRISM USE ONLY**  
 Site Arrival Time: \_\_\_\_\_  
 Site Departure Time: \_\_\_\_\_  
 Field Tech Fee: \_\_\_\_\_  
 Mileage: \_\_\_\_\_

SEE REVERSE FOR TERMS & CONDITIONS  
**ORIGINAL**



Full-Service Analytical & Environmental Solutions

449 Springbrook Road • Charlotte, NC 28217  
Phone 704/529-6364 • Fax: 704/525-0409

# CHAIN OF CUSTODY RECORD

PAGE 4 OF 4 QUOTE # TO ENSURE PROPER BILLING: 6477037

Project Name: West End UST Project: (Yes) (No) NO  
Short Hold Analysis: (Yes) (No) NO  
\*Please ATTACH any project specific reporting (QC LEVEL I III IV) provisions and/or QC Requirements  
Invoice To: Greystone  
Address: West End, NC

**LAB USE ONLY**

Samples INTACT upon arrival?  YES  NO  N/A

Received ON WET ICE?  YES  NO  N/A

PROPER PRESERVATIVES indicated?  YES  NO  N/A

Received WITHIN HOLDING TIMES?  YES  NO  N/A

CUSTODY SEALS INTACT?  YES  NO  N/A

VOLATILES rec'd W/OUT HEADSPACE?  YES  NO  N/A

PROPER CONTAINERS used?  YES  NO  N/A

TEMP: Therm ID: PC-14 Observed: 3.2 °C / Corr: 3.3 °C

Client Company Name: Greystone  
Report To/Contact Name: Michael Wang  
Reporting Address: 2501 Blue Ridge Rd  
Ste 420 Raleigh, NC 27607  
Phone: 979-551-5334 Fax (Yes) (No): NO  
Email Address: mwang@greystone.com  
EDD Type: PDF  Excel  Other   
Site Location Name: NDOT West End  
Site Location Physical Address: West End, NC

Purchase Order No./Billing Reference \_\_\_\_\_  
Requested Due Date  1 Day  2 Days  3 Days  4 Days  5 Days  
"Working Days"  6-9 Days  Standard 10 days  Rush Work Must Be Pre-Approved  
Samples received after 14:00 will be processed next business day.  
Turnaround time is based on business days, excluding weekends and holidays.  
**SEE REVERSE FOR TERMS & CONDITIONS REGARDING SERVICES RENDERED BY PRISM LABORATORIES, INC. TO CLIENT)**

**TO BE FILLED IN BY CLIENT/SAMPLING PERSONNEL**  
Certification: NELAC  DOD  FL  NC  
SC  OTHER  N/A  
Water Chlorinated: YES  NO   
Sample Iced Upon Collection: YES  NO

CLIENT SAMPLE DESCRIPTION	DATE COLLECTED	TIME COLLECTED MILITARY HOURS	MATRIX (SOIL, WATER OR SLUDGE)	SAMPLE CONTAINER			PRESERVATIVES	ANALYSIS REQUESTED	REMARKS	PRISM LAB ID NO.
				*TYPE	NO.	SIZE				
SB102-02-5-5-6	8/14/19	1135	Soil	VOA	4		Multiple			31
SB102-03-7-7.5	8/14/19	1300					Multiple			32
SB102-04-7-7.5	8/14/19	1330					Multiple			33
SB102-05-4-5-5	8/14/19	1400					Multiple			34
SB102-06-0-5-1	8/14/19	1450					Multiple			35
SB102-07-7-5-8	8/14/19	1535					Multiple			36
SB102-08-8-8-5	8/14/19	1605					Multiple			37
SB102-09-8-5-9	8/14/19	1645					Multiple			38
SB102-10-9-9-5	8/14/19	1720	Soil	VOA	4		Multiple			39

Sampler's Signature: [Signature] Sampled By (Print Name): Michael Wang Affiliation: \_\_\_\_\_

Upon relinquishing, this Chain of Custody is your authorization for Prism to proceed with the analyses as requested above. Any changes must be submitted in writing to the Prism Project Manager. There will be charges for any changes after analyses have been initialized.

Relinquished By: (Signature) [Signature] Received By: (Signature) \_\_\_\_\_ Date: 8-16-19 Military/Hours: 0915

Relinquished By: (Signature) [Signature] Received By: (Signature) \_\_\_\_\_ Date: \_\_\_\_\_ Military/Hours: \_\_\_\_\_

Relinquished By: (Signature) \_\_\_\_\_ Received For Prism Laboratories By: [Signature] Date: 8-16-19 Military/Hours: 0915

Method of Shipment:  Fed Ex  UPS  Hand-delivered  Prism Field Service  Other \_\_\_\_\_

NOTE: ALL SAMPLE COOLERS SHOULD BE TAPED SHUT WITH CUSTODY SEALS FOR TRANSPORTATION TO THE LABORATORY. SAMPLES ARE NOT ACCEPTED AND VERIFIED AGAINST COC UNTIL RECEIVED AT THE LABORATORY.

COC Group No. 9080260

Additional Comments: \_\_\_\_\_

**PRISM USE ONLY**

Site Arrival Time: \_\_\_\_\_  
Site Departure Time: \_\_\_\_\_  
Field Tech Fee: \_\_\_\_\_  
Mileage: \_\_\_\_\_

\*CONTAINER TYPE CODES: A = Amber C = Clear G = Glass P = Plastic TL = Teflon-Lined Cap VOA = Volatile Organics Analysis (Zero Head Space)

SEE REVERSE FOR TERMS & CONDITIONS

ORIGINAL