\bigcirc


	LEGEND
╺┅╫┼╢┅╴	NEW YAGI ANTENNA (DOUBLE)
<u> </u>	NEW YAGI ANTENNA (SINGLE)
	EXISTING YAGI ANTENNA (DOUBLE)
	EXISTING YAGI ANTENNA (SINGLE)
	NEW CONTROLLER AND CABINET
	EXISTING METAL POLE W/MAST ARM
03-XXXX	SIGNAL INVENTORY NUMBER
•	WOOD POLE FOR TEMPORARY SIGNAL


NOTES FOR WIRELESS COMMUNICATION	S:
----------------------------------	----

1. INSTALL COAXIAL CABLE:

- A. ON WOOD POLES, REQUIRING A NEW RIGID GALVANIZED STEEL RISER, INSTALL A 2" RISER WITH WEATHERHEAD AND ROUTE THE COAXIAL CABLE TO THE ANTENNA.
- B. ON METAL POLES WITH MAST ARMS, RUN COAXIAL CABLE UP THROUGH THE POLE AND OUT THE MAST ARM; FIELD DRILL
 A 1/2" HOLE UP THROUGH THE BOTTOM OF MAST ARM FOR INSTALLATION OF THE COAXIAL CABLE TO THE ANTENNA.
 C. ON METAL STRAIN POLES, RUN COAXIAL CABLE UP THROUGH THE POLE AND OUT THE WEATHERHEAD AND
- ROUTE THE COAXIAL CABLE TO THE ANTENNA. D. BETWEEN THE POINT OF EXITING THE RISER, METAL POLE, OR MAST ARM AND THE ANTENNA, SECURE THE COAXIAL CABLE
- TO THE STRUCTURE USING 3/4" STAINLESS STEEL STRAPS EVERY 12". 2. IF AN EXISTING 2" SPARE RIGID GALVANIZED STEEL RISER IS AVAILABLE, INSTALL THE COAXIAL CABLE IN THE SPARE RISER.
- 3. INSTALL WIRELESS ANTENNA ON POLE WITH RF WARNING SIGN. (NOTE: RF WARNING SIGN NOT REQUIRED WHEN ANTENNA IS INSTALLED ON AN NCDOT-OWNED POLE.)
- 4. MAINTAIN PROPER CLEARANCE FROM ALL UTILITIES PER THE NATIONAL ELECTRICAL SAFETY CODE.
- 5. REFERENCE "WIRELESS RADIO ANTENNA TYPICAL DETAILS" IN THE 2024 NCDOT ROADWAY STANDARD DRAWINGS.
- 6. RETURN EXISTING WIRELESS RADIO EQUIPMENT TO THE NCDOT DIVISION 3 SIGNAL SHOP. THE DIVISION 3 OFFICE CAN BE REACHED AT (910) 341–2200.
- 7. TWO (2) WEEKS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE CITY OF WILMINGTON SIGNAL SYSTEMS MANAGEMENT ENGINEER AT (910) 341–4676 TO ARRANGE FOR THE CITY TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE SIGNAL SYSTEMS MANAGEMENT ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND FUNCTIONAL.

 \bigcirc







Temp

			PROJECT REFERENCE NO. U-6202	SHEET NO. SCP. 7
R SCHOOL				
SCHOOL				
		r		
p Phase 2A			OT CONSIDERED I GNATURES COMP	
Plans Prepared for:	CITY OF WILMING		SEA	L
MODILITY and Science		ION SIGNAL SYS	TEM	ROLIN
		UTING PLANS	SFA	L
	Division 3 New Hano	ver County Wilmi	ngton	<u> </u> S
enfield Pkwy., Garner, NC 27529	PLAN DATE: July 2023	REVIEWED BY: J.A. Wagr REVIEWED BY: N.R. Simmo	DATE	ER. JOS
SCALE	REVISIONS		DATE DocuSigned by: <u>Natasha R Simm</u>	
N/A			F6DA88DE3AD445ARE	DATE
/			CADD Filename: U620	2_SCP-07.dgn