

ADA SUMMARY OF QUANTITIES - NC 42 FROM HARNETT COUNTY TO US 401

| | |
|-----------------|-----------------------|
| Municipality: | Fuquay-Varina |
| Project Number: | 2025CPT.05.07.10921.1 |
| County: | Wake |

| | |
|-----------|----|
| Sheet No. | 12 |
|-----------|----|

| Ramp ID | Inset Map Number | Route 1 | Route 2 | 0156000000-E (SY) Removal of Existing Asphalt Pavement | 2549000000-E (LF) 2'-6" Concrete Curb & Gutter | 2752000000-E (LF) Remove Curb & Gutter | 2591000000-E (SY) 4" Concrete Sidewalk | 2738000000-E (SY) Remove and Replace Sidewalk | 2738000000-E (SY) Remove Sidewalk | 2738000000-E (SY) Non-Standard Sidewalk | 2738000000-E (SY) Remove and Reset Brick Pavers | 2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes | 4116100000-N (EA) Sign Erection, relocate Type E (Ground Mounted) | 4860000000-E (LF) 8" Line Removal | 2738000000-E (SY) Remove and Replace Island | 2612300000-N (EA) Retrofit Existing Concrete Curb Ramps | 2612500000-N (EA) Remove and Replace Concrete Curb Ramps | 2759000000-N (EA) Remove Curb Ramps | Improvement Type |
|------------------|------------------|----------------------|---|---|---|---|---|--|--------------------------------------|--|--|---|--|--------------------------------------|--|--|---|--|--------------------------|
| 26075 | 1 | NC-42 (W Academy St) | Crimson Ridge Trl | 24 | | | 24 | | | | | | | | | | 1 | | Type 1 Modified - 848.06 |
| 26076 | 1 | NC-42 (W Academy St) | Crimson Ridge Trl | 18 | | | 18 | | | | | | | | | | 1 | | Type 1 Modified - 848.06 |
| 4692 | 2 | NC-42 (W Academy St) | Cameronwood Dr | | | | | 6 | | | | | | | | | 1 | | Type 1C - 848.06 |
| 4694 | 2 | NC-42 (W Academy St) | Cameronwood Dr | | | | | | | | | | | | | | 1 | | Type 1C - 848.06 |
| 26066 | 3 | NC-42 (W Academy St) | SR-6108 (S Judd Pkwy SW) | | | | | | | | | | | | | | 1 | | Standard - 848.06 |
| 26067 | 3 | NC-42 (W Academy St) | SR-6108 (S Judd Pkwy SW) | | | | | | 12 | | | | | | | | 1 | | Standard - 848.06 |
| 26070 | 3 | NC-42 (W Academy St) | SR-6108 (S Judd Pkwy SW) | | | | | | | | | | | | 4 | | | | Other |
| 26071 | 3 | NC-42 (W Academy St) | SR-6108 (S Judd Pkwy SW) | | | | | | | | | | | | | 1 | | | Retrofit Warnings |
| 26072 | 3 | NC-42 (W Academy St) | SR-6108 (S Judd Pkwy SW) | | | | | | 9 | | | | | | | 1 | | | Retrofit Warnings |
| 4699 | 4 | NC-42 (W Academy St) | Lyonshall St | | | | | | | | | | | | | 1 | | | Retrofit Warnings |
| 4702 | 4 | NC-42 (W Academy St) | Lyonshall St | | | | | | | | | | | | | 1 | | | Retrofit Warnings |
| 4703 | 4 | NC-42 (W Academy St) | SR-1105 (Coley Farm Rd) | | | | | 3 | 9 | | | | | | | | 1 | | Standard - 848.06 |
| 4704 | 4 | NC-42 (W Academy St) | SR-1105 (Coley Farm Rd) | | | | | 9 | | | | | | | | | 1 | | Standard - 848.06 |
| 4705 | 4 | NC-42 (W Academy St) | SR-1105 (Coley Farm Rd) | | | | | | | | | | | | | | 1 | | Standard - 848.06 |
| 4706 | 4 | NC-42 (W Academy St) | SR-1105 (Coley Farm Rd) | | | | | | | | | | | | | | 1 | | Standard - 848.06 |
| 4707 | 4 | NC-42 (W Academy St) | Lyonshall St | | | | | | | | | | | | | 1 | | | Retrofit Warnings |
| 4708 | 4 | NC-42 (W Academy St) | Lyonshall St | | | | | | | | | | | | | 1 | | | Retrofit Warnings |
| 4715 | 5 | NC-42 (W Academy St) | Stapleford Ln | | | | | | | | | | | | | | 1 | | Type 1D - 848.06 |
| 4716 | 5 | NC-42 (W Academy St) | Stapleford Ln | | 15 | | 9 | | | | | | | 70 | | | | 1 | Remove Ramp |
| 4719 | 5 | NC-42 (W Academy St) | Stapleford Ln | | | | | | | | | | | | | | 1 | | Standard - 848.06 |
| 4720 | 5 | NC-42 (W Academy St) | Stapleford Ln | | | | | | | | | | | | | | 1 | | Standard - 848.06 |
| 26065 | 5 | NC-42 (W Academy St) | SR-1179 (Bridge St) | | 10 | 10 | 6 | | 6 | | | | 1 | | | | 1 | | Type 1D - 848.06 |
| 4726 | 6 | NC-42 (W Academy St) | Lawrence St | | | | | | | | | | | | | | 1 | | Type 1C - 848.06 |
| 4727 | 6 | NC-42 (W Academy St) | Lawrence St | | 5 | 5 | 3 | 3 | | | | | | | | | 1 | | Type 1D - 848.06 |
| 4732 | 7 | NC-42 (W Academy St) | Bay Tree St | | | | | | | | | | | | | | 1 | | Type 1C - 848.06 |
| 5043 | 7 | NC-42 (W Academy St) | Bay Tree St | | | | | | | | | | | | | | 1 | | Type 1 Modified - 848.06 |
| 4736 | 8 | NC-42 (W Academy St) | N West St | | | | 3 | | | | | | | | | | 1 | | Type 1 Modified - 848.06 |
| 4747 | 9 | NC-42 (W Academy St) | Fidelity Bank (100 S Main St) W Academy St Entrance | | | | | | | | 1 | | | | | | 1 | | Type 1 - 848.06 |
| 4749 | 9 | NC-42 (W Academy St) | Fidelity Bank (100 S Main St) W Academy St Entrance | | | | | | | | 1 | | | | | | 1 | | Type 1 - 848.06 |
| 26063 | 9 | NC-42 (W Academy St) | Spring Ave | | 12 | | | | 3 | | | | | | | | | 1 | Remove Ramp |
| Sub-Total | | | | 42 | 42 | 15 | 63 | 21 | 39 | 0 | 2 | 0 | 1 | 70 | 4 | 6 | 21 | 2 | |

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page.; (2) Curb ramp work done in areas with brick paver sidewalk are to be constructed with concrete. Brick pavers are to be removed only as necessary. Any existing brick outside of the limits of the work are to be neatly sawcut along the edge of the curb ramp and reset in order to tie flush with the work itself.; (3) Excess removed brick pavers are to be neatly stacked along the North wall of the city owned lot located Northeast of the E Academy St and Main St intersection. See map inset 11 for more details.