Docusign Envelope ID: 3F695BA1-145D-4178-BC44-C4E6F4A08743

5/26/20

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the contract lump sum price for Grading.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

STATION L	Uncl. Exc. (Cu.yd)	Embt (Cu.yd)
10+00.00	0	0
10+50.00	6.306	18.988
11+00.00	7.053	118.829
11+50.00	4.997	247.499
12+00.00	3.224	250.513
12+50.00	5.311	283.475
13+00.00	12.912	363.302
13+50.00	23.875	416.618
14+00.00	44.31	483.131
14+50.00	72.469	629.129
15+00.00	81.384	832.883
15+50.00	70.21	1,040.51
16+00.00	69.007	1244.016
16+50.00	81.289	1386.26
17+00.00	86.264	1498.488
17+50.00	86.942	1563.561
18+00.00	95.539	1623.435
18+50.00	62.468	1794.646
18+63.75	7.707	532.652
21+66.25	0	0
22+00.00	45.354	756.511
22+50.00	54.798	851.89
23+00.00	34.591	517.038
23+50.00	93.677	198.734
24+00.00	239.576	67.116
24+50.00	344.614	66.346
25+00.00	351.895	83.193
25+50.00	298.192	110.223
26+00.00	206.555	131.796
26+50.00	138.716	101.965
27+00.00	101.262	48.496
27+50.00	58.887	36.794
28+00.00	31.818	55.631
28+50.00	42.188	63.221
29+00.00	64.762	54.638
29+50.00	66.834	31.917
30+00.00	55.254	8.744

NOTE:
1. A PORTION OF THE UNCLASSFIED MATERIAL THAT IS ACCEPTABLE, BUT NOT TO BE USED IN THE TOP OF 3' EMBANKMENT OR BACKFILL. THESE SOILS MAY BE UTILIZED IN AREAS OUTSIDE THE PAVEMENT SECTION OR IN LOWER PORTION OF HIGH FILLS AT THE DISCRETION OF THE ENGINEER. PLEASE REFER GEOTECH RECOMMENDATIONS FOR MORE DETAILS.

BR-0063
X | 001

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
ANSON COUNTY

ROADWAY DESIGN UNIT

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 054013 ENGINEER
DocuSigned by: 1DD6ED5B82074A8...
10/24/2024

HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 047056 ENGINEER
DocuSigned by: FE7F0FA3B6A9438...
10/24/2024

PREPARED BY

ARCADIS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS