


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

## TEMPORARY DRAINAGE AT END BENT







FOR ONE END BENT BAR | No. | SIZE | TYPE | LENGTH | WEIGHT #9 | 1 | 47'-0" 28 #4 | STR | 23'-7" 441 #4 | STR | 2'-5" 19 D1 | 26 | #8 | STR | 2'-3" 156 1,024 64 | #5 | 2 | 15′-4″ #4 | STR | 2'-11" 23 12 12 #4 | STR | 23'-7" 189 S1 | 56 | #4 | 3 | 10'-5" 390 56 #4 4 3′-2″ 118 S3 | 28 | #4 5 6′-6″ 122 U1 | 39 | #4 | 6 | 96 3′-8″ V1 | 76 | #4 | STR | 7'-8" 389 V2 | 78 | #4 | STR | 5'-9" 300 REINFORCING STEEL 4,545 LBS. (FOR ONE END BENT)


CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)


POUR 1 CAP, LOWER PART OF WINGS AND CONCRETE COLLARS

POUR 2 BACKWALL AND UPPER 8.7 C.Y. PART OF WINGS

23.7 C.Y.

TOTAL CLASS A CONCRETE 31.8 C.Y.





CORROSION PROTECTION FOR STEEL PILES DETAIL

END BENT 1 SHOWN, END BENT 2 SIMILAR.

BEARING AND 2"CL. #8D1 DOWEL #4U1— 1-#4K2 — (EACH FACE) CONST. JT.-4-#9B1 — 4-#4B2 @ 4"CTS. (CENTERED OVER 1-#4B2 — FILL FACE— (EACH FACE) PILES) #4B3-— #4S3 2-#9 B1 2"CL.(TYP.)— 2-**#**9B1 © HP 12 X 53 - 3"HIGH BEAM BOLSTERS STEEL PILE— € HP 12 X 53 STEEL BRACE PILE 1'-41/2" 1'-41/2" 2'-9"

11" 8" 1'-2"

1'-0"

1'-101/2"

SECTION A-A

(CONCRETE COLLAR NOT SHOWN, SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL.")

BR-0063 PROJECT NO. **ANSON** COUNTY 20+15.00 -L-STATION:

> STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

> > **SUBSTRUCTURE**

SEAL 046289

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

| N CARO. | END | BENT | DETAILS |
|---------|-----|------|---------|
| CAROLLA |     |      |         |

**REVISIONS** SHEET No. S-14 DATE: TOTAL SHEETS

K. E. LOFTON DATE : 6–22 G. P. HOOVER DATE : 9-23 CHECKED BY ENGINEER OF RECORD: G. P. HOOVER DATE: 9-23

PLANS PREPARED BY :
ARCADIS CARY, NORTH CAROLINA 27518

STD. No. EB\_33\_90S4\_39BB

ASSEMBLED BY: K.E.LOFTON DATE: 6-22 CHECKED BY: G.P.HOOVER DATE: 9-23 DRAWN BY: WJH 12/11 MAA/THC REV. 4/17 CHECKED BY : AAC 12/11

NC LICENSE No. 0486277 10/2/2024