

PROPOSED ALIGNMENT CONTROL SHEET

L

TYPE	STATION	NORTH	EAST
POT	10+00.00	638596.3592	1519517.9612
PC	21+64.51	638073.9726	1520558.7303
PCC	22+73.82	638047.5048	1520663.8908
PCC	24+93.48	638172.1210	1520823.8990
PT	25+92.63	638268.8725	1520813.0562
PC	26+17.65	638291.2386	1520801.8352
PT	27+63.69	638376.5183	1520689.5202
POT	28+04.38	638384.3243	1520649.5886

RPB

TYPE	STATION	NORTH	EAST
POT	10+00.00	638338.3364	1520032.0290
PC	15+08.43	637953.8292	1520364.6789
PT	15+90.58	637885.5240	1520409.9063
POT	16+88.86	637797.3048	1520453.2311

LPA

TYPE	STATION	NORTH	EAST
POT	10+00.00	638283.8786	1520140.5273
PC	10+39.22	638319.5718	1520124.2732
PT	11+51.70	638421.8715	1520147.0523
PC	11+52.51	638422.3988	1520147.6715
PT	12+39.79	638445.9335	1520229.0305
POT	12+55.07	638443.7689	1520244.1586

Y

TYPE	STATION	NORTH	EAST
POT	10+00.00	639024.6348	1520630.0145
PC	11+25.38	638903.8516	1520596.3902
PT	15+90.69	638449.0764	1520499.3223
PC	15+96.37	638443.4543	1520498.4779
PT	20+19.18	638022.6092	1520460.3561
POT	28+66.25	637175.9625	1520433.5817

LPC

TYPE	STATION	NORTH	EAST
POT	10+00.00	638073.9726	1520558.7303
PC	11+90.85	637988.3573	1520729.3046
PT	12+55.19	637946.7227	1520777.4873
PC	12+66.25	637937.6646	1520783.8282
PT	14+69.87	637781.3708	1520716.3825
POT	14+75.84	637780.5062	1520710.4738

REVISIONS

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.