



**PROJECT NOTES (FIBER):**

1. THE WIRELESS CLOSED LOOP SYSTEM SHALL BE MAINTAINED.
2. FIBER OPTIC CABLE EQUIPMENT AS SHOWN ON PLANS SHALL BE INSTALLED FOR FUTURE USE.
3. ALL FIBER OPTIC EQUIPMENT SHOWN SHALL BE INSTALLED, BUT NO SPLICING WILL BE PERFORMED. COIL AND CAP ALL FIBER OPTIC CABLES AT ENDS. SPLICING WILL BE DONE BY OTHERS.
4. FIBER OPTIC CABLE SHALL BE TESTED AFTER INSTALLATION TO ENSURE FUTURE COMMUNICATIONS ALONG ROUTE.
5. INSTALL 200' OF SLACK FO CABLE AT THIS LOCATION.

**FIBER INSTALLATION NOTES:**

- 1) CONTACT ENGINEER FOR SPECIFIC ATTACHMENT HEIGHT FOR NCDOT SIGNAL COMMUNICATION CABLE.

Plans Prepared By:  
**DRMP**  
 DRMP, Inc.  
 8210 University Executives Park Drive, Suite 220  
 Charlotte, NC 28262  
 NC License No. F-1524 (704) 332-2289  
 www.DRMP.com

**FINAL**

Prepared For:  

 750 N. Greenfield Place, Garner, NC 27529  
 SCALE: 0 N/A

<b>Camden Road CLS Cable Routing Plans</b>	
Division 6	Cumberland County Hope Mills
PLAN DATE: August 2024	REVIEWED BY: LM Moon
PREPARED BY: JA Wendt/DJW	DRMP PROJ. NO.: 2400555
REVISIONS	INIT. DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

Lisa Moon      10/3/2024  
DATE