



PROJECT NOTES (FIBER):

1. THE WIRELESS CLOSED LOOP SYSTEM SHALL BE MAINTAINED.
2. FIBER OPTIC CABLE EQUIPMENT AS SHOWN ON PLANS SHALL BE INSTALLED FOR FUTURE USE.
3. ALL FIBER OPTIC EQUIPMENT SHOWN SHALL BE INSTALLED, BUT NO SPLICING WILL BE PERFORMED. COIL AND CAP ALL FIBER OPTIC CABLES AT ENDS. SPLICING WILL BE DONE BY OTHERS.
4. FIBER OPTIC CABLE SHALL BE TESTED AFTER INSTALLATION TO ENSURE FUTURE COMMUNICATIONS ALONG ROUTE.
5. INSTALL 200' OF SLACK FO CABLE AT THIS LOCATION.

FIBER INSTALLATION NOTES:

- 1) CONTACT ENGINEER FOR SPECIFIC ATTACHMENT HEIGHT FOR NCDOT SIGNAL COMMUNICATION CABLE.

Plans Prepared By:

DRMP, Inc.
8210 University Executives Park Drive, Suite 220
Charlotte, NC 28262
NC License No. F-1524 (704) 332-2289
www.DRMP.com

<p>FINAL</p> <p>750 N. Greenfield Pkwy., Garner, NC 27529</p>		<p>Camden Road CLS Cable Routing Plans</p>		<p>SEAL</p> <p>Lisa Moon 10/3/2024</p>							
<p>Prepared For:</p> <p>Division 6 Cumberland County Hope Mills</p>		<p>PLAN DATE: August 2024 REVIEWED BY: LM Moon</p> <p>PREPARED BY: JA Wendt/DJW DRMP PROJ. NO.: 2400555</p>									
<p>SCALE: N/A</p>		<p>REVISIONS</p> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	DESCRIPTION				<p>INITIALS DATE</p>	
NO.	DATE	DESCRIPTION									

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED