


PROJECT NOTES (FIBER):

1. THE WIRELESS CLOSED LOOP SYSTEM SHALL BE MAINTAINED.
2. FIBER OPTIC CABLE EQUIPMENT AS SHOWN ON PLANS SHALL BE INSTALLED FOR FUTURE USE.
3. ALL FIBER OPTIC EQUIPMENT SHOWN SHALL BE INSTALLED, BUT NO SPLICING WILL BE PERFORMED. COIL AND CAP ALL FIBER OPTIC CABLES AT ENDS. SPLICING WILL BE DONE BY OTHERS.
4. FIBER OPTIC CABLE SHALL BE TESTED AFTER INSTALLATION TO ENSURE FUTURE COMMUNICATIONS ALONG ROUTE.
5. INSTALL 200' OF SLACK FO CABLE AT THIS LOCATION.

FIBER INSTALLATION NOTES:

- 1) CONTACT ENGINEER FOR SPECIFIC ATTACHMENT HEIGHT FOR NCDOT SIGNAL COMMUNICATION CABLE.



FINAL

	<p>Camden Road CLS Cable Routing Plans</p>							
	<p>Division 6 Cumberland County Hope Mills</p>	<p>PLAN DATE: August 2024 REVIEWED BY: LM Moon</p>						
<p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p>PREPARED BY: JA Wendt/DJW DRMP PROJ. NO.: 2400555</p>	<p>SEAL 022516 ENGINEER LISA M. MOON</p>						
<p>SCALE: 0 N/A</p>	<table border="1"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	INIT.	DATE				<p>Lisa Moon 10/3/2024 DATE</p>
REVISIONS	INIT.	DATE						

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED