


NOTES:

1. NOTIFY THE CITY OF GREENSBORO FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM. NOTIFY THE CITY AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS OPERATIONAL. GREENSBORO SIGNAL SYSTEM MUST BE BACK UP AND OPERATIONAL IN 24-HOURS (SEE ICT).
2. ALL CITY SIGNAL FIBER ATTACHMENT POINTS ARE 12" BELOW THE LOWEST FIBER OPTIC CABLE, FRONT SIDE OF POLE, UNLESS OTHERWISE NOTED.
3. ONCE THE NEW SIGNAL SYSTEM FIBER OPTIC CABLE NETWORK HAS BEEN INSTALLED AND TERMINATED ALONG THE ENTIRE PROJECT, CUT, DELASH, BACKPULL, AND REROUTE THE EXISTING FIBER OPTIC CABLE TO THE SPLICE ENCLOSURES AT SPLICE POINTS "S1" AND "S2" AND CUT OVER TO THE NEW FIBER OPTIC CABLE. CUTTING OVER TO THE NEW FIBER OPTIC CABLE SHALL NOT EXCEED 24 HOURS (SEE ICT) CUTTING OVER TO THE NEW FIBER OPTIC CABLE IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL AND COMMUNICATION WITH THE CENTRAL SYSTEM.

RK&K
 P: (919) 878-8560
 8801 Six Forks Road Suite 700 | Raleigh, North Carolina 27615-2965
 NC License No. F-0112
 www.rk.com
 Responsive People | Creative Solutions

TMP PHASE I - FINAL DESIGN

Prepared for the Offices of:

 Signal System-City of Greensboro
 Signal Communications Plans

Division 07 Guilford County Greensboro
 PLAN DATE: August 2024 REVIEWED BY: D.T. Sears
 PREPARED BY: A.C. Norman REVIEWED BY:

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL
 NORTH CAROLINA
 PROFESSIONAL ENGINEER
 SEAL 056142
 PORTER JONES
 PORTER JONES
 8/22/2024
 SIGNATURE DATE
 CADD Filename: