



**NOTES:**

1. NOTIFY THE CITY OF GREENSBORO FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM. NOTIFY THE CITY AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS OPERATIONAL. GREENSBORO SIGNAL SYSTEM MUST BE BACK UP AND OPERATIONAL IN 24-HOURS (SEE ICT).
2. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE CITY OF GREENSBORO ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
3. ONCE THE NEW SIGNAL SYSTEM FIBER OPTIC CABLE NETWORK HAS BEEN INSTALLED AND TERMINATED ALONG THE ENTIRE PROJECT, CUT, DELASH, BACKPULL, AND REROUTE THE EXISTING FIBER OPTIC CABLE TO THE SPLICE ENCLOSURES AT SPLICE POINTS "S1" AND "S2" AND CUT OVER TO THE NEW FIBER OPTIC CABLE. CUTTING OVER TO THE NEW FIBER OPTIC CABLE SHALL NOT EXCEED 24 HOURS (SEE ICT) CUTTING OVER TO THE NEW FIBER OPTIC CABLE IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL AND COMMUNICATION WITH THE CENTRAL SYSTEM.

**RK&K**  
 P: (919) 878-8560  
 8801 Six Forks Road Suite 700 | Raleigh, North Carolina 27615-2965  
 NC License No. F-0112  
 www.rk.com  
 Responsive People | Creative Solutions

Prepared for the Offices of:  
  
 750 N. Greenfield Pkwy., Garner, NC 27529

**TMP PHASE I - FINAL DESIGN**

Signal System-City of Greensboro  
Signal Communications Plans

Division 07 Guilford County Greensboro

PLAN DATE: August 2024	REVIEWED BY: D.T. Sears
PREPARED BY: A.C. Norman	REVIEWED BY:

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL  
 NORTH CAROLINA PROFESSIONAL ENGINEER  
 SEAL 056142  
 PORTER JONES  
 8/22/2024  
 SIGNATURE DATE  
 CADD Filename: