

SUMMARY OF QUANTITIES - ROADWAY

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0000100000-N	0000400000-N	0106000000-E	0156000000-E	1245000000-E	1260000000-E	1297000000-E	1297000000-E	1297000000-E	1308000000-E		
												MOBILIZATION	CONSTRUCTION SURVEYING	BORROW EXCAVATION	REMOVAL OF EXISTING ASPHALT PAVEMENT	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1.5" DEPTH	MILLING ASPHALT PAVEMENT, 3" DEPTH	MILLING ASPHALT PAVEMENT, 4" DEPTH	MILLING ASPHALT PAVEMENT, 0" TO 3"		
											LS	LS	CY	SY	SMI	TONS	SY	SY	SY	SY			
											MI	FT											
49989.3.1	Columbus	1	US 74 WB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24			715			8.095	11,994	61,227	749	271,246		
		2	US 74 EB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24			660	70		8.043	11,601	61,384	350	268,776		
TOTAL FOR MAP NO. 1											17.66						8.095	11,994	61,227	749	271,246		
TOTAL FOR MAP NO. 2											17.66						8.043	11,601	61,384	350	268,776		
GRAND TOTAL											35.33			1	1	1,380	70	65.50	16,138	23,595	122,611	1,099	540,022
TOTAL SAY														1	1	1,380	70	65.50	16,140	23,595	122,615	1,100	540,025

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1330000000-E	1491000000-E	1523000000-E	1575000000-E	1840000000-E	1880000000-E		
												INCIDENTAL MILLING	ASPHALT CONC BASE COURSE, TYPE B25.0C	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	ASPHALT BINDER FOR PLANT MIX	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	GENERIC PAVING ITEM - ASPHALT CONC SURFACE COURSE, TYPE S9.5C (WEDGING COURSE)		
											SY	TONS	TONS	TONS	LF	TONS			
											MI	FT							
49989.3.1	Columbus	1	US 74 WB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24	7,527	650	58,505	3,575	184,672	1,510		
		2	US 74 EB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24	7,500	615	58,132	3,550	184,630	1,560		
TOTAL FOR MAP NO. 1											17.66						1,510		
TOTAL FOR MAP NO. 2											17.66						1,560		
GRAND TOTAL											35.33			15,027	1,265	116,637	7,125	369,302	3,070
TOTAL SAY														15,030	1,265	116,640	7,125	369,310	3,070

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	3030000000-E	3150000000-N	3210000000-N	3287000000-N	3317000000-N	3360000000-E	3503000000-E	3509000000-E	3515000000-E		
												STEEL BEAM GUARDRAIL	ADDITIONAL GUARDRAIL POSTS	GUARDRAIL END UNITS, TYPE CAT-1	GUARDRAIL END UNITS, TYPE TL-3	GUARDRAIL ANCHOR UNITS, TYPE B-77	REMOVE EXISTING GUARDRAIL	WOVEN WIRE FENCE, 47" FABRIC	4" TIMBER FENCE POSTS, 7'-6" LONG	5" TIMBER FENCE POSTS, 8'-0" LONG		
											LF	EA	EA	EA	EA	LF	LF	EA	EA			
											MI	FT										
49989.3.1	Columbus	1	US 74 WB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24							6,520	429	69		
		2	US 74 EB	FROM EAST OF US 701 BUSINESS TO WEST OF NC 214	1	2	2WD	NO	NO	17.66	24							1,120	74	12		
TOTAL FOR MAP NO. 1											17.66							1,120	74	12		
TOTAL FOR MAP NO. 2											17.66											
GRAND TOTAL											35.33							7,640	503	81		
TOTAL SAY														2,837.5	25	6	16	3	2,300	7,640	503	81