

PROJECT NO.	SHEET NO.
18313.10592124, ETC.	3B-1

SUMMARY OF QUANTITIES

SITE NO	WBS	MILEPOST	SHOULDER LT/RT	613800000-E	002200000-E	031400000-E		024100000-E	109970000-E	111200000-E	149100000-E	152300000-E	157500000-E	204400000-E	207700000-E	303000000-E	328700000-N	336000000-E	342000000-E	364200000-E	364900000-E
				VEGETATIVE DEBRIS REMOVAL AND DISPOSAL CY	UNCLASSIFIED EXCAVATION CY	SELECT MATERIAL, CLASS ***** (CLASS VI) TON	SELECT MATERIAL, CLASS ***** (CLASS VII) TON	GEOTEXTILE FOR ROCK EMBANKMENTS (TYPE 2) SY	CLASS IV SUBGRADE STABILIZATION TON	GEOTEXTILE FOR SUBGRADE STABILIZATION SY	ASPHALT CONC BASE COURSE, TYPE B25.0C TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	ASPHALT BINDER FOR PLANT MIX TON	6" PERFORATED SUBDRAIN PIPE LF	6" OUTLET PIPE LF	STEEL BEAM GUARDRAIL LF	GUARDRAIL END UNITS, TYPE TL-3 EA	REMOVE EXISTING GUARDRAIL LF	STEEL BEAM GUARDRAIL, 2'-1" HEIGHT TRANSITION LF	RIP RAP, CLASS A TON	RIP RAP, CLASS B TON
NC 80 Site 45	18313.1059124	11.77	LT/RT	250	100	50	150,000	10,000	50	60	50	30	5	215	25	250	2	250		50	100
NC 80 Site 46	18313.1059125	11.80	LT/RT	50	350																
NC 80 Site 47	18313.1059126	11.86	LT/RT	20	50	30	3500	1000	50	60	30	20	2	90	15	100	2	250	150	30	75
NC 80 Site 48	18313.1059127	12.11	LT/RT	20	100	40	7500	2800	110	100	75	50	3	290	35	350	2			40	75
GRAND TOTAL				340	600	120	161,000	13,800	210	220	155	100	10	595	75	700	6	500	150	120.0	250.0

NOTES: QUANTITIES ARE ESTIMATED AND MAY CHANGE ACCORDING TO ACTUAL FIELD CONDITIONS.
THE ENGINEER SHALL FIELD MARK ALL SITE LOCATIONS AND LIMITS PRIOR TO BEGINNING CONSTRUCTION AT EACH LOCATION.