

PROJECT NO.	SHEET NO.
18313.1059124, ETC.	3B-2

### SUMMARY OF QUANTITIES

SITE NO	WBS	MILEPOST	SHOULDER LT/RT	440000000-E	440500000-E	441000000-E	444500000-E	481000000-E		496000000-N	600000000-E	601200000-E	602900000-E	603600000-E	608400000-E	611700000-N	825200000-E	883400000-N		883900000-E	885300000-E
				WORK ZONE SIGNS (STATIONARY)	WORK ZONE SIGNS (PORTABLE)	WORK ZONE SIGNS (BARRICADE MOUNTED)	BARRICADES (TYPE III)	PAINT PAVEMENT MARKING LINES (4", WHITE)	PAINT PAVEMENT MARKING LINES (4", YELLOW)	INLAID CRADLE MARKERS	TEMPORARY SILT FENCE	SEDIMENT CONTROL STONE	SAFETY FENCE	MATTING FOR EROSION CONTROL	SEEDING & MULCHING	RESPONSE FOR EROSION CONTROL	REINFORCING STEEL (RETAINING WALL)	MICROPILE, AVERAGE LENGTH	MICROPILE PROOF TESTS	MICROPILE, ADDITIONAL LENGTH OVER AVERAGE	SHOTCRETE
				SF	SF	SF	SF	LF	LF	EA	LF	TON	LF	SY	ACRE	EA	LB	EA	EA	LF	CY
NC 80 Site 45	18313.1059124	11.77	LT/RT	88	88	35	96	1000	1000	7	250	50	50		0.25	1					
NC 80 Site 46	18313.1059125	11.80	LT/RT								100		50		0.13	1					
NC 80 Site 47	18313.1059126	11.86	LT/RT					500	500	3	200	25	50	200	0.25	1					
NC 80 Site 48	18313.1059127	12.11	LT/RT	88	88	35	96	500	500	5	200	25	50	200	0.25	1	15,900	155	7	50	135
<b>GRAND TOTAL</b>				<b>176</b>	<b>176</b>	<b>70</b>	<b>192</b>	<b>2,000</b>	<b>2,000</b>	<b>15</b>	<b>750</b>	<b>100</b>	<b>200</b>	<b>400</b>	<b>0.88</b>	<b>4</b>	<b>15,900</b>	<b>155</b>	<b>7</b>	<b>50</b>	<b>135</b>

**NOTES:** QUANTITIES ARE ESTIMATED AND MAY CHANGE ACCORDING TO ACTUAL FIELD CONDITIONS.  
THE ENGINEER SHALL FIELD MARK ALL SITE LOCATIONS AND LIMITS PRIOR TO BEGINNING CONSTRUCTION AT EACH LOCATION.