

PROJECT NO.	SHEET NO.	TOTAL NO.
2025CPT.08.11.10621	11	
2025CPT.08.11.20621		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1245000000-E	1260000000-E	1297000000-E	1330000000-E	1519000000-E	1575000000-E	1704000000-E	1775500000-E	1838000000-E	1838500000-N	2830000000-N	2845000000-N		
												SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	ADJUST MANHOLES	ADJUST METER OR VALVE BOX		
												SMI	TON	SY	SY	TONS	TONS	TONS	SY	GAL	WK	EA	EA		
2025CPT.08.11.10621	Montgomery	1	NC-134	FROM SR 1324 (GLENN RD) TO SR 1377 (ATKINS DAIRTY RD)	1	2	2WU	4.55	23	1.68	6.23			61,395	4,875	5,467	357	35				2			
TOTAL FOR MAP NO. 1								4.55						61,395	4,875	5,467	357	35				2			
2025CPT.08.11.10621	Montgomery	2	NC-109	FROM RICHMOND COUNTY LINE TO SR 1100 (MCKAY HILL ROAD)	3	2	2WU	3.48	26	0	3.48	6.96	974.00		1,545	4,506	295	50					2		
TOTAL FOR MAP NO. 2								3.48				6.96	974.00		1,545	4,506	295	50					2		
TOTAL FOR PROJ NO. 2025CPT.08.11.10621								8.03				6.96	974.00		61,395	6,420	9,973	652	85					2	2
2025CPT.08.11.20621	Montgomery	3	SR-1540 / VALLEY VIEW CHURCH RD	FROM SR 1541 (BOWLES RD) TO SR 1005 (PEKIN RD)	2	2	2WU	1.73	17	0	1.73	3.46	484.00		225	1,577	104	30	17,300.00	6,920	1.00				
TOTAL FOR MAP NO. 3								1.73				3.46	484.00		225	1,577	104	30	17,300.00	6,920	1.00				
2025CPT.08.11.20621	Montgomery	4	SR-1541 / BOWLES RD	FROM SR 1540 (VALLEY VIEW CHURCH RD TO RICHMOND COUNTY LINE	2	2	2WU	1.39	20	0	1.39	2.78	389.00		505	1,489	98	30	16,050.00	6,420	1.00				
TOTAL FOR MAP NO. 4								1.39				2.78	389.00		505	1,489	98	30	16,050.00	6,420	1.00				
2025CPT.08.11.20621	Montgomery	5	SR-1349 / ETHER RD	FROM 0.2 MILES NW OF CHAROLAIS DRIVE (NON SYSTEM) TO US-220 ALT	3	2	2WU	0.9	21	0	0.9	1.80	252.00		300	1,012	67	30							
TOTAL FOR MAP NO. 5								0.9				1.80	252.00		300	1,012	67	30							
TOTAL FOR PROJ NO. 2025CPT.08.11.20621								4.02				8.04	1,125.00		1,030	4,078	269	90	33,350.00	13,340	2.00				
GRAND TOTAL								12.05				15.00	2,099.00		61,395	7,450	14,051	921	175	33,350.00	13,340	2.00	2	2	