PROJECT NO.	SHEET NO.	TOTAL NO.
2025CPT.09.07.10801, 2025CPT.09.08.20801	20	
2025CPT.09.18.10301		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4685000000-E 4" X 90 M WHITE THERMO	4685000000-E 4" X 90 M YELLOW THERMO	4687000000-E THERMOPLASTIC PAVEMENT MARKING LINES (4", 240 MILS)	4688000000-E 6" X 90 M WHITE THERMO	4688000000-E 6" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M WHITE THERMO	4700000000-E THERMOPLASTIC PAVEMENT MARKING LINES YELLOW(12", 90 MILS)	4704000000-E THERMOPLASTIC PAVEMENT MARKING LINES (16", 90 MILS)	4709000000-E THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	4720000000-E THERMO MSG SCHOOL 90 M	4720000000-E THERMO MSG STOP 90 M	4720000000-E THERMO MSG AHEAD 90 M	4720000000-E THERMO RXR 90 M	4725000000-E THERMO LT ARROW 90 M	4725000000-E THERMO RT ARROW 90 M	4725000000-E THERMO STR ARROW 90 M	4725000000-E THERMO STR & RT ARROW 90 M	4725000000-E THERMO LT STR RT ARROW 90 M	4810000000-E 4" WHITE PAINT	4810000000-E 4" YELLOW PAINT	4820000000-E 8" WHITE PAINT	4820000000-E 8" YELLOW PAINT	4830000000-E 16" WHITE PAINT	4835000000-E 24" WHITE PAINT	4840000000-N PAINT MSG SCHOOL	4840000000-N PAINT MSG STOP	4840000000-N PAINT MSG AHEAD	4840000000-N PAINT MSG RXR	4845000000-N PAINT LT ARROW	4845000000-N PAINT RT ARROW	4845000000-N PAINT STR ARROW	4845000000-N PAINT STR & RT ARROW	4845000000-N PAINT LT STR RT ARROW	4895000000-N POLYCARBONATE H-SHAPED MARKERS
								MI	FT			SF	LS	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2025CPT.09.07.10801	Rowan	1	NC-150	FROM JONES RD SR1760 TO IREDELL COUNTY LINE	1	2	2WU	2.87	22.5	0	2.87	315					29,376	29,376															29,376	29,376														210
TOTAL FOR MAP NO. 1								**2.87**				**315**					**29,376**	**29,376**															**29,376**	**29,376**														**210**
2025CPT.09.07.10801	Rowan	2	NC-801	FROM US70 TO SHERRILLS FORD RD SR1526	1	2	2WU	1.785	25-58	8	9.785	200					19,350	20,175			165		150	12				6	3	2			19,350	20,175	165			150	12				6	3	2			175
TOTAL FOR MAP NO. 2								**1.785**				**200**					**19,350**	**20,175**			**165**		**150**	**12**				**6**	**3**	**2**			**19,350**	**20,175**	**165**			**150**	**12**				**6**	**3**	**2**			**175**
2025CPT.09.07.10801	Rowan	3	NC-801	FROM SHERRILLS FORD RD SR1526 TO BEAR POPULAR RD SR1743	1	2	2WU	2.2	25	5.8	8	250				250	23,200	23,200					75		4	5							23,200	23,200				75		4	5							167
TOTAL FOR MAP NO. 3								**2.2**				**250**	*			**250**	**23,200**	**23,200**					**75**		**4**	**5**							**23,200**	**23,200**				**75**		**4**	**5**							**167**
2025CPT.09.07.10801	Rowan	4	NC-801	FROM GRAMPIAN RD SR1848 TO IREDELL COUNTY LINE	1	2	2WU	2.4	25.5	0	2.4	275					25,300	25,300				40	40				2						25,300	25,300			90	65				2						182
TOTAL FOR MAP NO. 4								**2.4**				**275**					**25,300**	**25,300**				**40**	**40**				**2**						**25,300**	**25,300**			**90**	**65**				**2**						**182**
2025CPT.09.07.10801	Rowan	5	NC-801	FROM DAVIE COUNTY LINE BRG#080 TO US70	8	2,3	2WU	6.77	24-42	11.3	18.07	750				480	71,411	70,826					330		8	10		6			4	2	71,411	70,826				330					6			4	2	530
TOTAL FOR MAP NO. 5								**6.77**				**750**				**480**	**71,411**	**70,826**					**330**		**8**	**10**		**6**			**4**	**2**	**71,411**	**70,826**				**330**					**6**			**4**	**2**	**530**
2025CPT.09.07.10801	Rowan	6	US-601	FROM DAVIE COUNTY LINE BRG# 074 TO W INNES ST SR2200	8	2,3	2WU	5.16	27-36	17.74	22.9	575					59,335	55,040			95		36					2	1				59,335	55,040		95		36					2	1				400
TOTAL FOR MAP NO. 6								**5.16**				**575**					**59,335**	**55,040**			**95**		**36**					**2**	**1**				**59,335**	**55,040**		**95**		**36**					**2**	**1**				**400**
TOTAL FOR PROJ NO. 2025CPT.09.07.10801								**21.185**				**2,365**	*			**730**	**227,972**	**223,917**			**260**	**40**	**631**	**12**	**12**	**15**	**2**	**14**	**4**	**2**	**4**	**2**	**227,972**	**223,917**	**165**	**95**	**90**	**656**	**12**	**4**	**5**	**2**	**14**	**4**	**2**	**4**	**2**	**1,664**
																	451,889							**41**						**26**			**451,889**		**260**				**23**				**26**				
2025CPT.09.08.20801	Rowan	7	SR-2120 / LONG FERRY RD	FROM LEONARD RD SR2168 TO LEONARD RD SR2168	2	2	2WU	1.8	24	2.8	4.6	200					19,042	19,042																															
TOTAL FOR MAP NO. 7								**1.8**				**200**					**19,042**	**19,042**																															
2025CPT.09.08.20801	Rowan	8	SR-2120 / LONG FERRY RD	FROM LEONARD RD SR2168 TO EOM	2	2	2WU	2.34	21.5	4.6	6.94	275					24,400	24,400																															
TOTAL FOR MAP NO. 8								**2.34**				**275**					**24,400**	**24,400**																															
2025CPT.09.08.20801	Rowan	9	SR-2528 / HEILIG RD	FROM FAITH RD SR1006 TO OLD CONCORD RD SR1002	2	2	2WU	1	24.5	0	1	115		11,210	12,532				105									5	4																			
TOTAL FOR MAP NO. 9								**1**				**115**		**11,210**	**12,532**				**105**									**5**	**4**																			
2025CPT.09.08.20801	Rowan	10	SR-2026 / CHARLES ST	FROM 3RD ST SR2037 TO OAKWOOD ST SR2026	3,7	2	2WU	0.392	25	0.375	0.767	50		4,422	4,422								50	6									4,422	4,422				100	6									
TOTAL FOR MAP NO. 10								**0.392**				**50**		**4,422**	**4,422**								**50**	**6**									**4,422**	**4,422**				**100**	**6**									
2025CPT.09.08.20801	Rowan	11	SR-2825 / S WHITEHEAD AVE	FROM US29/ N SALISBURY AVE TO 7TH ST SR1912	3,5	2,3	2WU	1.18	21-32	0	1.18	150		3,120	11,284								280	12				1			1		3,120	11,284				380	12				1			1		
TOTAL FOR MAP NO. 11								**1.18**				**150**		**3,120**	**11,284**								**280**	**12**				**1**			**1**		**3,120**	**11,284**				**380**	**12**				**1**			**1**		
2025CPT.09.08.20801	Rowan	12	SR-2026 / OAKWOOD DR	FROM CHARLES ST SR2026 TO S WHITEHEAD AVE SR2825	3,5	2	2WU	0.365	23-48	0	0.365	50	*	2,400	3,900								92	12									2,400	3,900				192	12									
TOTAL FOR MAP NO. 12								**0.365**				**50**	*	**2,400**	**3,900**								**92**	**12**									**2,400**	**3,900**				**192**	**12**									
2025CPT.09.08.20801	Rowan	13	SR-1914 / HAWKINSTOWN RD	FROM 7TH ST SR1912 TO OLD MOCKSVILLE RD SR1910	2	2	2WU	1.2	22	0	1.2	140		12,562	12,562																																	
TOTAL FOR MAP NO. 13								**1.2**				**140**		**12,562**	**12,562**																																	
2025CPT.09.08.20801	Rowan	14	SR-2313 / BYRD RD	FROM FAITH RD SR1006 TO SOUTH MAIN ST SR2300	3,5	2,3	2WU	1.09	24.5-49	0	1.09	125		11,280	11,580				120														11,280	11,580		120													
TOTAL FOR MAP NO. 14								**1.09**				**125**		**11,280**	**11,580**				**120**														**11,280**	**11,580**		**120**													
2025CPT.09.08.20801	Rowan	15	SR-2300 / S MAIN ST	FROM US52 TO FAITH RD SR1006	3,5	2	2WU	2.835	24	0	2.835	325		9,426	29,776							80	28		4	5	4						9,426	29,776			180	78		4	5	4							
TOTAL FOR MAP NO. 15								**2.835**				**325**		**9,426**	**29,776**							**80**	**28**		**4**	**5**	**4**						**9,426**	**29,776**			**180**	**78**		**4**	**5**	**4**							
2025CPT.09.08.20801	Rowan	16	SR-2131 / DUNNS MOUNTAIN RD	FROM US52 TO STOKES FERRY RD SR1004	2,6	2	2WU	1.355	23	1.785	3.14	150		14,580	14,580																																	
TOTAL FOR MAP NO. 16								**1.355**				**150**		**14,580**	**14,580**																																	
2025CPT.09.08.20801	Rowan	17	SR-1509 / MILLER RD	FROM NC150 TO NC152	4	2	2WU	5.47	23	0	5.47	615					57,668	57,668															57,668	57,668															
TOTAL FOR MAP NO. 17								**5.47**				**615**					**57,668**	**57,668**															**57,668**	**57,668**															
2025CPT.09.08.20801	Rowan	18	SR-1506 / SHUE RD	FROM GRACE CHURCH RD SR1503 TO N MAIN ST SR2740	2,3	2	2WU	3.01	22	0	3.01	335		31,362	31,362					162			103	12									31,362	31,362	162			203	12									
TOTAL FOR MAP NO. 18								**3.01**				**335**		**31,362**	**31,362**					**162**			**103**	**12**									**31,362**	**31,362**	**162**			**203**	**12**									
TOTAL FOR PROJ NO. 2025CPT.09.08.20801								**22.037**				**2,530**	*	**100,362**	**131,998**		**101,110**	**101,110**	**225**	**162**		**80**	**553**	**42**	**4**	**5**	**4**	**6**	**4**		**1**		**119,678**	**149,992**	**162**	**120**	**180**	**953**	**42**	**4**	**5**	**4**	**1**			**1**	
														232,360			**202,220**		**387**					**55**					**11**				**269,670**		**282**				**55**				**2**				
2025CPT.09.18.10301	Davie	19	NC-801 S	FROM US601 TO ROWAN COUNTY LINE BRG#080	8	2	2WU	2.33	25.5-36	0	2.33	255					24,074	24,974			140		47										24,074	24,974		140		47										185
TOTAL FOR MAP NO. 19								**2.33**				**255**	*				**24,074**	**24,974**			**140**		**47**										**24,074**	**24,974**		**140**		**47**										**185**
TOTAL FOR PROJ NO. 2025CPT.09.18.10301								**2.33**				**255**	*				**24,074**	**24,974**			**140**		**47**										**24,074**	**24,974**		**140**		**47**										**185**
																	49,048																**49,048**		**140**												
GRAND TOTAL								**45.552**				**5,150**	**1.000**	**100,362**	**131,998**	**730**	**353,156**	**350,001**	**225**	**162**	**400**	**120**	**1,231**	**54**	**16**	**20**	**6**	**20**	**8**	**2**	**5**	**2**	**371,724**	**398,883**	**327**	**355**	**270**	**1,656**	**54**	**8**	**10**	**6**	**15**	**4**	**2**	**5**	**2**	**1,849**
														232,360			**703,157**		**387**					**96**					**37**				**770,607**		**682**				**78**				**28**				

Note: All quantities listed include turn lanes and are estimates; Payment will be based on actual filed measurements and aquatities recieved