PROJ. REFERENCE NO.	SHEET NO.
BR-0100	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified Excavation, FineGrading, Clearing and Grubbing, Breaking of existing pavement and Removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+25.50	0	0
11+50.00	28	0
11+75.00	57	0
12+00.00	57	0
12+25.00	57	0
12+50.00	57	0
12+75.00	57	0
13+00.00	79	0
13+25.00	125	0
13+50.00	160	0
13+75.00	173	2
14+00.00	145	7
14+25.00	65	7
14+50.00	7	3
14+75.00	1	22
15+00.00	1	82
15+25.00	0	246
15+50.00	0	434
15+75.00	0	529
16+00.00	0	571
16+25.00	0	595
16+50.00	0	613
16+75.00	0	620
17+00.00	0	619
17+14.43	0	356

Station Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+57.01	0	0
18+75.00	0	470
19+00.00	0	650
19+25.00	0	640
19+50.00	0	632
19+75.00	0	628
20+00.00	0	628
20+25.00	0	628
20+50.00	0	624
20+75.00	0	627
21+00.00	0	640
21+25.00	0	657
21+50.00	0	662
21+75.00	0	647
22+00.00	0	604
22+25.00	0	489
22+50.00	0	345
22+75.00	0	253
23+00.00	0	212
23+25.00	0	181
23+50.00	0	84
23+75.00	0	42
24+00.00	7	83
24+25.00	13	85
24+50.00	12	75
24+75.00	14	63
25+00.00	20	52
25+25.00	12	24
25+30.99	2	3

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+65.00	0	0
13+75.00	1	0
14+00.00	2	3
15+42.00	0	0
15+50.00	0	2
15+75.00	1	7
16+00.00	0	27
16+25.00	0	122
16+50.00	0	257
16+75.00	0	283
17+00.00	0	216
17+25.00	0	156
17+50.00	1	122

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+08.17	0	0
19+25.00	0	178
19+50.00	0	269
19+75.00	0	281
20+00.00	0	289
20+25.00	0	300
20+50.00	0	309
20+75.00	0	318
21+00.00	0	320
21+25.00	0	316
21+50.00	0	297
21+75.00	0	261
22+00.00	19	216
22+25.00	48	171
22+50.00	55	131
22+75.00	45	92
23+00.00	37	74
23+25.00	37	43
23+50.00	19	8
23+75.00	0	0
24+00.00	1	3
24+25.00	0	5
24+50.00	0	3
24+75.00	0	2

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.07	0	0
10+25.00	0	6
10+50.00	0	17
10+75.00	0	7
11+00.00	0	1

Station Y1_Det	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+10.51	0	0
10+25.00	0	5
10+50.00	0	6
10+73.40	0	3

Station Dr1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+11.00	0	0
10+25.00	0	32
10+50.00	0	171
10+75.00	0	139
11+00.00	0	28