EARTHWORK BALANCE SHEET

Volumes in Cubic Yards

PROJECT: B-5766 DATE: 10/8/2024 COMP BY: GEOPAK & CHK. BY: KMP SHEET: 1

PROJECT:	D-3/00								DATE	10/6/2024	COMIT D1.	GEOPAK &	CIK. DI.	NIVIP			SHEET: I	
					EXCAVATION					EMBANKMENT				WASTE				
LINE	STATION	то	STATION	TOTAL UNCLASSIFIED EXCAVATION	ROCK EXCAVATION	UNDERCUT EXCAVATION	UNSUITABLE UNCLASSIFIED	SUITABLE UNCLASSIFIED	TOTAL EMBANKMENT	ROCK EMBANKMENT (25%)	EARTH EMBANKMENT	EMBANKMENT +15%	BORROW	ROCK	SUITABLE WASTE	UNSUITABLE WASTE	TOTAL WASTE	
-L-	10+08.83	ТО	13+09.00	39				39	6077	0	6077	6989	6950	0	0	0	0	
-L-	16+83.00	ТО	21+35.00	73				73	4313	0	4313	4960	4887	0	0	0	0	
TOTAL				112	0	0	0	112	10390	0	10390	11949	11837	0	0	0	0	
<u>ADJUSTMENT</u>	IS DUE TO																	
Shoulder Mate	rial								100		100	115	115					
PROJECT TOTAL				112	0	0	0	112	10490	0	10490	12064	11952	0	0	0	0	
Est. 5% to Replace Topsoil in Borrow Pits													598					
GRAND TOTA	L			112				<u> </u>					12550					
SAY				200									12600					
CONTINGENCY ITEMS:																		
Geotextile Fo	r Subgrade Stab.	600 SY	SY					Note 1	ı Lı Ouantiti	os ara ani	, provimato	only The	ı Dosidont	ı Fraince	· · will room	· see-eactio	<u></u>	
Select Granul	ar Material	200	CY						─ Note 1: Quantities are approximate only. The Resident Engineer will recross-section — the work accurately when the project is staked out. These cross-section notes will be ———————————————————————————————————									
Geotextile Fo	r Soil Stab.	300	SY															
Estimate Und	ercut	300	CY					used in computing the final quantities for which the contractor will be paid.										
Estimate Sha	llow Undercut	200	CY					Note 2	2: Earthwo	ork quantit	ties are ca	alculated I	by the roa	dway des	igner. The	se quantit	ties	
Class IV Subo	grade Stab.	400	TONS					are ba	are based in part on subsurface data provided by the geotechnical engineer.									