ADA SUMMARY OF QUANTITIES - PINECREST RD FROM US 70 TO SR 1836

Municipality:	**Raleigh**
WBS Number	**2025CPT.05.10.20921.1**
County:	**Wake**

Sheet No.
22

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	1704000000-E (TON) Patching Existing Pavement	1491000000-E (TON) Asphalt Conc Base Course, Type B25.0C	2542000000-E (LF) 1'-6" Concrete Curb & Gutter	2549000000-E (LF) 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 1'-6" Concrete Curb & Gutter	2752000000-E (LF) Remove 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2738000000-E (SY) Remove And Replace 4" Concrete Sidewalk	2738000000-E (SY) Remove 4" Concrete Sidewalk	2830000000-N (EA) Adjustment of Manholes	2845000000-N (EA) Adjustment of Meter Boxes or Valve Boxes	4116100000-N (EA) Sign Erection, Relocate Type E (Ground Mounted)	4192000000-N (EA) Disposal Of Support, U-Channel	4695000000-E (LF) Thermoplastic Pavement Marking Lines (8", 90 Mils)	4860000000-E (LF) Removal Of Pavement Marking Lines (8")	2655000000-E (SY) 5" Monolithic Concrete Island (Keyed In)	2738000000-E (SY) Remove 5" Monolithic Concrete Islands (Keyed In)	2612300000-N (EA) Retrofit Existing Concrete Curb Ramps	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	2605000000-N (EA) Concrete Curb Ramps	2759000000-N (EA) Remove Concrete Curb Ramps	Improvement Type
15209	1	SR-1835 (Pinecrest Rd)	Office Building (8024 Glenwood Ave) Pinecrest Rd Entrance																					1			Type 1C - 848.06
15210	1	SR-1835 (Pinecrest Rd)	Office Building (8024 Glenwood Ave) Pinecrest Rd Entrance										12											1			Type 1D - 848.06
15205	2	SR-1835 (Pinecrest Rd)	Jeanette Marie Ln					12					3											1			Type 3 Modified - 848D0609
15206	2	SR-1835 (Pinecrest Rd)	Jeanette Marie Ln					12																1			Type 3 Modified - 848D0609
15207	2	SR-1835 (Pinecrest Rd)	Jeanette Marie Ln										3											1			Type 2B - 848.06
15208	2	SR-1835 (Pinecrest Rd)	Jeanette Marie Ln					18				12														1	Remove Ramp
15211	2	SR-1835 (Pinecrest Rd)	Green Lantern St										6											1			Type 1 Modified - 848.06
15212	2	SR-1835 (Pinecrest Rd)	Green Lantern St					10																1			Type 3 Modified - 848D0609
15213	2	SR-1835 (Pinecrest Rd)	Green Lantern St					10																1			Type 3 Modified - 848D0609
15214	3	SR-1835 (Pinecrest Rd)	Office Building (7001 pinecrest Rd)										6											1			Type 1 Modified - 848.06
15197	4	SR-1835 (Pinecrest Rd)	Toscana Dr					5					3											1			Type 3 Modified - 848D0609
15198	4	SR-1835 (Pinecrest Rd)	Toscana Dr									9										9		1			Type 6 - 848.06
15199	4	SR-1835 (Pinecrest Rd)	Toscana Dr																		6					1	Remove Ramp
15200	4	SR-1835 (Pinecrest Rd)	Toscana Dr									9										9		1			Type 6 - 848.06
15201	4	SR-1835 (Pinecrest Rd)	Toscana Dr					16								1								1			Type 1 Modified - 848.06
15202	4	SR-1835 (Pinecrest Rd)	Toscana Dr					16																1			Type 3 - 848D0609
15203	4	SR-1835 (Pinecrest Rd)	Grove Barton Rd										6				1							1			Type 1D - 848.06
15204	4	SR-1835 (Pinecrest Rd)	Grove Barton Rd					15				9														1	Remove Ramp
15193	5	SR-1835 (Pinecrest Rd)	Berry Creek Cir					18					3				1							1			Type 1D - 848.06
15194	5	SR-1835 (Pinecrest Rd)	Berry Creek Cir					15				9														1	Remove Ramp
15195	5	SR-1835 (Pinecrest Rd)	Berry Creek Cir					15																1			Type 1D - 848.06
15196	5	SR-1835 (Pinecrest Rd)	Berry Creek Cir					15				9														1	Remove Ramp
26087	6	SR-1835 (Pinecrest Rd)	Tanglewild Dr	7				25			5	14		3		2									1		Type 1C - 848.06
26088	6	SR-1835 (Pinecrest Rd)	Tanglewild Dr					40				3													1		Type 1C - 848.06
15184	7	SR-1835 (Pinecrest Rd)	Aleppo Ln																				1				Retrofit Warnings
15185	7	SR-1835 (Pinecrest Rd)	Aleppo Ln																				1				Retrofit Warnings
15186	7	SR-1835 (Pinecrest Rd)	Aleppo Ln																				1				Retrofit Warnings
15187	7	SR-1835 (Pinecrest Rd)	Wind Mountain Ln										6											1			Standard - 848.06
15188	7	SR-1835 (Pinecrest Rd)	Wind Mountain Ln					18				10														1	Remove Ramp
15191	7	SR-1835 (Pinecrest Rd)	Wind Mountain Ln					23				10														1	Remove Ramp
15192	7	SR-1835 (Pinecrest Rd)	Wind Mountain Ln					12					6											1			Type 1D - 848.06
15180	8	SR-1835 (Pinecrest Rd)	Landguard Dr														1							1			Type 1D - 848.06
15181	8	SR-1835 (Pinecrest Rd)	Landguard Dr					20				9														1	Remove Ramp
15182	8	SR-1835 (Pinecrest Rd)	Landguard Dr					11					6											1			Type 1C - 848.06
15183	8	SR-1835 (Pinecrest Rd)	Landguard Dr					20																		1	Remove Ramp
15172	9	SR-1835 (Pinecrest Rd)	O'Neal road					12																1			Type 1C - 848.06
15173	9	SR-1835 (Pinecrest Rd)	O'Neal road					18																		1	Remove Ramp
15174	9	SR-1835 (Pinecrest Rd)	O'Neal road					15					6											1			Type 1D - 848.06
15175	9	SR-1835 (Pinecrest Rd)	O'Neal road					15				9														1	Remove Ramp
15148	10	SR-1835 (Pinecrest Rd)	Shopping Center (9101 Leesville Rd) Pinecrest Rd Entrance						7															1			Type 1 Modified - 848.06
15149	10	SR-1835 (Pinecrest Rd)	Shopping Center (9101 Leesville Rd) Pinecrest Rd Entrance						7					12										1			Type 1 Modified - 848.06
15150	10	SR-1835 (Pinecrest Rd)	Seafarer Ct					11					9											1			Type 1C - 848.06
15151	10	SR-1835 (Pinecrest Rd)	Seafarer Ct					15																		1	Remove Ramp
15152	10	SR-1835 (Pinecrest Rd)	Seafarer Ct					15				12														1	Remove Ramp
15153	10	SR-1835 (Pinecrest Rd)	Seafarer Ct					8					6											1			Type 1D - 848.06
15146	11	SR-1835 (Pinecrest Rd)	Business (9221 Fairbanks Dr) Pinecrest Rd Entrance										12											1			Type 1 Modified - 848.06
15147	11	SR-1835 (Pinecrest Rd)	Business (9221 Fairbanks Dr) Pinecrest Rd Entrance										3											1			Type 1 Modified - 848.06
15144	12	SR-1835 (Pinecrest Rd)	SR-1836 (Fairbanks Dr)					8																1			Type 1D - 848.06
15145	12	SR-1835 (Pinecrest Rd)	SR-1836 (Fairbanks Dr)					18				6														1	Remove Ramp
15154	12	SR-1835 (Pinecrest Rd)	SR-1836 (Fairbanks Dr)					15					3				1							1			Type 1D - 848.06
15155	12	SR-1835 (Pinecrest Rd)	SR-1836 (Fairbanks Dr)					15				12														1	Remove Ramp
-	-	-	-	-	-		-	93*	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Sub-Total for Pinecrest Rd From US 70 To SR 1836				**7**	**0**	**0**	**0**	**604**	**14**	**0**	**5**	**142**	**99**	**15**	**0**	**3**	**4**	**0**	**0**	**0**	**6**	**18**	**3**	**31**	**2**	**15**	

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) *Contingency line item amount provided for adjustments outside of curb ramp pay limits.