

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

**Kimley » Horn**  
421 FAYETTEVILLE STREET, SUITE 600  
RALEIGH, NC 27601

|                                  |                    |
|----------------------------------|--------------------|
| PROJECT REFERENCE NO.<br>R-5930B | SHEET NO.<br>EC-3B |
|----------------------------------|--------------------|

***SOIL STABILIZATION TIMEFRAMES***

| <i>SITE DESCRIPTION</i>                      | <i>STABILIZATION TIME</i> | <i>TIMEFRAME EXCEPTIONS</i>   |
|--|---------------------------|---|
| PERIMETER DIKES, SWALES, DITCHES AND SLOPES  | 7 DAYS                    | NONE  |
| HIGH QUALITY WATER (HQW) ZONES               | 7 DAYS                    | NONE  |
| SLOPES STEEPER THAN 3:1                      | 7 DAYS                    | IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.  |
| SLOPES 3:1 TO 4:1                            | 14 DAYS                   | 7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH WITH SLOPES STEEPER THAN 4:1.<br>7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES |
| ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1 | 14 DAYS                   | 7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES   |