PROJECT REFERENCE NO.	SHEET NO.
B-5845	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

STRAW & EXCELSIOR MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
DITCHLINE STRAW MATTING					
4	L	24+00	26+00	LT	425
DITCHLINE EXCELSIOR MATTING					
4	L	17+50	19+00	RT	375
5	L	26+00	31+50	RT	1360
5	L	28+50	29+00	LT	125
5	L	29+50	31+50	LT	310
SLOPE MATTING					
4	L	13+30	14+50	RT	299
4	L	16+50	17+00	RT	106
4	L	19+50	21+00	RT	541
4	L	24+00	25+00	RT	348
4	DR	10+25	11+75	LT	336
4	DR	10+75	11+75	RT	274
	DITCHLINE STRAW MATTING SUBTOTAL				425
	DITCHLINE EXCELSIOR MATTING SUBTOTAL				2170
	SLOPE MATTING SUBTOTAL				1904
MISCELLANEOUS MATTING TO BE DIRECTED BY THE ENGINEER					11,965
			TOTAL		11,965
			SAY		12,000

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)