NOTES


FOR BRIDGE APPROACH FILL, SEE ROADWAY PLANS.

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE JOINT OPENING AT THE APPROACH SLAB/DECK INTERFACE SHALL BE SAWED NO MORE THAN 12 HOURS AFTER THE APPROACH SLAB IS CAST. THE JOINT SHALL BE CLEANED OF ALL DEBRIS BEFORE THE SEALANT IS APPLIED. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1028-3 OF THE STANDARD SPECIFICATIONS.

AT THE CONTRACTORS OPTION "TYPE 1A - ALTERNATE APPROACH FILL" (ROADWAY STD. 423.02) MAY BE CONSTRUCTED AT NO ADDITIONAL COST TO THE DEPARTMENT IN LIEU OF "TYPE 1 - APPROACH FILL".



MATERIAL CONST. JT. → 13/8" SAWED OPENING DETAIL "A"


__ JOINT SEALER

B-5845 PROJECT NO.____

> CLEVELAND _ COUNTY

22+56.00-L-STATION:_

SHEET 2 OF 2



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

STANDARD

BRIDGE APPROACH SLAB DETAILS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED TGS ENGINEERS
201 W. MARION ST STE 200
SHELBY, NC 28150
PH (704) 476–0003
CORP. LICENSE NO.: C-0275

REVISIONS SHEET NO. S-40 DATE: NO. BY: DATE: BY: TOTAL SHEETS

STD. NO. BAS5

<pre></pre>
SEE DETAIL "A"
ROADWAY — 6" — #5 B1 — #4 A1
CONST. JT.
*4 A2
SEE SUPERSTRUCTURE
APPROVED WIRE BAR SUPPORTS @ 3'-0"CTS. PREVENT BOND 2 LAYERS OF 30 LB. ROOFING FELT TO PREVENT BOND 10"
\frac{1}{2}
TYPE 1 APPROACH FILL, SEE
ROADWAY STANDARD DRAWING 423.01
\mathcal{N}
† NORMAL TO END BENT
SEE INTEGRAL END BENT ————————————————————————————————————
SECTION THRU SLAB

ASSEMBLED BY : CHECKED BY :

DRAWN BY : TLA CHECKED BY : GM

JLA MGC

10/05 REV. 12/17 5/06 REV. 6/19 REV. 7/23

DATE: 4/22 DATE: 5/22

MAA/GM BNB/THC BNB/SNM