SURVEY CONTROL SHEET


W/EXISTING CENTERLINE ALIGNMENTS PRIOR TO CONSTRUCTION

I, Toynia E.S. Gibbs, PLS, certify that the Project Control was performed under my supervision from an actual GPS survey made under my supervision and the following information was used to perform the survey:

Class of survey: AA Type of GPS field procedure:VRS Dates of survey: February 22, 2023 - May 17, 2023 Datum/Epoch:NAD83 (2011) Published/Fixed-control use: CORS Localized around: U3424-1 Northing: 470729.9010 Easting: 2003980.0510

Combined grid factor:1.0001250200 Geoid model:GEOID09 Units:US SURVEY FEET

I also certify that the Baseline Control for this project was completed under my direct and responsible charge from an actual survey made under my supervision; that all horizontal closures had a minimum ratio of precision of 1:20,000 (Class AA) and Vertical accuracy to Class A. Field work was performed in April 2023 - May 2023, and all coordinates are based on NAD 83/2011 and all elevations are based on NAVD 88; that this survey was performed to meet the




PROJECT REFERENCE NO. U-4405B RW02C-2 Location and Surveys

ESP ASSOCIATES, INC 2200 GATEWAY CENTRE BLVD. SUITE 216 MORRISVILLE, NC 27560

PROJECT SURVEYOR: TOYNIA E.S. GIBBS LICENSE NO.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



NOTES:

- 1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
- 2. THE SURVEY CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
- 3. NOT TO SCALE