

<div>401</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>WRONG WAY</div><div>42" X 30"</div><div>R5-1a</div></div>	<div>402</div> <div>QUANTITY REQ'D 22</div> <div><div>STOP</div><div>36" X 36"</div><div>R1-1</div></div> <div>TWO "U" POST PER SIGN (MOUNT BELOW SIGN #403 IN 22 INSTALLATIONS)</div>	<div>403</div> <div>QUANTITY REQ'D 32</div> <div><div>ONE WAY</div><div>54" X 18"</div><div>R6-1</div></div> <div>TWO "U" POST PER SIGN (MOUNT BACK TO BACK WITH SIGN #404 IN 9 INSTALLATIONS)</div>	<div>404</div> <div>QUANTITY REQ'D 24</div> <div><div>ONE WAY</div><div>54" X 18"</div><div>R6-1</div></div> <div>TWO "U" POST PER SIGN (MOUNT BACK TO BACK WITH SIGN #403 IN 9 INSTALLATIONS)</div>	<div>405</div> <div>QUANTITY REQ'D 15</div> <div><div><div></div></div><div>24" X 30"</div><div>R4-7</div></div> <div>ONE "U" POST PER SIGN</div>	<div>406</div> <div>QUANTITY REQ'D 15</div> <div><div></div><div>18" X 18"</div><div>OM1-3</div></div> <div>MOUNT BELOW SIGN #405</div>	<div>TIP NO. U-4405B</div> <div>SHEET NO. SIGN-2</div> <div>APPROVED: Regina M. Muncey</div> <div>DATE: 10/18/2024</div> <div>SEAL</div> <div>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</div> <div>Stantec</div>
<div>407</div> <div>QUANTITY REQ'D 1</div> <div><div>DO NOT ENTER</div><div>36" X 36"</div><div>R5-1</div></div> <div>ONE "U" POST PER SIGN</div>	<div>408</div> <div>QUANTITY REQ'D 3</div> <div><div>AHEAD</div><div>24" X 12"</div><div>W16-9p</div></div> <div>(MOUNT BELOW SIGN #438 IN 2 INSTALLATIONS & BELOW #419 IN 1 INSTALLATION)</div>	<div>409</div> <div>QUANTITY REQ'D 5</div> <div><div>SPEED LIMIT 45</div><div>30" X 36"</div><div>R2-1</div></div> <div>ONE "U" POST PER SIGN</div>	<div>410</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>SPEED LIMIT 35</div><div>30" X 36"</div><div>R2-1</div></div>	<div>411</div> <div>QUANTITY REQ'D 7</div> <div><div><div></div></div><div>30" X 30"</div><div>W12-1</div></div> <div>ONE "U" POST PER SIGN</div>	<div>412</div> <div>QUANTITY REQ'D 3</div> <div><div>RIGHT LANE MUST TURN RIGHT</div><div>36" X 36"</div><div>R3-7</div></div> <div>ONE "U" POST PER SIGN</div>	<div>413</div> <div>QUANTITY REQ'D 2</div> <div><div>LEFT LANE MUST TURN LEFT</div><div>36" X 36"</div><div>R3-7</div></div> <div>ONE "U" POST PER SIGN</div>
<div>414</div> <div>QUANTITY REQ'D 5</div> <div><div><div></div></div><div>36" X 36"</div><div>R3-4</div></div> <div>ONE "U" POST PER SIGN</div>	<div>415</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>H</div><div>24" X 24"</div><div>D9-2</div></div>	<div>416</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>TRAUMA CENTER</div><div>24" X 12"</div><div>D9-13dP</div></div>	<div>417</div> <div>QUANTITY REQ'D 2</div> <div><div><div>STOP</div><div>HERE FOR</div><div></div></div><div>36" X 36"</div><div>R1-5b (LEFT)</div></div> <div>ONE "U" POST PER SIGN</div>	<div>418</div> <div>QUANTITY REQ'D 2</div> <div>(BACKGROUND COLOR SHALL BE FLUORESCENT YELLOW-GREEN)</div> <div><div><div>SCHOOL SPEED LIMIT 35</div></div><div>36" X 36"</div><div>S4-5</div></div> <div>ONE "U" POST PER SIGN</div>	<div>419</div> <div>QUANTITY REQ'D 2</div> <div>(BACKGROUND COLOR SHALL BE FLUORESCENT YELLOW-GREEN)</div> <div><div><div></div></div><div>36" X 36"</div><div>S1-1</div></div> <div>ONE "U" POST PER SIGN</div>	<div>420</div> <div>QUANTITY REQ'D 1</div> <div>(BACKGROUND COLOR SHALL BE FLUORESCENT YELLOW-GREEN)</div> <div><div>SCHOOL</div><div>24" X 8"</div><div>S4-3p</div></div> <div>(MOUNT BELOW SIGN #419 IN 3 INSTALLATIONS) (MOUNT ABOVE SIGN #410 IN 4 INSTALLATIONS)</div>
<div>421</div> <div>QUANTITY REQ'D 1</div> <div>(BACKGROUND COLOR SHALL BE FLUORESCENT YELLOW-GREEN)</div> <div><div><div></div></div><div>24" X 12"</div><div>W16-7p</div></div> <div>(MOUNT BELOW SIGN #438 IN 1 INSTALLATIONS)</div>	<div>422</div> <div>QUANTITY REQ'D 2</div> <div>(BACKGROUND COLOR SHALL BE FLUORESCENT YELLOW-GREEN)</div> <div><div><div></div></div><div>24" X 12"</div><div>W16-7p</div></div> <div>(MOUNT BELOW SIGN #438 IN 2 INSTALLATIONS)</div>	<div>423</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div><div>SCHOOL SPEED LIMIT 35 WHEN FLASHING</div></div><div>24" X 48"</div><div>S5-1</div></div>	<div>424</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>END SCHOOL ZONE</div><div>24" X 30"</div><div>S5-2</div></div>	<div>425</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div><div>7 00 9 00 AM 2 00 4 00 PM SCHOOL DAYS</div></div><div>24" X 10"</div><div>S4-1p</div></div>	<div>426</div> <div>QUANTITY REQ'D 2</div> <div><div>LANE ENDS MERGE RIGHT</div><div>36" X 36"</div><div>W9-2</div></div> <div>ONE "U" POST PER SIGN</div>	<div>427</div> <div>QUANTITY REQ'D 1</div> <div><div><div></div></div><div>36" X 36"</div><div>W4-3</div></div> <div>ONE "U" POST PER SIGN</div>
<div>428</div> <div>QUANTITY REQ'D 2</div> <div><div><div>STOP</div><div>HERE FOR</div><div></div></div><div>36" X 36"</div><div>R1-5b (RIGHT)</div></div> <div>ONE "U" POST PER SIGN</div>	<div>429</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div><div></div><div>SPEED LIMIT 45</div></div><div>36" X 36"</div><div>W3-5</div></div>	<div>430</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div><div></div></div><div>36" X 36"</div><div>W10-2</div></div>	<div>431</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>DO NOT STOP ON TRACKS</div><div>24" X 30"</div><div>R8-8</div></div>	<div>432</div> <div>QUANTITY REQ'D 0</div> <div>SIGN NOT USED IN THIS SEGMENT OF U-4405</div> <div><div>STOP HERE ON RED</div><div>24" X 36"</div><div>R10-6</div></div>	<div>TYPE "E" SIGNS</div>	