

GENERAL NOTE:

FIVE (5) DAYS BEFORE BEGINNING ANY WORK ON THE SIGNAL COMMUNICATIONS SYSTEM, THE CONTRACTOR SHALL CONTACT THE CITY OF FAYETTEVILLE TRAFFIC SERVICES DIVISION AT 910–433–1660. WORK IS NOT COMPLETE UNTIL ALL MODIFICATIONS TO THE SIGNAL COMMUNICATION SYSTEM HAVE BEEN MADE AND THE SYSTEM IS OPERATIONAL.

NOTES:

- 1. AS PART OF TEMPORARY SIGNAL DESIGN 1 (TMP PHASE 1), THE EXISTING CONTROLLER AND CABINET WILL BE RELOCATED TO A NEW CABINET FOUNDATION AND THE EXISTING COMMUNICATION CABLES WILL NEED TO BE BACK-PULLED FROM THE EXISTING CABINET LOCATION AND RECONNECTED AT THE NEW CABINET LOCATION.
- 2. ALL EXISTING FIBER OPTIC SPLICES WERE INSTALLED BY OTHERS AND ARE ASSUMED TO BE INSTALLED PER THE SPLICING DETAILS (SEE SHEETS SCP-9 TO SCP-15). IF ANY DESCREPANCIES ARE NOTED, CONTACT DIVISION AND/OR CITY ENGINEER IMMEDIATELY FOR FURTHER INSTRUCTION.
- 3. EXISTING CABINET RELOCATED ONTO NEW CABINET FOUNDATION.
- 4. EXISTING JOINT USE POLE WITH EXISTING SPARE COILED DROP CABLE. STORE EXTRA DROP CABLE IN JUNCTION BOX AND/OR CABINET.

ASSOCIATED HARDWARE, AS APPLICABLE.

REMOVE ANY REMAINING TEMPORARY MESSENGER CABLE/OTHER

5. RE-SPLICE EXISTING 12-STRAND FIBER OPTIC DROP CABLE AT

License No. F-0672

POWER POLE TO RELOCATED CABINET.

RELOCATED 06-0358 SIGNAL CABINET.

TEMPORARY SIGNAL DESIGN 1 (TMP PHASE 1)





COMMUNICATIONS CABLE CONDUIT ROUTING PLANS

DIVISION 06 CUMBERLAND CO. FAYETTEVIL PLAN DATE: AUGUST 2024 REVIEWED BY: R. MUNCEY FAYETTEVILLE PREPARED BY: REVIEWED BY: L. OVERN REVISIONS

SEAL 43239

Regina M. Muncey 10/8/2022 CADD FILE NAME