PROJECT REFERENCE NO. U-4405B

06-0491 BACK PULL AND RECONNECT STEPS: DISCONNECT EXISTING 12-STRAND FIBER OPTIC DROP CABLE FROM EXISTING 06-0491 SIGNAL CABINET. 2. UNLASH EXISTING 12-STRAND FIBER OPTIC DROP CABLE FROM EXISTING TEMPORARY MESSENGER CABLE SLACK LINE. PULL DROP CABLE FROM EXISTING CABINET TO EXISTING JOINT-USE POWER POLE(#175-2). RELOCATE EXISTING CABINET, CONTROLLER, & ETHERNET SWITCH ONTO NEW CABINET FOUNDATION. REINSTALL/REROUTE EXISTING DROP CABLE THROUGH JOINT-USE POWER POLE (#175-2) TO RELOCATED CABINET. 5. RE-SPLICE EXISTING 12-STRAND FIBER OPTIC DROP CABLE AT

1/4A726. REMOVE ANY REMAINING TEMPORARY MESSENGER 1/4A72CABLE/OTHER ASSOCIATED HARDWARE, AS APPLICABLE. KARR 2 4A 72 - SEE NOTE 4 1 6A 12 BREAKLINE RD 6A 12 US 401 BUSINESS US 401 BUSINESS 06-0491 (RAEFORD RD) (RAEFORD RD) (1)6A 12) 〔1 (14) 2〕 1 6A 12 SEE NOTE 1 SEE NOTE 1, 3

RELOCATED 06-0491 SIGNAL CABINET.

FIVE (5) DAYS BEFORE BEGINNING ANY WORK ON THE SIGNAL COMMUNICATIONS SYSTEM, THE CONTRACTOR SHALL CONTACT THE CITY OF FAYETTEVILLE TRAFFIC SERVICES DIVISION AT 910-433-1660. WORK IS NOT COMPLETE UNTIL ALL MODIFICATIONS TO THE SIGNAL COMMUNICATION SYSTEM HAVE BEEN MADE AND THE SYSTEM IS OPERATIONAL.

NOTES:

GENERAL NOTE:


- 1. AS PART OF TEMPORARY SIGNAL DESIGN 1 (TMP PHASE 1), THE EXISTING CONTROLLER AND CABINET WILL BE RELOCATED TO A NEW CABINET FOUNDATION AND THE EXISTING COMMUNICATION CABLES WILL NEED TO BE BACK-PULLED FROM THE EXISTING CABINET LOCATION AND RECONNECTED AT THE NEW CABINET LOCATION.
- 2. ALL EXISTING FIBER OPTIC SPLICES WERE INSTALLED BY OTHERS AND ARE ASSUMED TO BE INSTALLED PER THE SPLICING DETAILS (SEE SHEETS SCP-9 TO SCP-15). IF ANY DESCREPANCIES ARE NOTED, CONTACT DIVISION AND/OR CITY ENGINEER IMMEDIATELY FOR FURTHER INSTRUCTION.
- 3. EXISTING CABINET RELOCATED ONTO NEW CABINET FOUNDATION.
- 4. EXISTING JOINT USE POLE WITH EXISTING SPARE COILED DROP CABLE. STORE EXTRA DROP CABLE IN JUNCTION BOX AND/OR CABINET.

TEMPORARY SIGNAL DESIGN 1 (TMP PHASE 1)



License No. F-0672

Stantec Consulting Services Inc. 801 Jones Franklin Road Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com



COMMUNICATIONS CABLE CONDUIT ROUTING PLANS

DIVISION 06 CUMBERLAND CO. FAYETTEVIA PLAN DATE: AUGUST 2024 REVIEWED BY: R. MUNCEY FAYETTEVILLE PREPARED BY: REVIEWED BY: L. OVERN REVISIONS



Regina M. Muncey 10/8/202 CADD FILE NAME