TIP NO.	SHEET NO.
U-6011	SIGN-2

APPROVED: DocuSigned by: Steve Miller 9FBC6C15CEEB486...

DATE: 5/1/2024

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037026 ENGINEER STEVEN D. MILLER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ'D 7

R1-1
36" X 36"

TWO "U" POSTS PER SIGN

(402) QUANTITY REQ'D 1

R2-1 (35)
30" X 36"

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 2

R3-7R
30" X 30"

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 4

R4-7
24" X 30"

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D 4

OM1-3
18" X 18"

MOUNT BELOW SIGN 404
IN 4 INSTALLATIONS

(406) QUANTITY REQ'D 2

R6-2R
24" X 30"

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 2

D9-2
24" X 24"

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 2

M6-1
21" X 15"

MOUNT BELOW SIGN 407
IN 2 INSTALLATIONS

(409) QUANTITY REQ'D 1

W11-2
36" X 36"

ONE "U" POST PER SIGN

(410) QUANTITY REQ'D 1

W16-7p
24" X 12"

MOUNT BELOW SIGN 409
IN 1 INSTALLATIONS

(411) QUANTITY REQ'D 1

R1-2
36" x 36"

ONE "U" POST PER SIGN

(412) QUANTITY REQ'D 1

R3-2
36" x 36"

ONE "U" POST PER SIGN

(413) QUANTITY REQ'D 1

R5-1
36" x 36"

ONE "U" POST PER SIGN

TRANSYSTEMS
1 Glenwood Avenue
Raleigh, NC 27603
Tel:919.789.9977
Fax:919.789.9591
License: F-0453

TYPE "E" SIGNS

5/1/2024
R:\2015\SE19.015.02_U-6011 US 70 Shadow Brook Dr-\TP\Traffic\Signing\U-6011_SIGN-2.dgn
lpulmap