

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1308000000-E	1330000000-E	1523000000-E	1524000000-E	1575000000-E	1704000000-E	2830000000-N	2845000000-N	5255000000-N	7444000000-E	7456100000-E
								MI	FT			TON	SMI	TON	SY	SY	SY	TON	TONS	TON	TON	EA	EA	LS	LF	LF
2025CPT.13.07.20591	McDowell	1	SR 1001 (SUGAR HILL ROAD)	FROM SR 1162 (CHARLIE DRIVE) TO PROJECT PAVEMENT JOINT	1	2	2WU	2.45	22.00	7.70	10.15	70	4.90	637			2,135	9,364		567	310					
2025CPT.13.07.20591	McDowell	2	SR 1001 (SUGAR HILL ROAD / WEST HENDERSON STREET)	FROM PROJECT PAVEMENT JOINT TO SR 1183 (STOUT STREET)	2	5	MU	0.98	60.00	10.69	11.67	5			50,102			4,510		267	11	1	1		2,500	750
2025CPT.13.07.20591	McDowell	3	SR 1162 (CHARLIE DRIVE)	FROM SR 1001 (SUGAR HILL DRIVE) TO END OF MAINTENANCE	1	2	2WU	0.56	18.50	0.00	0.56	5	1.12	146				640		41	75					
2025CPT.13.07.20591	McDowell	4	SR 1165 (THREE POINT ROAD/CHAPEL HILL CHURCH LOOP/JACK TAYLOR ROAD)	FROM NC 226 SOUTH TO END OF MAINTENANCE	1	2	2WU	0.73	18.00	0.01	0.74	10	1.46	190			875	715		45	65					
2025CPT.13.07.20591	McDowell	5	SR 1323 (RANKIN DRIVE)	FROM SR 1001 (SUGAR HILL ROAD) TO END OF MAINTENANCE FROM NC 226	3	2	2WU	0.31	22.00	0.00	0.31	10				2,910		425		26	11				200	250
2025CPT.13.07.20591	McDowell	6	SR 1819 (COLLEGE DRIVE)	TO MILE POST 0.53 END OF STATE MAINTENANCE	1,3	2	2WU	0.51	24.00	0.02	0.53	5	0.81	106		1,135	1,185	710		45	60		1			
TOTAL FOR PROJ NO. 2025CPT.13.07.20591								5.54				105	8.29	1,079	50,102	4,045	4,195	16,364		991	532	1	1	1	2,700	1,000
2025CPT.13.07.20121	Burke	7	SR 1102 (GOLF COURSE ROAD)	FROM US 64 BYPASS TO SR 1107 (HOPEWELL ROAD)	1	2	2WU	1.02	19.00	0.02	1.04	8	1.90	247			595	1,025	50	69	110					
2025CPT.13.07.20121	Burke	8	SR 1138 (KATHY ROAD)	FROM US 70 TO SR 1142 (JAMESTOWN ROAD)	1	2	2WU	0.94	23.00	0.01	0.95	40	1.75	228		747	2,125	1,340		86	135					
2025CPT.13.07.20121	Burke	9	SR 1142 (JAMESTOWN ROAD FIRE DEPARTMENT 1)	FROM FIRE DEPARTMENT PARKING TO FIRE DEPARTMENT	4	2	2WU	0.01	24.00	0.33	0.34						287	26		2						
2025CPT.13.07.20121	Burke	10	SR 1142 (JAMESTOWN ROAD FIRE DEPARTMENT 2)	FROM FIRE DEPARTMENT PARKING TO FIRE DEPARTMENT	4	2	2WU	0.01	24.00	4.13	4.14				772			70		4		1				
2025CPT.13.07.20121	Burke	11	SR 1142 (JAMESTOWN ROAD)	FROM SR 1129 (DYSARTSVILLE ROAD) TO US 70 (CARBON CITY ROAD) - .07 MILE PAVEMENT JOINT	1	3	MU	7.59	27.00	0.01	7.60	260	15.18	1,974			10,992	11,957	50	736	572		7		1,750	
2025CPT.13.07.20121	Burke	12	SR 1233 (NORTH POWERHOUSE ROAD)	FROM SR 1234 (BENFIELDS LANDING ROAD)+.01 MILE TO NC 126	1	2	2WU	4.30	18.00	1.32	5.62	82	8.60	1,120			1,360	3,790	70	260	670					
2025CPT.13.07.20121	Burke	13	SR 1234 (BENFIELDS LANDING ROAD FIRE DEPARTMENT)	FROM PARKING FOR FIRE DEPARTENT TO FIRE DEPARTMENT	4	2	2WU	0.01	24.00	0.55	0.56				192			18		1		1				
2025CPT.13.07.20121	Burke	14	SR 1286 (BOYD MOORE AVENUE)	FROM SR 1233 (POWERHOUSE ROAD) TO END OF MAINTENANCE	1	2	2WU	0.33	18.00	0.00	0.33	10	0.64	84				310		21	55					
2025CPT.13.07.20121	Burke	15	SR 1621 (ICARD RHODHISS ROAD)	FROM SR 1624 (DOC PUGH ROAD) TO SR 1611 (RHODHISS ROAD)	1	2	2WU	1.55	21.00	1.65	3.20	50	3.10	403				1,720		103	40		4			
2025CPT.13.07.20121	Burke	16	SR 1786 (MILLER BRIDGE ROAD)	FROM NC 18 PAVEMENT JOINT TO 2024 CONTRACT PAVEMENT JOINT	1	2	2WU	2.43	22.00	0.02	2.45	25			33,482			3,013	100	186	50					
2025CPT.13.07.20121	Burke	17	SR 1922 (ENOLA ROAD)	FROM SR 1924 (OLD NC 18) TO SR 2026 (ARNOLD DRIVE) -0.02 @ PAVEMENT JOINT	1	2	2WU	5.40	21.00	0.01	5.41	180	10.80	1,404			2,103	6,148	50	387	452					
2025CPT.13.07.20121	Burke	18	SR 1940 (PETE BRITTAIN ROAD)	FROM SR 1922 (ENOLA ROAD) PAVEMENT JOINT TO SR (1949 (SALEM ROAD) PAVEMENT JOINT	1	2	2WU	1.62	21.50	0.73	2.35	78	3.25	422			1,818	1,958	100	124	57				250	20
2025CPT.13.07.20121	Burke	19	SR 1940 (OLD COLONY ROAD)	FROM OLD NC 18 TO SR 1922 (ENOLA ROAD) PAVEMENT JOINT	1	2	2WU	0.61	21.50	0.01	0.62	37	1.22	159			300			3	57	1	1			
2025CPT.13.07.20121	Burke	20	SR 1949 (SALEM ROAD)	FROM US 64 TO SR 1956 (BURKEMONT ROAD)+.01 MILE	1	2	2WU	1.23	23.50	0.01	1.24		2.46	320			1,410	1,654	50	104	75	1	2			
TOTAL FOR PROJ NO. 2025CPT.13.07.20121								27.05				770	48.90	6,361	33,482	1,711	20,990	33,029	470	2,086	2,273	2	16		2,000	20
GRAND TOTAL								32.59				875	57.19	7,440	83,584	5,756	25,185	49,393	470	3,077	2,805	3	17	1	4,700	1,020

*NOTE-ALL MAPS, FINAL SURFACE TESTING REQUIRED = NO, WARM MIX ASPHALT REQUIRED = NO.