

K:\RAL_Roadway\011036734 - R-5963A&B\ERosion Control\PSH\CA&R-5963A&B_ero_psh_16dgn

REVISIONS

2/18/2025

- PROP. 5" MONO. CONC. ISLAND
- PROP. PAVED SHOULDER
- PROP. PAVEMENT REMOVAL

NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B
AND TEMPORARY ROCK SILT CHECKS TYPE - A AT
DRAINAGE OUTLETS.

40 x 80 x 3
2 inch Skimmer
with 1.625 inch
Orifice Diameter
12 ft. weir
ID 16.1

78 x 39 x 3
2 inch Skimmer
with 1.625 inch
Orifice Diameter
11 ft. weir
ID 16.2

CONSTRUCTION NOTE 2

24 INCH
TEMPORARY
PIPE

66 x 33 x 3
1.5 inch Skimmer
with 1.25 inch
Orifice Diameter
8 ft. weir
ID 16.3

CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 16

Kimley » Horn

421 FAYETTEVILLE STREET, SUITE 600
RALEIGH, NC 27601

RIGHT-OF-WAY REV.
CONST. REV.

PROJECT REFERENCE NO.	SHEET NO.
R-5963A	EC-16/CONST.16
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

MATCHLINE -L- STA 175+50 (SEE SHEET EC-17)

CLEAN WATER DIVERSION

CWD CWD CWD CWD
(Not to Scale)

