	— TOTAL BILL OF MATERIAL —											
BRIDGE NO.	INCIDENTAL MILLING	ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B	ASPHALT BINDER FOR PLANT MIX	GROOVING BRIDGE FLOORS	EPOXY COATED REINFORCING STEEL	CONCRETE WORK FOR MEDIAN REPLACEMENT	CLASS II SURFACE PREPARATION	LATEX MODIFIED CONCRETE OVERLAY- VERY EARLY STRENGTH	PLACING AND FINISHING OF LATEX MODIFIED CONCRETE OVERLAY-VERY EARLY STRENGTH	SCARIFYING BRIDGE DECK	HYDRO- DEMOLITION OF BRIDGE DECK	
	SQ.YDS.	TONS	TONS	SQ.FT.	LBS.	SQ.FT.	SQ.YDS.	CU. YDS.	SQ.YDS.	SQ. YDS.	SQ.YDS.	
100053						527						
100076					4,796							
100278	134	11	1	16,834			80.8	114.3	2,055	2,055	2,055	
TOTAL	134	11	1	16,834	4,796	527	80.8	114.3	2,055	2,055	2,055	

					ТАТ				A 1]
	— TOTAL BILL OF MATERIAL —												
BRIDGE NO.	CONCRETE REPAIRS	SHOTCRETE REPAIRS	EPOXY RESIN INJECTION		STRIP SEALS FOR PRESERVATION	EXPANSION JOINT SEALS FOR PRESERVATION	MODULAR JOINT REPAIR	MOLDED RUBBER SEGMENTAL EXPANSION JOINT	ELASTOMERIC CONCRETE FOR PRESERVATION	BRIDGE JOINT DEMOLITION	CONCRETE DECK REPAIR FOR SILANE DECK TREATMENT	CONCRETE WORK FOR JOINT REPLACEMENT	POLLUTION CONTROL
	CU.FT.	CU.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	SQ.FT.	LUMP SUM	CU.FT.	SQ.FT.	SQ.FT.	SQ.FT.	LUMP SUM
100053				357.0					81.0	299.0			
100076					99.7	84.0	1,043	LUMP SUM			19.0	499	LUMP SUM
100278	1.6	103.5	66.0	266.0					73.5	252.0			LUMP SUM
TOTAL	1.6	103.5	66.0	623.0	99.7	84.0	1,043	LUMP SUM	154.5	551.0	19.0	499	LUMP SUM

	— TOTAL BILL OF MATERIAL —										
BRIDGE NO.	EPOXY COATING	BEAM REPAIR PLATING	SHOTBLASTING BRIDGE DECK	SILANE DECK TREATMENT	CLEANING AND REPAINTING OF BRIDGE NO	PAINTING CONTAINMENT FOR BRIDGE NO	CLEANING AND PAINTING OF EXISTING BEARINGS WITH HIGH RATIO CALCIUM SULFONATE	BRIDGE DRAINAGE CLEANOUT AND REPAIR	RAILROAD CONTRACTO PROTECTIV SERVICES		
	SQ.FT.	LBS.	SQ. YDS.	SQ.YDS.	LUMP SUM	LUMP SUM	EACH	LUMP SUM	DAY		
100053			5,175	5,175							
100076			9,862	9,862				LUMP SUM	60		
100278	605.5	1,172			LUMP SUM	LUMP SUM	80		60		
TOTAL	605.5	1,172	15,037	15,037	LUMP SUM	LUMP SUM	80	LUMP SUM	120		

DRAWN BY : B.E. LANNING	DATE: 07/2022
CHECKED BY : B.E. ATKINSON	DATE : 07/2022
DESIGN ENGINEER OF RECORD : B.E. ATKINSON	DATE : 12/2024

+

+



NOTE: ____

AT THE TIME OF THE PREPARATION OF THESE PLANS, IT WAS NOT ANTICIPATED THAT THE FOLLOWING ITEM(S) LISTED WOULD BE REQUIRED. HOWEVER, IT MAY BE DETERMINED IN THE FIELD THAT THE FOLLOWING ITEM(S) LISTED, OR OTHER WORK WILL BE NECESSARY TO PROPERLY COMPLETE THE INTENDED BRIDGE PRESERVATION/REHABILITATION WORK. THE CONTRACTOR SHALL BE PREPARED TO PERFORM SUCH WORK IN A TIMELY MANNER, AS DETERMINED IN THE FIELD. SUCH WORK SHALL BE CONSIDERED EXTRA WORK AND SHALL BE ADDRESSED AS PER ARTICLE 104-7 OF THE STANDARD SPECIFICATIONS. PROJECT SPECIAL PROVISIONS THAT OUTLINE REQUIREMENTS FOR THESE POTENTIAL ADDITIONAL WORK ITEMS HAVE BEEN PROVIDED IN THE PROJECT DOCUMENTS, BUT NO QUANTITIES HAVE BEEN LISTED. ACTUAL PAY ITEMS, QUANTITIES, AND COSTS WILL BE ESTABLISHED, AS REQUIRED, IF EXTRA WORK IS ENCOUNTERED. UNANTICIPATED ITEMS:

ITEM	DESCRIPTION	UNIT
1	CLASS III SURFACE PREPARATION	SY
2	CONCRETE FOR DECK REPAIR	
3	VOLUMETRIC MIXER	LS

	PROJECT	NO	15BPF	R.128.3
	BU	NCOM	BE	_ COUNTY
	BRIDGE	NO. <u>10</u>	<u>0053,</u> 1003	<u>100076</u> 278
	DEPART	MENT OF	NORTH CAROLINA TRANSP(ALEIGH	ORTATION
SEAL 24939 CINEF.P. CO S. ATKIMuruu 2/11/2025	(L BIL	

MI ENGINEERING			REVI	SION	S		SHEET NO.
1011 SCHAUB DRIVE, SUITE 100	N0.	BY:	DATE:	N0 .	BY:	DATE:	S-1
RALEIGH, NC 27606 (919) 851-6606	1			3			TOTAL SHEETS
FIRM PE NUMBER : P-0671	2			4			48