

REFERENCE: BR-0015

PROJECT: 67015

SEE SHEET 3 FOR PLAN SHEET LAYOUT
AT TIME OF INVESTIGATION

CONTENTS

LINE	STATION	PLAN	PROFILE
-L-	I2+00.00 - 49+50.00	4 - 6	N/A
-YI-	I0+00.00 - I9+35.00	5	N/A
-Y2-	I0+00.00 - I8+50.00	5	N/A
-RPB-	I0+00.00 - I9+28.28	4 - 5	N/A
-RPD-	I0+00.00 - I2+66.89	5	N/A
-RPD-RT-	I0+00.00 - I0+96.7I	5	N/A
-LPB-	I0+00.00 - I5+92.00	5	N/A
-DRWI-	I0+00.00 - II+45.00	5	N/A

APPENDICES

APPENDIX	TITLE	SHEETS
A	BORE LOGS	7 - 33
B	LABORATORY RESULTS	34 - 37

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

ROADWAY
SUBSURFACE INVESTIGATION

COUNTY DAVIDSON
PROJECT DESCRIPTION BRIDGE NO. 67 AND NO. 68
REPLACEMENTS ON US 29/US 70 NB & SB OVER
SR 1192 (W. 5TH AVENUE)

INVENTORY

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BR-0015	1	

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO PERFORM INDEPENDENT SUBSURFACE INVESTIGATIONS AND MAKE INTERPRETATIONS AS NECESSARY TO CONFIRM CONDITIONS ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

M. FOSTER

J. KARDON

D. KUBINSKI

TRIGON EXPLORATION

INVESTIGATED BY KLEINFELDER, INC

DRAWN BY D. KUBINSKI

CHECKED BY J. FREGOSI

SUBMITTED BY KLEINFELDER, INC

DATE AUGUST 2023

Prepared in the Office of:



422 Gallimore Dairy Road, Suite B
Greensboro, North Carolina 27409
NC Engineering Firm License No. F-1312



DocuSigned by:

Joshua D. Fregosi

08/08/2023

DA6130C3FB4C4E1...

SIGNATURE

DATE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED


SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

[illegible]

09/08/99

PROJECT: BR-0015

CONTRACT: TBD



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

DAVIDSON COUNTY


LOCATION: *BRIDGE 280067 AND 280068 REPLACEMENTS ON US 29/US 70.
NB & SB OVER SR 1192 (W. 5TH AVE.)*

TYPE OF WORK: *GRADING, DRAINAGE, PAVING, WIDENING AND STRUCTURES*

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BR-0015	3	
STATE PROJ. NO.	F. A. PROJ. NO.	DESCRIPTION	
67015.1.1		PE	
67015.2.1		R/W, UTIL	
67015.3.1		CONST.	

STAGE 2 PLANS
(2RD1)

Plans Developed with
OpenRoads



- ★ PROPOSED SIGNAL
- ☆ EXIST. SIGNAL

THIS IS A CONTROL OF ACCESS PROJECT WITH ACCESS BEING LIMITED TO INTERCHANGES.
A PORTION OF THIS PROJECT IS LOCATED WITHIN THE LIMITS OF THE CITY OF LEXINGTON.
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.
**A DESIGN EXCEPTION IS REQUIRED FOR -RPD- AND -RPD_RT- MAXIMUM GRADE.

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION
DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

GRAPHIC SCALES

50 25 0 50 100

PLANS

50 25 0 50 100

PROFILE (HORIZONTAL)

10 5 0 10 20

PROFILE (VERTICAL)

DESIGN DATA

ADT 2022 = 14500

ADT 2045 = 18700

K = 8 %

D = 55 %

T = 9 % *

V = 60 MPH

* TTST =5% DUAL 4%

FUNC CLASS =

PRINCIPAL ARTERIAL

STATEWIDE TIER

PROJECT LENGTH

PROJECT LENGTHS FOR PROJECT BR-0015:

LENGTH ROADWAY PROJECT BR-0015 = 0.689 MILES

LENGTH STRUCTURES PROJECT BR-0015 = 0.021 MILES

TOTAL LENGTH PROJECT BR-0015 = 0.710 MILES

NCDOT Contact: DAVID STUTTS, PE

Prepared in the Office of: **KCA**
KISINGER CAMPO & ASSOCIATES

NC FIRM LICENSE No: C-1506
301 Fayetteville St., Suite 1500
Raleigh, NC 27601
(919) 882-7839

2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE: 11/24/2023

LETTING DATE: 12/17/2024

JACOB H. DUKE, P.E.
PROJECT ENGINEER

ANDREA B. GORDON, E.I.
PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.

ROADWAY DESIGN ENGINEER

SIGNATURE: _____ P.E.



August 4, 2023
Kleinfelder File No. GSO23L155050

STATE PROJECT: 67015.1.1 (BR-0015)
COUNTY: Davidson
DESCRIPTION: Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)

SUBJECT: **GEOTECHNICAL REPORT - INVENTORY**

PROJECT DESCRIPTION

This project consists of the widening of US 29/US 70 (-L-) and replacement of Bridge No. 67 and No. 68 over SR 1192 (-Y1-). At the project location, US 29/US 70 is a four-lane highway consisting of two lanes in the northbound and southbound direction with a grass median dividing the highway. Additionally, the project consists of the widening of SR 1192 (-Y1-), Forest Rose Drive (-DRW1-), and US 29/US 70 northbound exit ramps (-RPD-, -RPD_RT-) to National Boulevard as well as a realignment of Murphy Drive (-Y2-), onramp to US 29/US 70 southbound (-RPB-), and US 29/US 70 southbound exit ramp (-LPB-) to SR 1192.

Bridge No. 67 and No. 68 will be approximately 110 feet long (W.P. # 1 to W.P. #2) and 109.3 feet wide (out to out). The bridge will consist of a concrete deck with precast concrete girders. Abutment MSE retaining walls are proposed at end bent no. 1 and end bent no. 2. At end bent no. 1, a retaining wall will extend along US 29/US 70 northbound from station 24+60.37 -L- (54' RT) to 29+16.75 -L- (60' RT) and turn to run parallel along SR 1192 from station 29+16.75 -L- (60' RT) to 15+30.00 -Y1- (46' RT). At end bent no. 2, a retaining wall will extend parallel to SR 1192 from station 15+53.00 -Y1- (34' LT) to 17+73.00 -Y1- (34' LT). Maximum cut and fill heights to achieve finished grade are anticipated to be approximately 31 feet and 24 feet, respectively.

The geotechnical investigation was conducted in April and May 2023. Standard Penetration Test borings were advanced with a CME-55 drill rig with an automatic hammer. Hand augers were also performed in areas where the use of a drill rig was restricted, or overhead and underground utility conflicts were observed. Representative soil samples were collected for visual classification in the field and selected samples were submitted for laboratory analysis by Kleinfelder, Inc.

The following alignments, totaling 1.43 miles, were investigated. Plan sheets of these alignments are included in this report.

<u>LINE</u>	<u>STATIONS</u>
-L-	12+00.00 – 49+50.00
-Y1-	10+00.00 – 19+35.00
-Y2-	10+00.00 – 18+50.00
-RPB-	10+00.00 – 19+28.28
-RPD-	10+00.00 – 12+66.89
-RPD-RT-	10+00.00 – 10+96.71
-LPB-	10+00.00 – 15+92.00
-DRW1-	10+00.00 – 11+45.00

PHYSIOGRAPHY AND GEOLOGY

According to the 1985 Geologic Map of North Carolina, the project is located in the Charlotte Belt of the Piedmont Physiographic Province. The Charlotte Belt typically consists of metamorphosed igneous rocks and the bedrock unit encompassing the site is Metamorphosed Mafic Rock (PzZm). The Piedmont is characterized by gently rolling topography, well rounded hills, and long low ridges with a few hundred feet of elevation difference between the hills and valleys. It contains deeply weathered bedrock and relatively few rock outcrops. Erratic weathering of the rock can often result in varying depths of the residual soil profile. Additionally, it is not uncommon to encounter lenses or boulders of bedrock and zones of weathered rock within the residual soil, well above the general bedrock level.

The project corridor is comprised primarily of residential and rural properties. The general topography along the project is flat to gently sloping.

Surface water is drained from the corridor by the existing roadway ditches and culverts. Michael Branch runs along the east side of the project parallel to US 29/US 70.

SOIL PROPERTIES

Soils encountered during this investigation are separated into three categories based on origin. They consist of roadway embankment, alluvial soil, and residual soil.

Roadway embankment is defined as any material placed to raise grade for roadway construction and is present along the existing roadways on the project and inside exit/entry ramps. The roadway embankment encountered generally consist of moist to wet, soft to very stiff, fine sandy silts (A-4), clayey silts (A-5), and silty clays (A-7) with trace mica, gravel, and concrete fragments. The plasticity index of the roadway embankment clayey silt (A-5) tested is 9. The plasticity index of the roadway embankment silty clays (A-7) tested ranged from 22 to 38.

Alluvial soils are formed by deposition and are present underlying roadway embankment at the existing bridge abutments on US 29/US 70 (-L-), SR 1192 (-Y1-), and Central Avenue (-Y3-). The alluvial soils encountered generally consist of moist to saturated, very soft to stiff, silty clays (A-7) with trace mica and organic matter, and moist, loose, clayey fine to coarse sands (A-2-6).

The onsite residual soils are the product of the in-place chemical and mechanical weathering of the parent bedrock, and oftentimes maintain the same layering and lineation of the parent bedrock. Residual soils are derived from the weathering of underlying mafic metamorphic rock. The majority of the residual soil encountered consist of moist to saturated, soft to hard, fine and coarse to fine sandy silts (A-4), clayey silts (A-5), silty clays (A-7) with trace mica, rock fragments, and quartz fragments and wet, very dense, silty coarse to fine sands (A-2-4). The plasticity index of the residual silty clays (A-7) tested ranged from 12 to 44.

ROCK PROPERTIES

Weathered rock was encountered on and along US 29/US 70 (-L-) at the existing bridge abutments and Central Avenue (-Y3-) at elevations ranging from 666.4 to 691.5 feet Mean Sea Level (MSL). The weathered rock consists of Metagabbro. Crystalline rock was not encountered during the field investigation.

GROUNDWATER

Groundwater was encountered at elevations ranging from 694.9 to 722.1 feet. Typically, the groundwater depth ranges from 11.2 to 21.1 feet below the existing ground surface, where encountered.

AREAS OF SPECIAL GEOTECHNICAL INTEREST

1) Highly Plastic Clays: Highly plastic clays (PI > 25) were encountered on the project at the following locations:

LINE	STATIONS	OFFSETS
-L-	12+25 to 25+75	LT to RT
-L-	30+75 to 32+75	LT to RT
-L-	33+25 to 33+75	LT to RT
-L-	35+75 to 39+75	LT to RT
-L-	41+75 to 45+75	LT to RT
-Y1-	10+25 to 12+25	LT to RT
-Y1-	13+25 to 14+75	LT to RT
-Y2-	12+25 to 16+06	LT to RT
-RPB-	10+00 to 16+75	LT to RT
-RPB-	18+75 to 19+14	LT to RT
-LPB-	12+34 to 13+54	LT
-DRW1-	10+00 to 11+45	LT to RT

2) Groundwater: The following areas exhibit a high-water table, seasonal high groundwater, or the potential for groundwater related construction problems:

LINE	STATIONS	OFFSETS
-Y1-	15+75 to 17+50	LT to RT

3) Alluvial Soil: Alluvial soil was encountered on the project at the following locations:

LINE	STATIONS	OFFSETS
-L-	27+25 to 28+25	RT
-L-	28+25 to 29+25	LT to RT
-Y1-	14+50 to 17+50	RT

4) Wet Samples: Soils classified as wet based on visual inspection and laboratory test results were encountered at the following locations:

LINE	STATIONS	OFFSETS
-L-	20+50 to 22+25	LT
-L-	26+00 to 27+25	RT
-L-	42+00 to 45+75	LT to RT
-LPB-	12+84 to 15+25	RT

Prepared by,
KLEINFELDER, INC.
NC License No. F-1312



Daniel H. Kubinski, PE
Senior Professional


DHK/JDF:jrs


Bulk Samples

Sample No.	Alignment	Station No.	Offset	Depth (ft)	Tests Performed
CBR-1	-L-	14+50	88' LT	8.5 – 18.5	CBR
CBR-2	-L-	18+50	89' LT	0.0 – 10.0	CBR
CBR-3	-L-	42+00	0' CL	0.0 – 2.5	No Test



Joshua D. Fregosi, PE
Program Manager





PROJECT: 67015
REFERENCE: BR-0015

PROJECT REFERENCE NO.	SHEET NO.
BR-0015	7

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
APPENDIX A
BORE LOGS

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)					
BORING NO. L_1250			STATION 12+50			OFFSET 95 ft LT			ALIGNMENT -L-		0 HR. Dry				
COLLAR ELEV. 751.8 ft			TOTAL DEPTH 24.9 ft			NORTHING 756,770			EASTING 1,620,878		24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/27/23			COMP. DATE 04/27/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
755															
750	751.4	0.4	3	5	5						SS-1	30%		751.8	0.0
	748.4	3.4	3	4	5									749.1	2.7
745												M		RESIDUAL Stiff, Highly Plastic, Reddish Brown, Silty CLAY, Trace Rock Fragments	
	743.4	8.4	2	3	5									Medium Stiff to Stiff, Reddish Brown to Yellowish Brown, Fine Sandy SILT, Trace Mica	
740												M			
	738.4	13.4	2	4	5										
735												M			
	733.4	18.4	2	4	5										
730												M			
	728.4	23.4	2	4	5										
														Boring Terminated at Elevation 726.9 ft in RESIDUAL (Sandy SILT)	

WBS 67015.1.1				TIP BR-0015				COUNTY DAVIDSON				GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)												GROUND WTR (ft)					
BORING NO. L_1450				STATION 14+50				OFFSET 88 ft LT				ALIGNMENT -L-				0 HR. Dry	
COLLAR ELEV. 756.1 ft				TOTAL DEPTH 25.0 ft				NORTHING 756,929				EASTING 1,621,002				24 HR. FIAD	
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER R. Toothman				START DATE 05/08/23				COMP. DATE 05/08/23				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
760																	
755	755.2	0.9												756.1 GROUND SURFACE 0.0			
														755.2 ROADWAY EMBANKMENT 0.9			
750	752.6	3.5	7	9	12							M		Asphalt and ABC Stone (0.0 - 0.9 Foot)			
														RESIDUAL			
745	752.6		6	8	9						SS-2	24%		Very Stiff, Highly Plastic, Reddish Brown, Silty CLAY			
														749.4 6.7			
740	747.6	8.5	2	4	4									Medium Stiff, Moderately Plastic, Yellowish Brown, Silty CLAY			
735	742.6	13.5	2	3	4							27% M					
	737.6	18.5	2	3	4							M					
	732.6	23.5	2	3	4							M		734.1 22.0			
														731.1 25.0			
														Medium Stiff, Yellowish Brown, Coarse to Fine Sandy SILT, Trace Mica			
														Boring Terminated at Elevation 731.1 ft in RESIDUAL (Sandy SILT)			
														Other Samples: CBR-1 (8.5 - 18.5)			

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

NCDOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC DOT GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)				
BORING NO. L_2250			STATION 22+50			OFFSET 106 ft LT			ALIGNMENT -L-		0 HR. Dry			
COLLAR ELEV. 757.2 ft			TOTAL DEPTH 35.0 ft			NORTHING 757,575			EASTING 1,621,477		24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/08/23			COMP. DATE 05/08/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
760														
	757.2	0.0	3	8	9									757.2 GROUND SURFACE 0.0
755	753.7	3.5	3	3	4						SS-6	16%	M	Very Stiff to Medium Stiff, Highly Plastic, Dark Reddish Brown to Reddish Yellow to Reddish Brown, Silty CLAY, Trace Mica and Rock Fragments
750	748.7	8.5	5	8	10						SS-7	32%		
745	743.7	13.5	2	2	3								M	740.2 Medium Stiff, Slightly Plastic, Reddish Brown, Silty CLAY 17.0
740	738.7	18.5	2	3	3						SS-8	43%	M	735.4 Medium Stiff to Stiff, Yellowish Brown to Olive Brown and Pink, Coarse to Fine Sandy SILT, Trace Mica and Rock Fragments 21.8
735	733.7	23.5	2	2	3									
730	728.7	28.5	2	3	5								M	
725	723.7	33.5	11	7	6								M	722.2 Boring Terminated at Elevation 722.2 ft in RESIDUAL (Sandy SILT) 35.0

NC DOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster				
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)				
BORING NO. L_2492			STATION 24+92			OFFSET 26 ft RT			ALIGNMENT -L-				
COLLAR ELEV. 737.7 ft			TOTAL DEPTH 20.0 ft			NORTHING 757,686			EASTING 1,621,729				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic				
DRILLER R. Toothman			START DATE 05/05/23			COMP. DATE 05/05/23			SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100	MOI		
740													
735	736.5	1.2	4	6	2								737.7 GROUND SURFACE 0.0
	734.2	3.5	1	2	2								736.8 ROADWAY EMBANKMENT 0.9
730													734.6 Asphalt and ABC Stone (0.0 - 0.9 Foot) 3.1
													Medium Stiff, Reddish Brown, Coarse to Fine Sandy SILT, Trace Mica
725	729.2	8.5	2	2	3								Medium Stiff, Highly Plastic, Reddish Brown, Silty CLAY, Trace Mica
	724.2	13.5	2	3	5								726.6 RESIDUAL 11.1
720													Medium Stiff to Stiff, Yellowish Brown to Light Brownish Gray, Coarse to Fine Sandy SILT, Trace Mica
	719.2	18.5	3	4	6								717.7 Boring Terminated at Elevation 717.7 ft in RESIDUAL (Sandy SILT) 20.0

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. L_2599			STATION 25+99			OFFSET 35 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 735.6 ft			TOTAL DEPTH 25.0 ft			NORTHING 757,765			EASTING 1,621,802			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/05/23			COMP. DATE 05/05/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
740														
735	734.6	1.0	3	2	3	5								735.6 GROUND SURFACE 0.0 734.9 ROADWAY EMBANKMENT 0.7
730	732.0	3.6	2	2	3	5						M		733.3 Asphalt and ABC Stone (0.0 - 0.7 Foot) 2.3 Medium Stiff, Highly Plastic, Reddish Brown, Silty CLAY, Trace Mica
	727.1	8.5	3	3	5	8						M		Medium Stiff, Reddish Brown, Fine Sandy SILT, Trace Mica
725	722.1	13.5	1	3	4	7					SS-10 39%			728.1 RESIDUAL 7.5 Medium Stiff, Highly Plastic, Reddish Brown to Reddish Yellow, Silty CLAY
720	717.1	18.5	2	4	4	8						W		718.6 17.0 Medium Stiff, Reddish Yellow and Light Brownish Gray to Yellowish Brown and Light Brownish Gray, Coarse to Fine Sandy SILT, Trace Mica and Rock Fragments
715	712.1	23.5	2	2	4	6						M		710.6 25.0 Boring Terminated at Elevation 710.6 ft in RESIDUAL (Sandy SILT)

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST J. Kardon						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)						
BORING NO. L_2650			STATION 26+50			OFFSET 90 ft RT			ALIGNMENT -L-			0 HR. Dry			
COLLAR ELEV. 715.9 ft			TOTAL DEPTH 20.0 ft			NORTHING 757,771			EASTING 1,621,877			24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman			START DATE 05/09/23			COMP. DATE 05/09/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
720															
715	714.9	1.0	3	3	4									715.9	0.0
710	712.4	3.5	2	3	3						SS-11	32%		714.9	1.0
	707.4	8.5	3	6	6							M			708.9
705	702.4	13.5	3	6	9							M			RESIDUAL Stiff to Very Stiff, Yellowish Brown, Coarse to Fine Sandy SILT
700	697.4	18.5	7	11	13							M			Boring Terminated at Elevation 695.9 ft in RESIDUAL (Sandy SILT)
															695.9

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. L_2700			STATION 27+00			OFFSET 31 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 734.2 ft			TOTAL DEPTH 30.0 ft			NORTHING 757,847			EASTING 1,621,861			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/05/23			COMP. DATE 05/05/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
730	730.5	3.7	1	3	3						SS-12	33%		734.2 GROUND SURFACE 0.0
725	725.7	8.5	2	3	4									732.3 ROADWAY EMBANKMENT 1.9
720	720.7	13.5	2	3	5									Asphalt and ABC Stone (0.0 - 1.9 Feet)
715	715.7	18.5	3	5	5									Medium Stiff to Stiff, Moderately Plastic, Reddish Brown to Dark Reddish Brown, Reddish Brown and Olive Gray, Silty CLAY, Trace Mica
710	710.7	23.5	4	6	8									
705	705.7	28.5	7	8	12									712.4 RESIDUAL 21.8
														Stiff to Very Stiff, Yellowish Brown to Gray, Fine Sandy SILT
														704.2 Boring Terminated at Elevation 704.2 ft in RESIDUAL (Sandy SILT) 30.0

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. L_2800			STATION 28+00			OFFSET 29 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 733.4 ft			TOTAL DEPTH 35.0 ft			NORTHING 757,927			EASTING 1,621,920			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/05/23			COMP. DATE 05/05/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
730	729.9	3.5	2	2	3	5						M		733.4 GROUND SURFACE 0.0 731.6 ROADWAY EMBANKMENT 1.8 Asphalt and ABC Stone (0.0 - 1.8 Feet) Medium Stiff, Reddish Brown, Fine Sandy SILT, Little Mica
725	724.9	8.5	2	2	3	5						M		726.6 6.8 Medium Stiff, Moderately Plastic, Reddish Brown and Olive Gray to Reddish Brown to Olive Brown, Silty CLAY, Trace Mica
720	719.9	13.5	2	3	4	7						SS-14 30%		
715	714.9	18.5	2	4	4	8						M		
710	709.9	23.5	2	2	3	5						M		
705	704.9	28.5	1	3	6	9						M		706.4 27.0 ALLUVIAL Stiff, Highly Plastic, Dark Brown and Gray, Silty CLAY
700	699.9	33.5	2	4	5	9						M		701.6 31.8 RESIDUAL Stiff, Light Brownish Gray, Silty CLAY
						9						M		698.4 35.0 Boring Terminated at Elevation 698.4 ft in RESIDUAL (Silty CLAY)

NC DOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC_DOT.GDT 6/15/23

[illegible]

NC DOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1				TIP BR-0015				COUNTY DAVIDSON				GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)												GROUND WTR (ft)					
BORING NO. EB1-C				STATION 28+69				OFFSET 16 ft LT				ALIGNMENT -L-				0 HR. N/A	
COLLAR ELEV. 733.1 ft				TOTAL DEPTH 73.5 ft				NORTHING 758,009				EASTING 1,621,927				24 HR. 21.1	
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022								DRILL METHOD Mud Rotary				HAMMER TYPE Automatic					
DRILLER R. Toothman				START DATE 04/20/23				COMP. DATE 04/20/23				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
735																	
	731.0	2.1															
730			4	2	2												
	728.6	4.5															
			1	2	3												
725																	
	724.7	8.4															
			1	2	2												
720																	
	719.7	13.4															
			1	3	3												
715																	
	714.7	18.4															
			1	2	2												
710																	
	709.8	23.3															
			2	2	2												
705																	
	704.8	28.3															
			3	3	3												
700																	
	699.8	33.3															
			2	3	4												
695																	
	694.8	38.3															
			12	16	17												
690																	
	689.8	43.3															
			21	16	12												
685																	
	684.8	48.3															
			37	63/0.4													
680																	
	679.8	53.3															
			7	13	18												
675																	
	674.8	58.3															
			8	14	14												
670																	
	669.8	63.3															
			100/0.4														
665																	
	664.8	68.3															
			66	34/0.1													
660																	
	659.8	73.3															
			100/0.2														
		</															

NC DOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. EB2-B			STATION 30+22			OFFSET 33 ft RT			ALIGNMENT -L-			0 HR. N/A		
COLLAR ELEV. 733.2 ft			TOTAL DEPTH 54.8 ft			NORTHING 758,100			EASTING 1,622,059			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD Mud Rotary			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/25/23			COMP. DATE 04/25/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		MOI		
735														
730	729.9	3.3	2	3	4	7						M		733.2 GROUND SURFACE 0.0 732.2 ROADWAY EMBANKMENT 1.0 Asphalt & ABC Stone (0.0 - 1.0 Feet) Medium Stiff, Reddish Brown, Silty CLAY
725	724.8	8.4	2	3	3	6						M		
720	719.9	13.3	3	5	7	12						M		721.6 RESIDUAL 11.6 Stiff, Reddish Yellow, Silty CLAY
715	714.9	18.3	5	7	11	18						M		716.6 Very Stiff to Hard, Yellowish Brown, Olive Brown, Olive, Coarse to Fine Sandy SILT, Trace to Little Mica, Trace Rock Fragments and Quartz 16.6
710	709.9	23.3	10	12	15	27						M		
705	704.9	28.3	9	14	18	32						M		
700	699.9	33.3	10	16	20	36						M		
695	694.9	38.3	8	13	17	30						M		
690	689.9	43.3	18	24	26	50						M		
685	684.9	48.3	20	27	47	74						M		
680	679.9	53.3	35	35	49	84						M		678.4 Boring Terminated at Elevation 678.4 ft in RESIDUAL (Sandy SILT) 54.8

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)					
BORING NO. EB2-D			STATION 30+28			OFFSET 19 ft RT			ALIGNMENT -L-			0 HR. N/A			
COLLAR ELEV. 733.3 ft			TOTAL DEPTH 64.2 ft			NORTHING 758,114			EASTING 1,622,052			24 HR. 11.2			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD Mud Rotary				HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/26/23			COMP. DATE 04/26/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
735															
														733.3	0.0
														732.3	1.0
730	730.0	3.3	2	3	3	6						M		ROADWAY EMBANKMENT	
														Asphalt & ABC Stone (0.0 - 1.0 Foot)	
														Medium Stiff, Reddish Brown, Silty CLAY, Trace Mica	
725	724.8	8.5	3	3	3	6						M			
														721.4	11.9
720	720.0	13.3	3	4	4	8						M		RESIDUAL	
														Medium Stiff to Stiff, Reddish Brown and Yellowish Brown, Silty CLAY, Trace Mica	
715	715.0	18.3	3	5	6	11						W			
														711.7	21.6
710	710.0	23.3	3	3	4	7						W		Medium Stiff to Hard, Reddish Yellow, Light Brownish Gray, Brown, and Pale Red, Coarse to Fine Sandy SILT, Trace Mica	
705	705.0	28.3	2	2	3	5						Sat.			
700	700.0	33.3	6	7	17	24						Sat.			
695	695.0	38.3	10	8	7	15						Sat.			
690	690.0	43.3	6	11	15	26						Sat.			
685	685.0	48.3	10	19	28	47									
680	680.0	53.3	18	27	38	65						Sat.			
675	675.0	58.3	30	60	40/0.2									674.0	59.3
														WEATHERED ROCK	
670	670.0	63.3	16	84/0.4										Olive Gray and Light Brownish Gray, METAGABBRO	
														669.1	64.2
														Boring Terminated at Elevation 669.1 ft in Weathered Rock (METAGABBRO)	

NCDOT BORE DOUBLE BR0015_GEO ROWY_GINT.GPJ NC DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. L_3200			STATION 32+00			OFFSET 60 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 731.9 ft			TOTAL DEPTH 9.9 ft			NORTHING 758,224			EASTING 1,622,190			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/24/23			COMP. DATE 04/24/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
	731.9	0.0												731.9 GROUND SURFACE 0.0
730			2	11	11							M		RESIDUAL Very Stiff to Stiff, Yellowish Brown and Olive Gray to Reddish Brown and Reddish Yellow, Coarse to Fine Sandy SILT, Trace Mica and Rock Fragments
	728.5	3.4										M		
			3	4	6							M		
725												M		
	723.5	8.4	2	4	5									722.0 9.9
Boring Terminated at Elevation 722.0 ft in RESIDUAL (Sandy SILT)														

NC DOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. L_3600			STATION 36+00			OFFSET 85 ft LT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 748.1 ft			TOTAL DEPTH 20.0 ft			NORTHING 758,629			EASTING 1,622,320			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/04/23			COMP. DATE 05/04/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
750														
	748.1	0.0	3	4	5									748.1 GROUND SURFACE 0.0
745	744.6	3.5	4	5	8						SS-16	32%		RESIDUAL Stiff, Highly Plastic, Dark Reddish Brown to Red to Reddish Yellow, Silty CLAY
740	739.6	8.5	5	7	8									
735	734.6	13.5	3	4	6									736.4 Stiff to Medium Stiff, Reddish Yellow, Fine Sandy SILT 11.7
730	729.6	18.5	3	4	4									
														728.1 Boring Terminated at Elevation 728.1 ft in RESIDUAL (Sandy SILT) 20.0

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST M. Foster				
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)								GROUND WTR (ft)				
BORING NO. L_3800		STATION 38+00		OFFSET CL		ALIGNMENT -L-		0 HR. Dry				
COLLAR ELEV. 741.1 ft		TOTAL DEPTH 7.0 ft		NORTHING 758,735		EASTING 1,622,510		24 HR. Dry				
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD Hand Auger			HAMMER TYPE N/A					
DRILLER M. Foster		START DATE 04/26/23		COMP. DATE 04/26/23		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		
745												
740												741.1 GROUND SURFACE 0.0
735												RESIDUAL Medium Stiff to Stiff, Highly Plastic, Reddish Brown to Yellowish Brown, Silty CLAY
												734.1 Boring Terminated at Elevation 734.1 ft in RESIDUAL (Silty CLAY) 7.0

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST M. Foster				
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)								GROUND WTR (ft)				
BORING NO. L_4000		STATION 40+00		OFFSET CL		ALIGNMENT -L-		0 HR. Dry				
COLLAR ELEV. 744.6 ft		TOTAL DEPTH 6.8 ft		NORTHING 758,893		EASTING 1,622,633		24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD Hand Auger			HAMMER TYPE N/A					
DRILLER M. Foster		START DATE 04/27/23		COMP. DATE 04/27/23		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		
745												744.6 GROUND SURFACE 0.0
740												RESIDUAL Soft to Medium Stiff, Moderately Plastic, Olive Gray to Reddish Brown, Silty CLAY, Trace Mica
												742.4 2.2
												737.8 6.8
												Boring Terminated at Elevation 737.8 ft in RESIDUAL (Sandy SILT)
												NOTE: Kessler dual mass dynamic cone penetrometer test performed on 5/4/2023 adjacent to hand auger boring.

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1					TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST M. Foster							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)						
BORING NO. L_4200					STATION 42+00		OFFSET CL		ALIGNMENT -L-		0 HR. Dry					
COLLAR ELEV. 747.0 ft					TOTAL DEPTH 7.0 ft		NORTHING 759,051		EASTING 1,622,755		24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE N/A							DRILL METHOD Hand Auger			HAMMER TYPE N/A						
DRILLER M. Foster					START DATE 05/01/23		COMP. DATE 05/01/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	▼ MOI	L O G	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft) DEPTH (ft)		
750																
745											37%		747.0	GROUND SURFACE 0.0		
													743.3	RESIDUAL Medium Stiff to Soft, Highly Plastic, Brown and Reddish Brown, Silty CLAY, Trace Mica 3.7		
740											M		740.0	Soft, Reddish Yellow, Fine Sandy SILT, Trace Mica 7.0		
														Boring Terminated at Elevation 740.0 ft in RESIDUAL (Sandy SILT)		
														Other Samples: CBR-3 (0.0 - 2.5)		

WBS 67015.1.1					TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST D. Kubinski							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)						
BORING NO. L_4400					STATION 44+00		OFFSET CL		ALIGNMENT -L-		0 HR. Dry					
COLLAR ELEV. 747.3 ft					TOTAL DEPTH 6.5 ft		NORTHING 759,209		EASTING 1,622,878		24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE N/A							DRILL METHOD Hand Auger			HAMMER TYPE N/A						
DRILLER D. Kubinski					START DATE 05/02/23		COMP. DATE 05/02/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	▼ MOI	L O G	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft) DEPTH (ft)		
750																
745													747.3	GROUND SURFACE 0.0		
											S-19	30% M	745.8	RESIDUAL Soft, Highly Plastic, Reddish Brown, Silty CLAY, Trace Mica 1.5		
													740.8	Medium Stiff, Olive, Coarse to Fine Sandy SILT, Trace Mica 6.5		
														Boring Terminated at Elevation 740.8 ft in RESIDUAL (Sandy SILT)		

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

WBS 67015.1.1				TIP BR-0015				COUNTY DAVIDSON				GEOLOGIST D. Kubinski					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)												GROUND WTR (ft)					
BORING NO. L_4800				STATION 48+00				OFFSET CL				ALIGNMENT -L-				0 HR. Dry	
COLLAR ELEV. 744.6 ft				TOTAL DEPTH 6.7 ft				NORTHING 759,525				EASTING 1,623,123				24 HR. FIAD	
DRILL RIG/HAMMER EFF./DATE N/A								DRILL METHOD Hand Auger				HAMMER TYPE N/A					
DRILLER D. Kubinski				START DATE 05/03/23				COMP. DATE 05/03/23				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.		LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
745														744.6 GROUND SURFACE 0.0			
												M		743.6 RESIDUAL 1.0			
740														Soft, Yellowish Brown and Reddish Brown, Silty CLAY			
														Soft to Medium Stiff, Brown, Coarse to Fine Sandy SILT, Trace Mica			
														737.9 Boring Terminated at Elevation 737.9 ft in RESIDUAL (Sandy SILT) 6.7			
NOTE: Kessler dual mass dynamic cone penetrometer test performed on 5/4/2023 adjacent to hand auger boring.																	

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)											GROUND WTR (ft)					
BORING NO. Y1_1042			STATION 10+42			OFFSET 62 ft RT			ALIGNMENT -Y1-			0 HR. Dry				
COLLAR ELEV. 753.3 ft			TOTAL DEPTH 24.8 ft			NORTHING 758,208			EASTING 1,621,398			24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic						
DRILLER R. Toothman			START DATE 05/10/23			COMP. DATE 05/10/23			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
755																
	753.3	0.0												753.3	0.0	
750	750.0	3.3	3	5	7	12					SS-21	28%		RESIDUAL		
														Stiff, Highly Plastic, Reddish Brown and Reddish Yellow, Silty CLAY, Trace Mica		
745	745.0	8.3	4	6	6	12						M			745.8	7.5
														M	Stiff, Yellowish Brown, Coarse to Fine Sandy SILT, Trace Mica	
740	740.0	13.3	5	7	6	13						M				
			4	6	7								M			
735	735.0	18.3	3	4	5	9						M				
730	730.0	23.3	3	4	5	9						M		728.5	24.8	
														Boring Terminated at Elevation 728.5 ft in RESIDUAL (Sandy SILT)		

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)						
BORING NO. Y1_1250			STATION 12+50			OFFSET 43 ft LT			ALIGNMENT -Y1-			0 HR. Dry			
COLLAR ELEV. 732.2 ft			TOTAL DEPTH 10.0 ft			NORTHING 758,236			EASTING 1,621,629			24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman			START DATE 05/08/23			COMP. DATE 05/08/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
735															
730	731.2	1.0	4	5	6	11	.	.	.	.		SS-22	31%		732.2 GROUND SURFACE 0.0
	728.7	3.5	3	4	5	9	.	.	.	.					731.8 ROADWAY EMBANKMENT 0.4 Asphalt (0.0 - 0.4 Foot)
725							.	.	.	.		M	M		725.4 RESIDUAL 6.8 Stiff, Moderately Plastic, Reddish Brown to Reddish Yellow, Silty CLAY
	723.7	8.5	2	3	3	6	.	.	.	.				722.2 Medium Stiff, Yellowish Brown, Fine Sandy SILT, Trace Mica 10.0	
														Boring Terminated at Elevation 722.2 ft in RESIDUAL (Sandy SILT)	

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST M. Foster							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)					
BORING NO. Y1_1455				STATION 14+55		OFFSET 40 ft RT		ALIGNMENT -Y1-		0 HR.	Dry				
COLLAR ELEV. 718.8 ft				TOTAL DEPTH 10.0 ft		NORTHING 758,088		EASTING 1,621,794		24 HR.	FIAD				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman				START DATE 05/08/23		COMP. DATE 05/08/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
720															
	718.8	0.0	1	2	3	5						M		718.8	0.0
715	715.3	3.5	2	3	3	6						M			
710	710.3	8.5	1	3	3	6						M		711.3	7.5
														708.8	10.0
														Medium Stiff, Gray, Silty CLAY, Trace Mica	
														Boring Terminated at Elevation 708.8 ft in ALLUVIAL (Silty CLAY)	

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)				
BORING NO. Y1_1512			STATION 15+12			OFFSET 46 ft RT			ALIGNMENT -Y1-			0 HR. Dry		
COLLAR ELEV. 715.1 ft			TOTAL DEPTH 19.9 ft			NORTHING 758,063			EASTING 1,621,845			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic				
DRILLER R. Toothman			START DATE 05/10/23			COMP. DATE 05/10/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
720														
715	715.1	0.0												
710	711.7	3.4	2	3	2	5								
			2	2	2	4					SS-23	39%		
705	706.7	8.4	WOH	1	3	4						M		
700	701.7	13.4	WOH	2	2	4							M	
	696.7	18.4				15							W	
			5	7	8							Sat.		

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/15/23

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)											GROUND WTR (ft)				
BORING NO. Y1_1550			STATION 15+50			OFFSET 45 ft LT			ALIGNMENT -Y1-			0 HR.	Dry		
COLLAR ELEV. 717.8 ft			TOTAL DEPTH 13.5 ft			NORTHING 758,135			EASTING 1,621,912			24 HR.	Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/18/23			COMP. DATE 04/18/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
720															
715	716.8	1.0	4	4	3							M		717.8 GROUND SURFACE 0.0	
	714.3	3.5	3	4	5						SS-24	29%		ROADWAY EMBANKMENT Stiff to Medium Stiff, Moderately Plastic, Reddish Brown, Silty CLAY	
710	709.3	8.5	2	2	2							M			
705														704.3 13.5	
Boring Terminated at Elevation 704.3 ft in ROADWAY EMBANKMENT (Silty CLAY)															
NOTE: No Sample taken at 13.5 ft due to potential obstruction on 54" RCP.															

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST D. Kubinski			
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)			
BORING NO. Y1_1783			STATION 17+83			OFFSET 34 ft LT			ALIGNMENT -Y1-			0 HR. Dry
COLLAR ELEV. 715.2 ft			TOTAL DEPTH 10.3 ft			NORTHING 758,045			EASTING 1,622,127			24 HR. FIAD
DRILL RIG/HAMMER EFF./DATE N/A						DRILL METHOD Hand Auger			HAMMER TYPE N/A			
DRILLER D. Kubinski			START DATE 05/02/23			COMP. DATE 05/02/23			SURFACE WATER DEPTH N/A			
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER INCREMENT			SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			1.75in	1.75in	1.75in	0	25					
720												
715												
710	714.2	1.0										
	713.2	2.0	11	12	12							
	712.2	3.0	7	8	13							
	711.2	4.0	9	9	12							
	710.2	5.0	22	25+								
705	709.2	6.0	19	23	25							
	708.2	7.0	13	25	25+							
	707.2	8.0	15	25+								
	706.2	9.0	25+									
	705.2	10.0	24	25+								
			24	25+								
715.2 GROUND SURFACE 0.0												
RESIDUAL Medium Stiff to Stiff, Olive, Coarse to Fine Sandy SILT, Trace Mica												
704.9 10.3												
Boring Terminated at Elevation 704.9 ft in RESIDUAL (Sandy SILT)												
NOTE: Conventional dynamic cone penetrometer test performed at 1 foot intervals.												

NCDOT BORE DOUBLE BR0015_GEO_RDWY_GINT.GPJ NC_DOT.GDT 6/14/23

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST D. Kubinski					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)								GROUND WTR (ft)					
BORING NO. Y1_1800		STATION 18+00		OFFSET 35 ft RT		ALIGNMENT -Y1-		0 HR. Dry					
COLLAR ELEV. 713.9 ft		TOTAL DEPTH 7.0 ft		NORTHING 757,975		EASTING 1,622,120		24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD Hand Auger		HAMMER TYPE N/A							
DRILLER D. Kubinski		START DATE 05/04/23		COMP. DATE 05/04/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft) DEPTH (ft)
715													713.9 GROUND SURFACE 0.0
710											M		RESIDUAL Medium Stiff to Stiff, Brown to Light Brownish Gray, Coarse to Fine Sandy SILT
											M		706.9 7.0
													Boring Terminated at Elevation 706.9 ft in RESIDUAL (Sandy SILT)

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST D. Kubinski					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)								GROUND WTR (ft)					
BORING NO. Y1_1900		STATION 19+00		OFFSET 35 ft LT		ALIGNMENT -Y1-		0 HR. Dry					
COLLAR ELEV. 705.9 ft		TOTAL DEPTH 6.7 ft		NORTHING 758,006		EASTING 1,622,238		24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE N/A				DRILL METHOD Hand Auger		HAMMER TYPE N/A							
DRILLER D. Kubinski		START DATE 05/04/23		COMP. DATE 05/04/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft) DEPTH (ft)
710													705.9 GROUND SURFACE 0.0
705											M		RESIDUAL Soft to Medium Stiff, Light Brownish Gray, Coarse to Fine Sandy SILT
700											M		699.2 6.7
													Boring Terminated at Elevation 699.2 ft in RESIDUAL (Sandy SILT)

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1				TIP BR-0015		COUNTY DAVIDSON		GEOLOGIST M. Foster							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)										GROUND WTR (ft)					
BORING NO. Y2_1050				STATION 10+50		OFFSET 11 ft LT		ALIGNMENT -Y2-		0 HR.	Dry				
COLLAR ELEV. 729.5 ft				TOTAL DEPTH 9.9 ft		NORTHING 758,225		EASTING 1,621,685		24 HR.	FIAD				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman				START DATE 04/28/23		COMP. DATE 04/28/23		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
730														GROUND SURFACE 0.0	
725	729.5	0.0	1	3	4	7	.	.	.	.		M		ROADWAY EMBANKMENT	
	726.0	3.5	21	3	4	7	.	.	.	.		M		Medium Stiff, Reddish Brown and Gray, Silty CLAY, Trace Mica and Concrete Fragments	
720							.	.	.	.				722.8	6.7
	721.1	8.4	3	2	2		.	.	.	.		W		Medium Stiff, Reddish Brown, Fine Sandy SILT	
						4	.	.	.	.				719.9	9.6
														719.6	9.9

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST J. Kardon					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. Y2_1250			STATION 12+50			OFFSET 20 ft RT			ALIGNMENT -Y2-			0 HR. Dry		
COLLAR ELEV. 730.5 ft			TOTAL DEPTH 15.0 ft			NORTHING 758,259			EASTING 1,621,885			24 HR. FIAD		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 05/09/23			COMP. DATE 05/09/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
730														
725	729.5	1.0												730.5 GROUND SURFACE 0.0
	727.0	3.5	3	3	3						SS-25	31%		729.5 ROADWAY EMBANKMENT 1.0
	727.0		2	4	4							M		Asphalt (0.0 - 0.5 Foot) ABC Stone (0.5 - 1.0 Foot) Medium Stiff, Highly Plastic, Red, Silty CLAY, Trace Mica
720	722.0	8.5	3	3	3							M		
	717.0	13.5	2	2	3							M		

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

NCDOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC DOT.GDT 6/15/23

[illegible]

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)											GROUND WTR (ft)				
BORING NO. RPB_1706			STATION 17+06			OFFSET 53 ft LT			ALIGNMENT -RPB-			0 HR.	Dry		
COLLAR ELEV. 758.9 ft			TOTAL DEPTH 39.8 ft			NORTHING 757,994			EASTING 1,621,500			24 HR.	Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/28/23			COMP. DATE 04/28/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
760															
	758.9	0.0												758.9	GROUND SURFACE 0.0
			WOH	WOH	2							M		Soft to Medium Stiff, Moderately Plastic, Reddish Brown, Silty CLAY, Trace Mica	
755	755.6	3.3	4	6	2						SS-27	33%			
750	750.4	8.5	2	3	4							M			
745	745.4	13.5	4	5	6							M			
740	740.4	18.5	4	7	7							M			
735	735.4	23.5	4	6	8							M			
730	730.4	28.5	5	6	8							M			
725	725.4	33.5	5	7	8							M			
720	720.6	38.3	3	6	7							M			
													Boring Terminated at Elevation 719.1 ft in RESIDUAL (Sandy SILT)		

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. RPB_1900			STATION 19+00			OFFSET 70 ft RT			ALIGNMENT -RPB-			0 HR. Dry		
COLLAR ELEV. 729.7 ft			TOTAL DEPTH 19.5 ft			NORTHING 758,118			EASTING 1,621,694			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/19/23			COMP. DATE 04/19/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
730														
725	728.7	1.0									SS-28	38%		729.7 GROUND SURFACE 0.0
	726.7	3.0	2	3	3									M
720	721.7	8.0												724.2 5.5
	716.7	13.0	2	3	3									M
715	711.7	18.0	1	1	2									
			1	1	2									M
														710.2 19.5
														Boring Terminated at Elevation 710.2 ft in RESIDUAL (Sandy SILT)

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23




GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)						
BORING NO. RPD_1183			STATION 11+83			OFFSET 15 ft LT			ALIGNMENT -RPD-			0 HR. Dry			
COLLAR ELEV. 734.7 ft			TOTAL DEPTH 10.0 ft			NORTHING 758,463			EASTING 1,622,368			24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman			START DATE 05/04/23			COMP. DATE 05/04/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
735															
	734.7	0.0	2	2	3	5	.	.	.	.		M		734.7	GROUND SURFACE 0.0
	731.2	3.5	2	2	3	5	.	.	.	.		M		RESIDUAL Medium Stiff, Brown, Coarse to Fine Sandy SILT, Trace Mica	
	726.2	8.5	2	3	4	7	.	.	.	.		M		724.7	10.0
														Boring Terminated at Elevation 724.7 ft in RESIDUAL (Sandy SILT)	

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster						
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)						
BORING NO. RPD-RT_1055			STATION 10+55			OFFSET 37 ft RT			ALIGNMENT -RPD-RT-			0 HR. Dry			
COLLAR ELEV. 730.3 ft			TOTAL DEPTH 9.8 ft			NORTHING 758,395			EASTING 1,622,369			24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER R. Toothman			START DATE 05/01/23			COMP. DATE 05/01/23			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
735															
730	730.3	0.0												730.3 GROUND SURFACE 0.0	
725			1	2	2	4	.	.	.	.	SS-29	31%		727.9	RESIDUAL Medium Stiff, Moderately Plastic, Reddish Brown, Silty CLAY, Trace Mica 2.4
	727.0	3.3	1	2	3	5	.	.	.	.		M		727.9	Medium Stiff, Yellowish Brown, Fine Sandy SILT, Trace Mica
	722.0	8.3	2	3	4	7	.	.	.	.		M		720.5	9.8
														Boring Terminated at Elevation 720.5 ft in RESIDUAL (Sandy SILT)	

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

NCDOT BORE DOUBLE BR0015 GEO RDWY GINT.GPJ NC DOT GDT 6/15/23

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster					
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)					
BORING NO. LPB_1375			STATION 13+75			OFFSET 70 ft RT			ALIGNMENT -LPB-			0 HR. Dry		
COLLAR ELEV. 737.5 ft			TOTAL DEPTH 20.0 ft			NORTHING 757,997			EASTING 1,621,665			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER R. Toothman			START DATE 04/19/23			COMP. DATE 04/19/23			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
740														
735	736.4	1.1	2	3	3	6					SS-30	40%		737.5 GROUND SURFACE 0.0
	734.0	3.5	2	4	4	8						W		
730														
	729.0	8.5	2	4	5	9						M		
725														
	724.0	13.5	3	3	5	8						M		
720														
	719.0	18.5	2	3	5	8						M		
														Boring Terminated at Elevation 717.5 ft in RESIDUAL (Sandy SILT) 20.0

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 67015.1.1			TIP BR-0015			COUNTY DAVIDSON			GEOLOGIST M. Foster							
SITE DESCRIPTION Bridge No. 67 and No. 68 Replacements on US 29/US 70 NB & SB over SR 1192 (W. 5th Avenue)									GROUND WTR (ft)							
BORING NO. DRW1_1050			STATION 10+50			OFFSET 15 ft RT			ALIGNMENT -DRW1-			0 HR. Dry				
COLLAR ELEV. 737.5 ft			TOTAL DEPTH 20.0 ft			NORTHING 758,376			EASTING 1,622,037			24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE TRI0055 CME-55 83% 05/09/2022						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER R. Toothman			START DATE 04/25/23			COMP. DATE 04/25/23			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
740																
735	737.5	0.0	3	7	5						SS-31	31%		737.5	0.0	
	734.0	3.5	3	5	6							M				
730												M			730.7	6.8
725	729.0	8.5	2	4	4							M			Medium Stiff to Stiff, Reddish Brown to Yellowish Brown to Light Brown, Fine Sandy SILT, Trace Mica	
	724.0	13.5	2	4	5							M				
720																
	719.0	18.5	2	4	5							M		717.5	20.0	
														Boring Terminated at Elevation 717.5 ft in RESIDUAL (Sandy SILT)		

NCDOT BORE DOUBLE BR0015_GEO_ROWY_GINT.GPJ NC_DOT.GDT 6/15/23

PROJECT: 67015 REFERENCE: BR-0015

PROJECT REFERENCE NO.	SHEET NO.
BR-0015	34

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
APPENDIX B
LABORATORY RESULTS

LABORATORY SUMMARY SHEET FOR SOIL SAMPLES

WBS NO. (TIP NO.): 67015.1.1 (BR-0015)
PROJECT ID: 41620
COUNTY: DAVIDSON
DESCRIPTION: BRIDGE NO. 67 AND NO. 68 REPLACEMENTS ON US 29/US 70 NB & SB OVER SR 1192 (W. 5TH AVENUE)

									Atterberg Limits			Gradation Results							
Sample No.	Boring Number	Alignment	Station	Offset	Sample Depth (ft.)	Natural Moisture Content (%)	AASHTO Class.	N-Value (blows/ft)	L.L.	P.L.	P.I.	Retained #4 Sieve	Pass #10 Sieve	Pass #40 Sieve	Pass #200 Sieve	Coarse Sand (%)	Fine Sand (%)	Silt (%)	Clay (%)
SS-1	L_1250	-L-	12+50	95' LT	0.4 - 1.9	30.3	A-7-6	10	74	34	40	0.0	98.8	85.5	68.7	19.9	14.4	11.9	53.8
SS-2	L_1450	-L-	14+50	88' LT	3.5 - 5.0	24.1	A-7-6	17	54	28	26	0.0	99.0	84.0	64.0	21.3	20.7	25.1	33.0
SS-3	L_1650	-L-	16+50	87' LT	3.6 - 5.1	26.7	A-7-5	18	76	33	43	0.0	99.0	93.8	79.2	11.5	11.5	36.4	40.6
SS-4	L_2049	-L-	20+49	90' LT	3.5 - 5.0	27.3	A-7-5	18	68	32	36	0.0	100.0	97.2	77.8	8.5	16.5	42.4	32.6
SS-5	L_2049	-L-	20+49	90' LT	8.5 - 10.0	42.8	A-7-5	12	58	40	18	0.0	100.0	97.3	65.0	12.2	29.2	26.3	32.3
SS-6	L_2250	-L-	22+50	106' LT	0.0 - 1.5	16.2	A-7-6	17	48	21	27	2.0	96.0	89.9	66.3	17.4	20.1	20.0	42.5
SS-7	L_2250	-L-	22+50	106' LT	8.5 - 10.0	31.5	A-7-5	18	86	42	44	16.0	100.0	95.5	81.8	9.0	11.7	19.0	60.3
SS-8	L_2250	-L-	22+50	106' LT	18.5 - 20.0	42.6	A-7-5	6	62	50	12	0.0	100.0	96.0	68.5	7.2	32.9	27.6	32.2
SS-9	L_2460	-L-	24+60	90' RT	1.0 - 2.5	37.1	A-7-5	6	78	45	33	0.0	100.0	97.8	86.5	4.2	13.2	23.4	59.2
SS-10	L_2599	-L-	25+99	35' RT	8.5 - 10.0	39.4	A-7-5	8	65	34	31	0.0	100.0	99.4	80.3	2.4	25.4	34.6	37.7
SS-11	L_2650	-L-	26+50	90' RT	1.0 - 2.5	32.1	A-7-5	7	73	35	38	2.0	97.0	94.5	79.0	8.8	16.4	21.4	53.4
SS-12	L_2700	-L-	27+00	31' RT	3.7 - 5.2	32.5	A-7-5	6	52	30	22	0.0	100.0	90.1	64.0	16.3	25.7	25.6	32.5
SS-13	L_2750	-L-	27+50	90' RT	1.0 - 2.5	21.7	A-7-5	5	56	31	25	3.0	92.0	88.3	63.3	18.1	24.2	23.0	34.6
SS-14	L_2800	-L-	28+00	29' RT	13.5 - 15.0	29.7	A-7-5	7	58	34	24	0.0	100.0	96.0	72.4	9.4	23.7	24.9	41.9
SS-15	L_3400	-L-	34+00	81' LT	0.0 - 1.5	25.8	A-7-5	6	64	44	20	14.0	94.0	85.0	60.0	14.4	28.8	23.9	32.9
SS-16	L_3600	-L-	36+00	85' LT	3.5 - 5.0	32.2	A-7-5	13	72	35	37	0.0	100.0	97.3	86.0	5.9	10.6	61.7	97.3
S-17	L_3800	-L-	38+00	0' CL	0.5 - 1.0	24.7	A-7-6	--	55	25	30	0.0	99.2	92.5	69.9	14.0	19.8	13.2	53.0
S-18	L_4000	-L-	40+00	0' CL	1.0 - 1.5	33.2	A-7-5	--	65	40	25	0.0	99.1	94.7	73.2	10.1	20.9	23.9	45.1
S-19	L_4400	-L-	44+00	0' CL	1.0 - 1.5	30.4	A-7-6	--	56	29	27	4.0	96.0	91.0	60.0	11.3	32.6	19.6	36.5
S-20	L_4600	-L-	46+00	0' CL	1.0 - 2.0	26.8	A-7-5	--	51	33	18	0.0	99.0	96.0	51.0	13.0	41.3	13.6	32.1
SS-21	Y1_1042	-Y1-	10+42	62' RT	0.0 - 1.5	27.7	A-7-5	12	69	37	32	0.0	100.0	95.2	76.1	10.9	16.2	20.3	52.6
SS-22	Y1_1250	-Y1-	12+50	43' LT	1.0 - 2.5	31.1	A-7-5	11	60	36	24	0.0	99.0	93.3	73.9	11.2	20.5	24.9	43.4
SS-23	Y1_1512	-Y1-	15+12	46' RT	3.4 - 4.1	38.7	A-5	4	50	41	9	0.0	99.0	94.3	66.6	11.8	28.5	25.9	33.8
SS-24	Y1_1550	-Y1-	15+50	45' LT	3.5 - 5.0	28.6	A-7-5	9	59	35	24	0.0	98.0	94.3	76.3	10.3	15.9	25.7	48.1
SS-25	Y2_1250	-Y2-	12+50	20' RT	1.0 - 2.5	31.3	A-7-5	6	67	33	34	0.0	100.0	96.8	77.3	7.2	20.7	23.3	48.8
SS-26	RPB_1495	-RPB-	14+95	50' LT	8.4 - 9.9	34.2	A-7-5	12	66	49	17	0.0	100.0	97.3	75.2	7.8	21.9	27.7	42.6
SS-27	RPB_1706	-RPB-	17+06	53' LT	3.3 - 4.8	32.7	A-7-5	13	64	43	21	0.0	99.9	96.1	73.2	9.4	22.0	16.1	52.5
SS-28	RPB_1900	-RPB-	19+00	70' RT	1.0 - 2.5	37.8	A-7-5	6	74	46	28	0.0	100.0	99.3	76.1	2.3	28.4	25.3	44.0
SS-29	RPD-RT_1055	-RPD-RT-	10+55	37' RT	0.0 - 1.5	30.7	A-7-5	4	51	31	20	1.0	97.0	89.7	64.7	16.0	25.8	33.5	24.7
SS-30	LPB_1375	-LPB-	13+75	70' RT	1.1 - 2.6	39.5	A-7-5	6	62	37	25	0.0	100.0	98.4	85.5	3.6	17.6	36.7	42.1
SS-31	DRW1_1050	-DRW1-	10+50	15' RT	0.0 - 1.5	30.7	A-7-5	12	62	34	28	0.0	99.4	92.2	72.4	13.8	17.3	21.8	47.1
CBR-1	L_1450	-L-	14+50	88' LT	8.5 - 18.5	27.0	A-7-5	--	60	44	16	0.0	100.0	93.1	56.6	14.7	35.3	23.4	26.6
CBR-2	L_1850	-L-	18+50	89' LT	0.0 - 10.0	30.6	A-7-5	--	60	35	25	0.0	100.0	95.2	75.9	9.9	19.4	26.1	44.7
CBR-3	L_4200	-L-	42+00	0' CL	0.0 - 2.5	37.3	A-7-5	--	73	37	36	8.0	91.0	96.6	78.4	7.2	18.6	28.9	45.2

Michelle Stadel, P.E.
Lab Manager, NCDOT Certification No.: 111-02-1203

Clifford Blalock
Lab Technician, NCDOT Certification No.: 111-03-1203

Matt Johnson
Lab Technician, NCDOT Certification No.: 111-01-1203

Victoria Siebert
Lab Technician, NCDOT Certification No.: 109-02-1003


Laboratory Test Report

Client: North Carolina Dept. of Transportation
Project: 20235702.001A
NCDOT BR-0015 Roadway
02-000L - Lab

Report No.: 23-CLT-00649 Rev. 1
Sampled by: Mayson Foster
Submitted by: Dan Kubinski

Issued: 6/9/2023
Field ID: L_1450, CBR-1
Date: 5/8/2023
Date: 5/15/2023

Tested on 5/24/2023 by C. Blalock
Material Description: Brown Sandy Silt (A-7-5)
Location: Boring No. L_1450, Alignment -L-, STA 14+50, 88' LT



Test Method: AASHTO T99 A	Uncorrected	Corrected
Maximum Dry Unit Weight (pcf)	94.0	na
Optimum Water Content (%)	23.6	na
Oversize Fraction, retained on 3/4 (%)		<5
Bulk Specific Gravity of Oversize Fraction		na

Rammer Type: Manual
Specimen Preparation: Moist

Remarks:
AASHTO T-100, Soil Specific Gravity @ 20°C: 2.747

Reviewed on 6/9/2023 by Michelle Stadel,

Michelle M. Stadel

Laboratory Test Report

Client: North Carolina Dept. of Transportation
Project: 20235702.001A
NCDOT BR-0015 Roadway
02-000L - Lab

Report No.: 23-CLT-00649 Rev. 1
Sampled by: Mayson Foster
Submitted by: Dan Kubinski

Issued: 6/9/2023
Field ID: L_1450, CBR-1
Date: 5/8/2023
Date: 5/15/2023


Sample Source: Boring No. L_1450, Alignment -L-, STA 14+50, 88' LT
Sample ID: CBR-1
Sample Description: Brown Sandy Silt (A-7-5)
Material Used:
Surcharge Weight: 10 lbs

Date Tested: 5/30/2023
Tested By: C. Blalock
Condition of Sample: Soaked
Time Soaked: 96 hrs

AASHTO T193 - Standard Test Method for The California Bearing Ratio (CBR)

Dry Unit Wgt Before Soaking (pcf): 90.8
Water Content Before Soaking (%): 21.2
Dry Unit Wgt After Soaking (pcf): 101.1
Water Content After Soak, Top in. (%): 30.3
Swell (%): 5.65
CBR (Corrected CBR) @ 0.1 in. Penetration: 5.8 (5.8)
CBR (Corrected CBR) @ 0.2 in. Penetration: 6.6 (6.6)

Compaction Method: Manual
Max. Dry Unit Weight: 94.0 pcf
Optimum Water Content: 23.6 %



Remarks:

Reviewed on 6/9/2023 by Michelle Stadel,

Michelle M. Stadel



Laboratory Test Report

Client: North Carolina Dept. of Transportation

Report No.: 23-CLT-00650 Rev. 1

Issued: 6/9/2023

Project: 20235702.001A

Field ID: L_1850, CBR-2

Sampled by: Mayson Foster

Date: 5/9/2023

Submitted by: Dan Kubinski

Date: 5/15/2023


NCDOT BR-0015 Roadway

02-000L - Lab

Tested on 5/24/2023 by C. Blalock

Material Description: Reddish Yellow Elastic Silt with Sand (A-7-5)

Location: Boring No. L_1850, -L-, STA 18+50, 89' LT



Test Method: AASHTO T99 A	Uncorrected	Corrected
Maximum Dry Unit Weight (pcf)	102.8	na
Optimum Water Content (%)	19.1	na
Oversize Fraction, retained on 3/4 (%)		<5
Bulk Specific Gravity of Oversize Fraction		na

Rammer Type: Manual

Specimen Preparation: Moist

Remarks:

AASHTO T-100, Soil Specific Gravity at 20°C: 2.678

Reviewed on 6/9/2023 by Michelle Stadel,

Michelle M Stadel

Limitations: Pursuant to applicable building codes, the results presented in this report are for the exclusive use of the client and the registered design professional in responsible charge. The results apply only to the samples tested. If changes to the specifications were made and not communicated to Kleinfelder, Kleinfelder assumes no responsibility for pass/fail statements (meets/did not meet), if provided. This report may not be reproduced, except in full, without written approval of Kleinfelder.



Laboratory Test Report

Client: North Carolina Dept. of Transportation

Report No.: 23-CLT-00650 Rev. 1

Issued: 6/9/2023

Project: 20235702.001A

Field ID: L_1850, CBR-2

Sampled by: Mayson Foster

Date: 5/9/2023

Submitted by: Dan Kubinski

Date: 5/15/2023

NCDOT BR-0015 Roadway

02-000L - Lab

Sample Source: Boring No. L_1850, -L-, STA 18+50, 89' LT

Sample ID: CBR-2

Sample Description: Reddish Yellow Elastic Silt with Sand (A-7-5)

Material Used:

Surcharge Weight: 10 lbs

Date Tested: 5/30/2023


Tested By: C. Blalock

Condition of Sample: Soaked

Time Soaked: 96 hrs

AASHTO T-193 - Standard Test Method for The California Bearing Ratio

Dry Unit Wgt Before Soaking (pcf):	100.6	Compaction Method:	Manual
Water Content Before Soaking (%):	17.0	Max. Dry Unit Weight:	102.8 pcf
Dry Unit Wgt After Soaking (pcf):	106.1	Optimum Water Content:	19.1 %
Water Content After Soak, Top in. (%):	27.1		
Swell (%):	4.1		
CBR (Corrected CBR) @ 0.1 in. Penetration:	6.1 (6.1)		
CBR (Corrected CBR) @ 0.2 in. Penetration:	6.7 (6.7)		



Remarks:

Reviewed on 6/9/2023 by Michelle Stadel,

Michelle M Stadel

Limitations: Pursuant to applicable building codes, the results presented in this report are for the exclusive use of the client and the registered design professional in responsible charge. The results apply only to the samples tested. If changes to the specifications were made and not communicated to Kleinfelder, Kleinfelder assumes no responsibility for pass/fail statements (meets/did not meet), if provided. This report may not be reproduced, except in full, without written approval of Kleinfelder.