

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.07.03.20011	18	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	BEGIN MP	END MP	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH	1330000000-E INCIDENTAL MILLING	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775000000-E ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEEDING & MULCHING	7990000000-E INDUCTIVE LOOP SAW CUT (DEEP CUT)
							MI	FT			CY	TONS	SMI	TON	SY	SY	TONS	TON	TONS	SY	GAL	EA	EA	LF	LF	AC	LF
2026CPT.07.03.20011	Alamance	22	SR-1633 / HAMILTON RD	FROM SR 1597 - GREENWOOD DR TO DEAD END	1	2	0.24	20	0.00	0.24	11	9	0.45			167	252	20	80	2,639	871			89	9	0.04	
TOTAL FOR MAP NO. 22							0.24				11	9	0.45			167	252	20	80	2,639	871			89	9	0.04	
2026CPT.07.03.20011	Alamance	23	SR-1625 / DOGWOOD ST	FROM DEAD END TO DEAD END	1	2	0.36	20	0.00	0.36	17	24	0.70	2			411	31	85	4,126	1,361			140	14	0.06	
TOTAL FOR MAP NO. 23							0.36				17	24	0.70	2			411	31	85	4,126	1,361			140	14	0.06	
2026CPT.07.03.20011	Alamance	24	SR-1634 / CARLTON AVE	FROM END PVMT TO DEAD END	1	2	0.26	20	0.00	0.26	13	48	0.53	1			292	21	45	3,119	1,029			106	11	0.05	
TOTAL FOR MAP NO. 24							0.26				13	48	0.53	1			292	21	45	3,119	1,029			106	11	0.05	
2026CPT.07.03.20011	Alamance	25	SR-1624 / BEVERLY RD	FROM SR 1597 - GREENWOOD DR TO SR 1634 - CARLTON AV	1	2	0.16	19	0.00	0.16	7	3	0.27			167	142	13	75	1,567	517			54	5	0.02	
TOTAL FOR MAP NO. 25							0.16				7	3	0.27			167	142	13	75	1,567	517			54	5	0.02	
2026CPT.07.03.20011	Alamance	26	SR-1673 / ELON CT	FROM SR 1672 - SPRINGFIELD DR TO CUL-DE-SAC	1	2	0.03	20	0.00	0.03	2		0.06				55	4		608	201			12	1	0.01	
TOTAL FOR MAP NO. 26							0.03				2		0.06				55	4		608	201			12	1	0.01	
2026CPT.07.03.20011	Alamance	27	SR-1672 / SPRINGFIELD DR	FROM SR 1504 - ELON OSSIPEE RD TO CUL-DE-SAC	1	2	0.29	20	0.00	0.29	12	12	0.53	3		667	334	23	30	3,343	1,103			106	11	0.04	
TOTAL FOR MAP NO. 27							0.29				12	12	0.53	3		667	334	23	30	3,343	1,103			106	11	0.04	
2026CPT.07.03.20011	Alamance	28	SR-1674 / WIMBSLEY DR	FROM SR 1672 - SPRINGFIELD DR TO SR 1676 - BARRINGTON RD	1	2	0.14	20	0.00	0.14	6		0.24				151	10	10	1,478	488			49	5	0.02	
TOTAL FOR MAP NO. 28							0.14				6		0.24				151	10	10	1,478	488			49	5	0.02	
2026CPT.07.03.20011	Alamance	29	SR-1676 / BARRINGTON RD	FROM SR 1504 - ELON OSSIPEE RD TO DEAD END	1	2	0.15	21	0.00	0.15	5	15	0.29	5		175	183	12	10	1,784	589			58	6	0.02	
TOTAL FOR MAP NO. 29							0.15				5	15	0.29	5		175	183	12	10	1,784	589			58	6	0.02	
2026CPT.07.03.20011	Alamance	30	SR-1675 / BARTON CT	FROM SR 1674 - WIMBSLEY DR TO CUL- DE-SAC	1	2	0.05	20	0.00	0.05	2	3	0.09				68	5	15	754	249			18	2	0.01	
TOTAL FOR MAP NO. 30							0.05				2	3	0.09				68	5	15	754	249			18	2	0.01	
2026CPT.07.03.20011	Alamance	31	SR-1677 / INDIAN VALLEY DR	FROM SR 1597 - GREENWOOD DR TO SR 1597 - GREENWOOD DR	1	2	1.14	21	0.00	1.14	37	21	2.27	38		350	1,305	87	40	14,083	4,648			455	45	0.13	
TOTAL FOR MAP NO. 31							1.14				37	21	2.27	38		350	1,305	87	40	14,083	4,648			455	45	0.13	
2026CPT.07.03.20011	Alamance	32	SR-1678 / WHISPERING WIND RD	FROM SR 1677 - INDIAN VALLEY DR TO SR 1677 - INDIAN VALLEY DR	1	2	0.26	20	0.00	0.26	6	3	0.51	12			275	19	15	3,030	1,000			103	10	0.02	
TOTAL FOR MAP NO. 32							0.26				6	3	0.51	12			275	19	15	3,030	1,000			103	10	0.02	
2026CPT.07.03.20011	Alamance	33	SR-1679 / HIAWATHA PL	FROM SR 1677 - INDIAN VALLEY DR TO EOM	1	2	0.08	20	0.00	0.08	4	3	0.17				105	8	20	1,017	336			34	3	0.02	
TOTAL FOR MAP NO. 33							0.08				4	3	0.17				105	8	20	1,017	336			34	3	0.02	
2026CPT.07.03.20011	Alamance	34	SR-1680 / HIAWATHA CT	FROM SR 1679 - HIAWATHA PL TO CUL- DE-SAC	1	2	0.09	20	0.00	0.09	5	12	0.18				115	8	20	1,273	420			36	4	0.02	
TOTAL FOR MAP NO. 34							0.09				5	12	0.18				115	8	20	1,273	420			36	4	0.02	
2026CPT.07.03.20011	Alamance	35	SR-1652 / SNUG HARBOR RD	FROM SR 1597 - GREENWOOD DR TO SR 1598 - ISLEY SCHOOL RD	1	2	0.29	20	0.00	0.29	9	12	0.54	8		354	308	22	45	3,270	1,079			108	11	0.03	
TOTAL FOR MAP NO. 35							0.29				9	12	0.54	8		354	308	22	45	3,270	1,079			108	11	0.03	
2026CPT.07.03.20011	Alamance	36	SR-1653 / YAMOTA DR	FROM SR 1652 - SNUG HARBOR RD TO END PVMT	1	2	0.25	17	0.00	0.25	7	15	0.50	9			239	17	40	2,638	871			99	10	0.03	
TOTAL FOR MAP NO. 36							0.25				7	15	0.50	9			239	17	40	2,638	871			99	10	0.03	
2026CPT.07.03.20011	Alamance	37	SR-2701 / GORDON ST	FROM SR 1520 - RIVERVIEW DR TO SR 1530 - BURCH BRIDGE RD	1	2	0.32	20	0.00	0.32	8	45	0.61	14		167	327	24	65	3,600	1,188			122	12	0.03	
TOTAL FOR MAP NO. 37							0.32				8	45	0.61	14		167	327	24	65	3,600	1,188			122	12	0.03	
2026CPT.07.03.20011	Alamance	38	SR-1521 / ST REGIS DR	FROM SR 1520 - RIVERVIEW DR TO SR 1530 - BURCH BRIDGE RD	1	2	0.34	20	0.00	0.34	11	60	0.65	9		167	370	26	40	3,813	1,258			129	13	0.04	
TOTAL FOR MAP NO. 38							0.34				11	60	0.65	9		167	370	26	40	3,813	1,258			129	13	0.04	
2026CPT.07.03.20011	Alamance	39	SR-1520 / RIVERVIEW DR	FROM SR 1529 - DURHAM ST EXT TO SR 2701 - GORDON ST	1	2	0.26	20	0.00	0.26	5	36	0.49	14		167	297	21	25	2,885	952	1		98	10	0.02	
TOTAL FOR MAP NO. 39							0.26				5	36	0.49	14		167	297	21	25	2,885	952	1		98	10	0.02	
2026CPT.07.03.20011	Alamance	40	SR-1519 / PINECROFT DR	FROM SR 1521 - ST REGIS DR TO SR 1516 - POLLARD AV	1	2	0.38	20	0.00	0.38	11	78	0.72	14			384	27	35	4,226	1,395	1		143	14	0.04	
TOTAL FOR MAP NO. 40							0.38				11	78	0.72	14			384	27	35	4,226	1,395	1		143	14	0.04	
2026CPT.07.03.20011	Alamance	41	SR-1516 / POLLARD AVE	FROM SR 1530 - BURCH BRIDGE RD TO SR 1529 - DURHAM ST EXT	1	2	0.37	19	0.00	0.37	15	75	0.72	5		325	402	28	35	4,165	1,374	1	2	145	14	0.06	
TOTAL FOR MAP NO. 41							0.37				15	75	0.72	5		325	402	28	35	4,165	1,374	1	2	145	14	0.06	
TOTAL FOR PROJ NO. 2026CPT.07.03.20011							29.85				761	1,839	56.88	1,246	15,718	10,428	35,906	2,511	3,709	367,400	121,243	13	15	11,464	1,146	2.76	816
GRAND TOTAL							29.85				761	1,839	56.88	1,246	15,718	10,428	35,906	2,511	3,709	367,400	121,243	13	15	11,464	1,146	2.76	816

NOTE: All Quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received.