
Docusign Envelope ID: E237D0F0-9E2A-4677-A80C-647C717DF96C



### DESIGN REFERENCE MATERIAL

36.8 ft.

+4.5 ft.

-1.8 ft.

Terminal

Compartment

180°--

-·180°--

180°--Ç ---

-Plate width

@ 180°

# DESIGN REQUIREMENTS

- requirements.

- the following:

METAL POLE No. 1
------------------

ROJECT REFERENCE NO. SHEET NO. R-4463A

Sig-8.3

MAST ARM LOADING SCHEDULE					
loading symbol	DESCRIPTION	AREA	SIZE	WEIGHT	
	RIGID MOUNTED SIGNAL HEAD 12"-3 SECTION-WITH BACKPLATE	9.3 S.F.	25.5″W X 52.5″L	60 LBS	
Street Name	STREET NAME SIGN RIGID MOUNTED	16.0 S.F.	24.0″W X 96.0″L	36 LBS	

### NOTES

1. Design the traffic signal structure and foundation in accordance with: • The 1st Edition 2015 AASHTO LRFD "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, including all of the latest interim revisions. • The 2024 NCDOT "Standard Specifications for Roads and Structures." The latest addenda to the specifications can be found in the traffic signalproject specialprovisions. • The 2024 NCDOT Roadway Standard Drawings.

• The traffic signal project plans and special provisions.

The NCDOT "MetalPole Standards" located at the following NCDOT website:

https://connect.ncdot.gov/resources/safety/Pages/ITS-Design-Resources.aspx

2. Design the traffic signalstructure using the loading conditions shown in the elevation views. These are anticipated worst case "design loads" and may not represent the actual loads that will be applied at the time of the installation. The contractor should refer to the traffic signalplans for the actualloads that willbe applied at the time of the installation. 3. Design all signal supports using force ratios that do not exceed 0.9.

4. The camber design for the mast arm deflection should provide an appearance of a low pitched arch where the tip or the free end of the mast arm does not deflect below horizontal when fully loaded.

5. A clamp-type bolted mast arm-to-pole connection may be used instead of the welded ring stiffened box connection shown as long as the connection meets all of the design

6. Design base plate with 8 anchor bolt holes. Provide 2 inch x 60 inch anchor bolts. 7. The mast arm attachment height (H1) shown is based on the following design assumptions: a. Mast arm slope and deflection are not considered in determining the arm attachment height as they are assumed to offset each other.

b. Signalheads are rigidly mounted and vertically centered on the mast arm.

c. The roadway clearance height for design is as shown in the elevation views.

d. The top of the pole base plate is 0.75 feet above the ground elevation.

e. Refer to the Elevation Data Chart for the elevation differences between the proposed foundation ground leveland the high point of the roadway.

8. The pole manufacturer will determine the total height (H2) of each pole using the greater of

• Mast arm attachment height (H1) plus 2 feet, or

• H1 plus 1/2 of the total height of the mast arm attachment assembly plus 1 foot. 9. If pole location adjustments are required, the contractor must gain approval from the Engineer as this may affect the mast arm lengths and arm attachment heights. The contractor may contact the Signal Design Section Senior Structural Engineer for assistance at (919)814-5000.

10. The contractor is responsible for verifying that the mast arm length shown will allow proper positioning of the signalheads over the roadway.

11. The contractor is responsible for providing soilpenetration testing data (SPT) to the pole manufacturer so site specific foundations can be designed.

## NCDOT Wind Zone 2 (140 mph)

		UNLESS ALL SIGNATURES COMPLETED	
Prepared for: Nobility and Society Division	NC 43 at US 17 NB/US 70 EB Ramps	SEAL	
	Division 2 Craven County New Bern	052936	
Design Section	PLAN DATE: April 2025 REVIEWED BY: BN Groome	TI P AGINEER	
.Greenfield Pkwy,Garner,NC 27529	PREPARED BY: DS Griffith DRMP PROJ. NO.: 17359 (040)		
SCALE	REVISIONS INIT. DATE	Signed by:	
<b> </b>		Brittary N Groome 4/24/2025	
N / A		1E0933402ENQ0944484RE DATE SIG. INVENTORY NO. 02-0924	

DOCUMENT NOT CONSIDERED FINA