1	INSTALL REA, PE – 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE
2	INSTALL COAX CABLE
3	INSTALL ETHERNET CABLE
4	INSTALL SMFO CABLE
5	INSTALL MMFO CABLE
6	INSTALL FIBER OPTIC DROP CABLE
7	INSTALL TRACER WIRE
8	TRENCH
9	INSTALL PVC CONDUIT
10	INSTALL RIGID, GALVANIZED STEEL CONDUIT
11	INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
12	INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
13	INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
14	INSTALL POLYETHYLENE CONDUIT
15	DIRECTIONAL DRILL CONDUIT
16	BORE AND JACK CONDUIT
17	INSTALL CABLE(S) IN EXISTING CONDUIT
18	INSTALL CABLE(S) IN NEW CONDUIT
19	INSTALL CABLE(S) IN EXISTING RISER
20	INSTALL CABLE(S) IN NEW RISER
(21)	INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS
22	INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
23	INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
24	INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
25	INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
26	MODIFY EXISTING INTERCONNECT CENTER /SPLICE ENCLOSURE
27	INSTALL NEW ETHERNET EDGE SWITCH
28	INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS AND FUSION SPLICE CABLE IN CABINET
29	INSTALL UNDERGROUND SPLICE ENCLOSURE
30	INSTALL AERIAL SPLICE ENCLOSURE
31	INSTALL POLE MOUNTED SPLICE CABINET
32	INSTALL BASE MOUNTED SPLICE CABINET
33	REMOVE EXISTING SPLICE CABINET

INSTALL CABINET FOUNDATION REMOVE EXISTING CABINET FOUNDATION INSTALL CCTV CAMERA ASSEMBLY INSTALL CCTV CAMERA WOOD POLE INSTALL CCTV CAMERA METAL POLE AND FOUNDATION INSTALL JUNCTION BOX INSTALL OVERSIZED JUNCTION BOX INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" X 24" X 24") REMOVE EXISTING JUNCTION BOX INSTALL WOOD POLE REMOVE EXISTING WOOD POLE INSTALL AERIAL GUY ASSEMBLY INSTALL STANDARD GUY ASSEMBLY INSTALL SIDEWALK GUY ASSEMBLY INSTALL MESSENGER CABLE REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE REMOVE EXISTING MESSENGER CABLE INSTALL TELEPHONE SERVICE INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE INSTALL DELINEATOR MARKER INSTALL JUNCTION BOX MARKER STORE 50 FEET OF COMMUNICATIONS CABLE LASH CABLE(S) TO EXISTING SIGNAL/COMMUNICATIONS CABLE LASH CABLE(S) TO EXISTING MESSENGER CABLE LASH CABLE(S) TO NEW MESSENGER CABLE 56 MODIFY EXISTING ELECTRICAL SERVICE INSTALL NEW ELECTRICAL SERVICE INSTALL NEW FIELD ETHERNET SWITCH BOND TRACER WIRE TO EQUIPMENT GROUND BUS DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS BOND RISER AND MESSENGER CABLE TO POLE GROUND ATTACHMENT POINT: XX"/SS DISTANCE ABOVE (IN)/ATTACHMENT POINT REFERENCE POINT

REFERENCE POINT

"SS" REFERENCE LOCATION

FS = FRONT SIDE OF POLE

BS = BACK SIDE OF POLE

XX"/SS / DISTANCE BELOW (IN)/ATTACHMENT POINT

(XX XX

LEGEND NEW FIBER OPTIC COMMUNICATIONS CABLE NEW TWISTED PAIR COMMUNICATIONS CABLE EXISTING COMMUNICATIONS CABLE EXISTING COMMUNICATIONS CABLE TO BE REMOVED NEW AERIAL GUY ASSEMBLY **NEW CONDUIT** EXISTING CONDUIT NEW DIRECTIONAL DRILLED CONDUIT NEW BORED AND JACKED CONDUIT NEW JUNCTION BOX EXISTING JUNCTION BOX NEW WOOD POLE EXISTING WOOD POLE NEW UNDERGROUND SPLICE ENCLOSURE AERIAL SPLICE ENCLOSURE NEW METAL POLE EXISTING METAL POLE NEW CCTV ASSEMBLY NEW STANDARD GUY ASSEMBLY NEW SIDEWALK GUY ASSEMBLY NEW CABLE STORAGE RACKS (SNOW SHOES) EXISTING CABLE STORAGE RACK (SNOW SHOES) EXISTING CONTROLLER AND CABINET EXISTING GATEWAY CONTROLLER AND CABINET EXISTING SPLICE CABINET NEW SPLICE CABINET SIGNAL POLE XX-XXXX SIGNAL INVENTORY NUMBER

PROJECT REFERENCE NO.

R-4463A


CONSTRUCTION NOTE SYMBOLOGY KEY


INDICATES NUMBER OF CABLES, LOOPS, ETC.

INDICATES NUMBER OF FIBERS PER CABLE, TWISTED PAIRS PER CABLE, ETC.

 $\langle xx \rangle$ INDICATES NUMBER OF RISER(S)/CONDUIT(S)

INDICATES DIAMETER OF RISER(S)/CONDUIT(S) (INCH)





N/A

D02-15 New Bern Cable Routing Plans DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

TH CARO

ESSION /


052936

New Bern REVIEWED BY: BN Groome TRKA PROJ. NO.: 17359 (041) Brittary N Groome 4/24/2025 -1E09340E1094484... DATE

PREPARED BY: DS Griffth

Plans Prepared By:

R-4463A SCP-



NOTES:


1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

2) CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

3) PRIOR TO CUTTING AND REMOVING ANY EXISTING FIBER OPTIC CABLE, INSTALL A NEW 12-FIBER TRUNK CABLE BETWEEN THE NEW SPLICE ENCLOSURE ON SCP-3 AND THE NEW SPLICE ENCLOSURE ON SCP-2. ENSURE THE NEW 12-FIBER TRUNK LINE AND THE 12-FIBER DROP CABLE TO 02-0629 ARE INSTALLED, SPLICED AND OPERATIONAL.

4) RELOCATE EXISTING FIELD ETHERNET SWITCH AND MODEM TO NEW SIGNAL CABINET WHEN INSTALLED IN TMP PHASE 1, STEP 1.

5) ATTACH THE FIBER OPTIC CABLE AT A HEIGHT OF 28' ON THE NEW POLES.



D02-15_New Bern Cable Routing Plans

Division 2 Craven County New Bern

PLAN DATE: April 2025 REVIEWED BY: BN Groome

PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)

REVISIONS INIT. DATE

FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

SEAL

052936

SEAL

052936

Signed by:

Brittary N Groome


1E09340E1094484...

DATE

DOCUMENT NOT CONSIDERED

Signal*04—Design*SCP*SCP-2.dgn : Kjones

PROJECT REFERENCE NO. SCP-3 R-4463A



NOTES:

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

2) BACKPULL EXISTING FIBER FROM POLE "A" TO NEW AERIAL SPLICE ENCLOSURE. WRAP EXISTING SLACK FIBER AROUND SNOW SHOE AS SHOWN.

3) PRIOR TO CUTTING AND REMOVING ANY EXISTING FIBER OPTIC CABLE, INSTALL A NEW 12–FIBER TRUNK CABLE BETWEEN THE NEW SPLICE ENCLOSURE ON SCP–3 AND THE NEW SPLICE ENCLOSURE ON SCP-2. ENSURE THE NEW 12-FIBER TRUNK LINE AND THE 12-FIBER DROP CABLE TO 02-0629 ARE INSTALLED, SPLICED AND OPERATIONAL.

4) ATTACH THE FIBER OPTIC CABLE AT A HEIGHT OF 28' ON THE NEW POLES.



Preparea For:				
MODILITY and Society of the MORTH CARD			_	lew Bern ing Plan
	Division	2	Craven	County


Plans New Bern PLAN DATE: April 2025 REVIEWED BY: BN Groome DRMP PROJ. NO: 17359 (041) O N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: DS Griffith

SEAL 052936 Brittary N Groome 4/24/2025

DOCUMENT NOT CONSIDERED

FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS INIT. DATE



PROJECT REFERENCE NO. SPLICE ENCLOSURE NC 43 SHEET SHEET 02-0923 SEE SEE 52A 53 52A 53 53 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED D02-15_New Bern Cable Routing Plans NOTES: Division 2 Craven County PLAN DATE: April 2025 REVIEWED BY: BN Groome

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.



PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)

Brittany N Groome 4/24/2025

PROJECT REFERENCE NO. R-4463A NC 43 SHEET SEE 53 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED D02-15_New Bern Cable Routing Plans NOTES: Craven County 1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL. PLAN DATE: April 2025 REVIEWED BY: BN Groome 50 N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041) Brittany N Groome 4/24/2025

PROJECT REFERENCE NO. R-4463A NC 43 40A 52A 53 53 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED D02-15_New Bern Cable Routing Plans NOTES: Division 2 Craven County 1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL. PLAN DATE: April 2025 REVIEWED BY: BN Groome O N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041) Brittany N Groome 4/24/2025

PROJECT REFERENCE NO. NC 43 SHEET SEE DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED D02-15_New Bern Cable Routing Plans NOTES: Division 2 Craven County New Bern 1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL. PLAN DATE: April 2025 REVIEWED BY: BN Groome 50 N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041) Brittary N Groome 4/24/2025 —1E09340E1094484... DATE

PROJECT REFERENCE NO. R-4463A SCP-9 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


NOTES:

MATCHI

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

53

1/412



NC 43


D02-15_New Bern Cable Routing Plans

53

Division 2 Craven County New Bern PLAN DATE: April 2025 REVIEWED BY: BN Groome O N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041) REVISIONS

SEAL 052936 Brittany N Groome 4/24/2025 160934061094484... DATE


PROJECT REFERENCE NO. R-4463A 40A 52A 53 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



NC 43

NOTES:

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.



Plans Prepared By:

D02-15_New Bern Cable Routing Plans

Division 2 Craven County New Bern
PLAN DATE: April 2025 REVIEWED BY: BN Groome
PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)
REVISIONS INIT. DATE

SEAL

OF CAROLING SEAL

SEAL

OS2936

SEAL

SIGNEE

SIGNEE

SIGNEE

SIGNEE

SIGNEE

SIGNEE

SIGNEE


SIGNEE

SIGNEE

DATE

DATE

PROJECT REFERENCE NO. R-4463A 53 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED D02-15_New Bern Cable Routing Plans



NC 43

NOTES:

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.




BDRMP 750 N. Greenfield Phwy., Garner, NC 27529 PREPARED BY: DS Griffith

Division 2 Craven County New Bern PLAN DATE: April 2025 REVIEWED BY: BN Groome DRMP PROJ. NO: 17359 (041)

SEAL 052936 Brittany N Groome 4/24/2025

PROJECT REFERENCE NO.



D02-15_New Bern Cable Routing Plans

Division 2 Craven County PLAN DATE: April 2025 REVIEWED BY: BN Groome DRMP PROJ. NO: 17359 (041)

New Bern


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL 052936

Brittary N Groome 4/24/2025 1E09340E1094484... DATE


NOTES:

1) NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.



PROJECT REFERENCE NO. SHEET NO.

R-4463A SCP-13



NOTES:

- 1. NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

1) SPLICE LOCATION

2) DATE

3) COMPANY NAME

4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.





NO SCALE


D02-15_New Bern Splice Details

Division 2 Craven County New Bern

PLAN DATE: April 2025 REVIEWED BY: BN Groome

PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)

REVISIONS INIT. DATE




DOCUMENT NOT CONSIDERED

4/23/2025 ...*04-Design*SCP*SCP-13.d liser: kiones Docusign Envelope ID: E237D0F0-9E2A-4677-A80C-647C717DF96C

PROJECT REFERENCE NO. SHEET NO.

R-4463A SCP-14




NOTES:

- 1. NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"
 - 1) SPLICE LOCATION
 - 2) DATE
 3) COMPANY NAME
 - 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

ETHERNET SWITCH TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING PROPER TERMINATIONS.





NO SCALE

D02-15_New Bern Splice Details

Division 2 Craven County New Bern
PLAN DATE: April 2025 REVIEWED BY: BN Groome
PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)
REVISIONS INIT. DATE

FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

OFESSION

SEAL

OS2936

TE

Signed by:

WGINEE

A/24/2025


1E09340E1094484...

DATE

DOCUMENT NOT CONSIDERED

4/23/2025 ...*04-Design*SCP*SCP-14.dgn User: kiones

R-4463A SCP-15



ETHERNET SWITCH TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING PROPER TERMINATIONS.

NOTES:

- 1. NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

1) SPLICE LOCATION


2) DATE

3) COMPANY NAME

4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.





NO SCALE

D02-15_New Bern Splice Details

Division 2 Craven County New Bern

PLAN DATE: April 2025 REVIEWED BY: BN Groome

PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)

REVISIONS INIT. DATE

FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

SEAL

052936

SIGNER

Signed by:

Brittary N Groome

4/24/2025


1E09340E1094484...

DATE

DOCUMENT NOT CONSIDERED

4/23/2025 ...*04-Design*SCP*SCP-15.c Hser: kiones

R - 4463A SCP - 16



ETHERNET SWITCH TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING PROPER TERMINATIONS.

NOTES:

- 1. NOTIFY THE DIVISION TRAFFIC ENGINEER AT (252)439–2829 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

1) SPLICE LOCATION


2) DATE

3) COMPANY NAME

4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.






NO SCALE

D02-15_New Bern Splice Details

Division 2 Craven County New Bern
PLAN DATE: April 2025 REVIEWED BY: BN Groome
PREPARED BY: DS Griffith DRMP PROJ. NO: 17359 (041)
REVISIONS INIT. DATE



1/23/2025 ...*04-Design*SCP*SCP-16. Iser: kiones