


TIP NO.		SHEET NO.
I-5880		SIGN-3B
<p>Signed by:</p> <div style="border: 1px solid black; padding: 2px; display: inline-block;">  </div> <p>8A8DDC5-32D44421...</p>		
11/2025   10:44:22 AM EDT		
		
<b>DOCUMENT NOT CONSIDERED FINAL USS ALL SIGNATURES COMPLETED</b>		

**JURIMENT NOT CONSIDERED FINAL  
TILL ALL SIGNATURES COMPLETED**



## NOTES:

1. IF THE CONTRACTOR BIDS ALUMINUM SIGN STRUCTURE, EACH SHALL BE PROVIDED WITH AN APPROVED HIGHWAY TRUSS DAMPER DEVICE IN ACCORDANCE WITH AASHTO SPECIFICATIONS.
2. MOUNT SIGNS VERTICALLY CENTERED ON HORIZONTAL MEMBER OF STRUCTURE.
3. FIELD VERIFICATION SHALL BE REQUIRED FOR ALL FOOTING ELEVATIONS, PER THE LATEST NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES. PROVIDE FIELD VERIFICATION TO THE SIGNING SECTION.
4. THE TOP OF THE FOOTING SHALL EXTEND AT LEAST 4 INCHES AND NOT MORE THAN 24 INCHES ABOVE THE HIGHEST POINT OF THE GROUND SURFACE AT THE FOOTING.
5. SIGN HANGERS AND ATTACHMENT HARDWARE SHALL BE PROVIDED AND INSTALLED ON THE ASSEMBLY TO ACCOMMODATE ALL SIGNS SHOWN IN THIS PLAN SHEET.
6. DESIGN AND CONSTRUCTION REQUIREMENTS FOR SIGN STRUCTURES SHALL ACCOMMODATE WIND VELOCITY OF 110 M.P.H.

LOCATION: 36.059251, -80.217844

**JM&T** *Johnson, Mirmiran, & Thompson Inc.*  
4700 Falls of Neuse Rd, Suite 100,  
Raleigh, NC, 27603  
License No: C-3097

**OVERHEAD SIGN ASSEMBLY 'C'**  
**- L - 45+39.32**  
**I-40 EB**