Docusign Envelope ID: 48B0556E-0A89-4F2F-B18B-ADD4B9A12A90

TIP NO.	SHEET NO.
I-5880	SIGN-4E

APPROVED: Signed by: BA5DDCF32D4842F...

DATE: 7/11/2025 | 10:44:22 AM EDT

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 046062 ENGINEER CHARLES J. YOUNG

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

401 QUANTITY REQ'D 4

30" X 30"
W3-2

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 8

24" X 12"
W16-7P

MOUNT BELOW SIGN 403 IN 8 INSTALLATIONS

403 QUANTITY REQ'D 8

36" X 36"
W11-2

ONE "U" POST PER SIGN

404 QUANTITY REQ'D 2

W4-1R
48" X 48"

TWO "U" POST PER SIGN

405 QUANTITY REQ'D 4

R2-1
24" X 30"

ONE "U" POST PER SIGN

406 QUANTITY REQ'D 6

R6-1 R
36" X 12"

TWO "U" POST PER SIGN

407 QUANTITY REQ'D 6



36" X 36" X 36"
R1-2

ONE "U" POST PER SIGN

408 QUANTITY REQ'D 2

R6-1 L
36" X 12"

MOUNT BACK TO BACK WITH SIGN 406 IN 2 INSTALLATIONS

409 QUANTITY REQ'D 4

R5-1 A
36" X 24"

ONE "U" POST PER SIGN

410 QUANTITY REQ'D 6

24" X 30"
R4-7

ONE "U" POST PER SIGN

NOTE: SIGN R4-7 WILL BE INSTALLED AT A MINIMUM OF 10 FT FROM THE NOSE OF AN ISLAND.

411 QUANTITY REQ'D 1



W3-3
30" X 30"

ONE "U" POST PER SIGN

412 QUANTITY REQ'D 4

W2-6
30" X 30"

ONE "U" POST PER SIGN

413 QUANTITY REQ'D 1

W9-1 R
36" X 36"

ONE "U" POST PER SIGN

414 QUANTITY REQ'D 1

W16-2P
24" X 18"

MOUNT BELOW SIGN 413 IN 1 INSTALLATIONS

415 QUANTITY REQ'D 4

W13-1
24" X 24"

MOUNT BELOW SIGN 412 IN 4 INSTALLATIONS

416 QUANTITY REQ'D 4

R5-1
30" X 30"

ONE "U" POST PER SIGN

417 QUANTITY REQ'D 1

R3-7 R
30" X 30"

ONE "U" POST PER SIGN

418 QUANTITY REQ'D 1

W4-2R
36" X 36"

ONE "U" POST PER SIGN

Johnson, Mirmiran, & Thompson Inc.
4700 Falls of Neuse Rd, Suite 100,
Raleigh, NC, 27603
License No: C-3097

TYPE "E" SIGNS

7/11/2025 7:57:18 AM
...\I5880_SIGN_4E.dgn
User:dTreade