



SEE SHEET SCP-6

NOTES:

1. NOTIFY THE NCDOT REGIONAL ITS ENGINEER AT 336-554-9700 AND THE W-S SIGNAL SYSTEM MANAGER AT 336-747-6867 AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM AND ITS DEVICES ARE BACK UP AND OPERATIONAL. EXISTING FIBER MUST REMAIN IN OPERATION THROUGHOUT INSTALLATION OF PROPOSED FIBER. SPlicing CUT OVER FROM EXISTING TO PROPOSED FIBER MUST OCCUR WITHIN A DAY'S WORK TO ENSURE NO DEVICE IS OFFLINE MORE THAN 24 HOURS. SEE ICT'S.
2. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
3. CONTRACTOR TO INSTALL CONDUIT AND FIBER AS CLOSE TO BACK EDGE OF MAINTAINED RIGHT-OF-WAY AS POSSIBLE WITHOUT IMPACTING NOISE WALL.
4. CONTRACTOR MAINTAIN A MINIMUM DEPTH OF 15' TO AVOID IMPACT WITH FUTURE RAMP CONSTRUCTION AND DECONSTRUCTION ACTIVITIES.
5. REMOVE AND DISPOSE OF EXISTING JUNCTION BOXES AND FIBER OPTIC CABLE. CUT CONDUITS AT 30" BELOW GRADE AND ABANDON. FILL VOIDS AFTER REMOVALS WITH APPROVED MATERIALS.



NC License #C-4445  
304-F W. Millbrook Rd  
Raleigh, NC 27609  
984.500.5426  
www.exultengineering.com

TMP Phase 1

 250 N. Greenfield Pkwy., Garner, NC 27529	Prepared for: <b>Winston-Salem Signal System Communications Cable and Conduit Routing</b>		 DocuSigned by: <b>Kelly Nicholas</b> 05/06/2025
	Division 9 Forsyth County Winston-Salem		
	PLAN DATE: May 2025	EXULT PROJ. NO: 15021	
	PREPARED BY: JA Wendt	REVIEWED BY: KV Nicholas	
	REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED